# HITACH

KAOHSIUNG HITACHI **ELECTRONICS CO..LTD** P.O. BOX 26-27 2,13TH EAST ST. K.E.P.Z. KAOHSIUNG TAIWAN R.O.C. TEL:(07) 8215811 (7 LINE) FAX:(07) 821-5815

FOR MESSRS:

# HID, LTD S.P.Z. R.O.C. DATE: Jun. 17,2004 'G' CUSTOMER'S ACCEPTANCE SPECIFICATIONS TX09D50VM1CCA CONTENTS

No.	ITEM	SHEET No.	PAGE
1	COVER	7B64PS 2701-TX09D50VM1CCA-1	1-1/1
2	RECORD OF REVISION	7B64PS 2702-TX09D50VM1CCA-1	2-1/1
3	GENERAL DATA	7B64PS 2703-TX09D50VM1CCA-1	3-1/1
4	ABSOLUTE MAXIMUM RATINGS	7B64PS 2704-TX09D50VM1CCA-1	4-1/2~2/2
5	ELECTRICAL CHARACTERISTICS	7B64PS 2705-TX09D50VM1CCA-1	5-1/2~2/2
6	OPTICAL CHARACTERISTICS	7B64PS 2706-TX09D50VM1CCA-1	6-1/2~2/2
7	BLOCK DIAGRAM	7B64PS 2707-TX09D50VM1CCA-1	7-1/1
8	INTERFACE TIMING CHART	7B64PS 2708-TX09D50VM1CCA-1	8-1/5~5/5
9	DIMENSIONAL OUTLINE	7B63PS 2709-TX09D50VM1CCA-1	9-1/1
10	APPEARANCE STANDARD	7B64PS 2710-TX09D50VM1CCA-1	10-1/4~4/4
11	PRECAUTION IN DESIGN	7B64PS 2711-TX09D50VM1CCA-1	11-1/3~3/3
12	DESIGNATION OF LOT MARK	7B64PS 2712-TX09D50VM1CCA-1	12-1/1
13	PRECAUTION FOR USE	7B64PS 2713-TX09D50VM1CCA-1	13-1/1

\*When product will be discontinued, customer will be informed by HITACHI with twelve months prior announcement. ACCEPTED BY;

PROPOSED BY; Dan Change

KAOHSIUNG HITACHI	Sh	7B64PS 2701-TX09D50VM1CCA-1	PAGE	1 1/1
ELECTRONICS CO.,LTD.	No.	7B04F3 270T-TX09B30VWTCCA-T	PAGE	1-1/1

# RECORD OF REVISION

DATE	SHEET No.	SUMMARY
-		

KAOHSIUNG HITACHI ELECTRONICS CO.,LTD.

DATE Jun.17,'04

Sh.

7B64PS 2702-TX09D50VM1CCA-1 PAGE | 2-1/1

# 3.GENERAL DATA

(1) Part Name TX09D50VM1CCA

(2) Module Dimensions 64.0(W)mm x 86.0(H)mm x (8.05)

(3) Effective Display Area 53.64(W)mm x 71.52(H)mm (Diagonal:9cm)

(4) Dot Pitch 0.0745mm x 3(R,G,B)(W) x 0.2235(H)mm

(5) Resolution 240 x 3(R,G,B)(W) x 320 (H) dots

(6) Color Pixel Arrangement R,G,B Vertical stripe

(7) LCD Type Transmissive Color TFT LCD (Normally White)

(8) Display Type Active Matrix

(9) Number of Colors 262<sup>K</sup> Colors (R,G,B 6 Bit Parallel)

(10) Backlight Light Emitting Diode (LED) x 6

(11) Weight (T.B.D) typ.

(12) Interface 40 pin C-MOS

# 4. ABSOLUTE MAXIMUM RATINGS

#### 4.1 ELECTRICAL ABSOLUTE MAXIMUM RATINGS OF LCD

VSS=0V


	ITEM	SYMBOL	MIN.	MAX.	UNIT	COMMENT
Power Supply for Logic		VDD	-0.3	4.0	V	
Inpu	t Voltage	VI	-0.2	VDD+0.2		(Note 1)
Inpu	t Current	li	0	1	Α	
Static Electricity		VESD0	-	±100	V	(Note 2,3)
		VESD1	<u></u>	(8)	kV	(Note 2,4)
	Forward Carrent	IF I	-	30	mA	(Note 5)
LED	Pulse Forward Carrent	IFP	-	100	mA	(Note 6)
	Reverse Voltage	VR		5	V	

Note 1: DTMG, DCLK, RD0~RD5, GD0~GD5, BD0~BD5.


Note 2 : 200pF-0  $\Omega$  25 $^{\circ}$ C -70 $^{\circ}$ RH Note 3 : Interface Pin Connector.

Note 4: The surface of metal bezel and LCD panel.

Note 5:



Note 6: IFP Conditions: pulse width≤10ms and Duty≤5%



# 4.2 ELECTRICAL ABSOLUTE MAXIMUM RATINGS OF TOUCH PANEL

ITEM	SPECIFICATION	UNIT	CONDITION	REMARKS
Supply Voltage	7.0	V	DC	
Endurance Voltage	25	V	DC	(Note 1)

Note 1: Waiting 1 minute.

## 4.3 ENVIRONMENTAL ABSOLUTE MAXIMUM RATINGS

ITCM	OPERATING		ST	ORAGE	REMARKS	
ITEM	Min.	Max.	Min.	Max.	KLIVIARRO	
Ambient Temperature	-10°C	50℃	-20°C	60℃	(Note 1)	
Humidity		ote 2)			Without condensation	
Vibration	-	(2.45)m/s <sup>2</sup> (0.25G)	-	(11.76)m/s <sup>2</sup> (1.2G)	(Note 4, 5)	
Shock		(29.4)m/s <sup>2</sup> (3G)	<u>.</u>	(490)m/s <sup>2</sup> (50G)	(Note 4 , 6)	
Corrosive Gas	Not A	cceptable	Not A	cceptable		

- Note 1: Background color changes slightly depending on ambient temperature.

  This phenomenon is reversible.
- Note 2 :  $Ta \le 40^{\circ}C$  : 85%RH max.
  - Ta>40°C : Absolute humidity must be lower than the humidity of 85%RH at 40°C.
- Note 3: Please attach not to add the stress by temperature change and mechanical stress to LCM.
- Note 4: It should be fixed and assembled into the customer's application when test. And the test condition should be followed HITACHI test method. After finished testing, the module should be normal operating. But it is for reference only.
- Note 5:15Hz  $\sim 100$ Hz (except resonance frequency)
- Note 6:  $\pm X$ ,  $\pm Y$ ,  $\pm Z$ , 10ms.

# 5. ELECTRICAL CHARACTERISTICS

# 5.1 ELECTRICAL CHARACTERISTICS OF LCD

Ta=25°C, VSS=0V

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT
Power Supply Voltage	VDD	-	3.0	3.3	3.6	V
Input voltage for logic		"H" level	1.7	-	VDD	V
(note 1)	VI	"L" level VSS -		0.7	· · · · · · · · · · · · · · · · · · ·	
Power Supply Current (note 2)	IDD	VDD-VSS=3.3V	-	(T.B.D)	-	mA
Vsync Frequency	fV	.=	_	60	-	Hz
Hsync Frequency	fH	_	_	(19.5)	-	kHz
DCLK Frequency	fCLK	_	_	(5.33)	-	MHz

Note 1: DTMG, DCLK, RD0~RD5, GD0~GD5, BD0~BD5.

Note 2: fV=60Hzm, Ta=25°C, Pattern used as display pattern: All Black.

Note 3: Need to made sure of flickering and rippling of display when setting the frame frequency in your set.

5.2 ELECTRICAL CHARACTERISTICS OF BACK LIGHT

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT	REMARKS
LED Input Voltage	VF	IF=20mA	ı	3.6	4.0	٧	LED / Part
LED Forward Current	IF	-	8	20	25	mA	LED / Part
LED Reverse Current	IR	VR=5V	_	_	50	μΑ	LED / Part

KAOHSIUNG HITACHI DATE Jun.17,'04 Sh. 7B64PS 2705-TX09D50VM1CCA-1 PAGE 5	 			
ELECTRONICS CO.,LTD.   No.   No.	DATE	Jun.17,'04 Sh.	7B64PS 2705-TX09D50VM1CCA-1 PAGE	5-1/2


# 5.3 ELECTRICAL CHARACTERISTICS OF TOUCH PANEL

ITEM	-	SPECIFICATION	UNIT
	xR - xL	200 - 650	ohm
Resistance between Terminal	yU - yL.	250 - 500	ohm
Insulance Resistance (Note 1)	x - y	10M min.	ohm
	Х	1.5 max.	%
Linearity (Note 2,3)	У	1.5 max.	%
Chattering		10 max.	ms

Note 1: Operating Voltage 25V DC.


Note 2: Test Condition.

(a) Y axis linearity testing method (with tip radius 0.8, polaycetal pen). VxL-xR=5V , VOUT=VyU.



(b) X axis linearity method VyU-yL=5V , VOUT=VxL.

Note 3 : Calculation
(a) Y axis linearity



# 5.4 MECHANICAL CHARACTERISTICS OF TOUCH PANEL

ITEM	SPECIFICATION	UNIT	REMARKS
Pen Input Pressure	0.1 - 1.3	N	R0.8mm Polyacetal pen (Note 4)
Surface Hardness	3H min.	-	JIS K 5400

KAOHSIUNG HITACHI ELECTRONICS CO.,LTD	DATE	Jun.17,'04	Sh. No.	7B64PS 2705-TX09D50VM1CCA-1	PAGE	5-2/2
--	------	------------	------------	-----------------------------	------	-------

# 6. OPTICAL CHARACTERISTICS

# 6.1 OPTICAL CHARACTERISTICS OF LCD (BACKLIGHT ON, ON TOUCH PANEL)

Ta=25°C

ITEM		SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT	NOTE	
Brightness		В	$\phi = 0^{\circ} \theta = 0^{\circ}$	ı	(100)	-	cd/m <sup>2</sup>	(1,3)	
Uniformity		-	$\phi = 0^{\circ} \theta = 0^{\circ}$	(70)	-	•	%	(2,3)	
Viewing Angle		10 11	θ=0°, K≧2.0	-	(130)	1	deg	(4.5)	
Viewing Angle		<i>φ</i> 2- <i>φ</i> 1	<i>θ</i> =90°, K≧2.0	ı	(120)	-	ueg	(4,5)	
Contrast Ratio		К	$\phi = 0^{\circ} \theta = 0^{\circ}$	(180)	(300)	ı	_	(3)	
Response Time (rise-fall)		tr+tf	$\phi = 0^{\circ} \theta = 0^{\circ}$	-	(35)	70	ms	(7)	
Color Tone	Red	х			(0.60)	-	<b>-</b>		
(Primary Color)	Reu	у			(0.34)	-	-		
	Groon	×		-	(0.33)	-	-		
	Green	у	$\phi = 0^{\circ}  \theta = 0^{\circ}$	-	(0.55)	1	-	(3)	
	Blue	X			(0.14)		-		
	Diue	у		-	(0.13)	-	-		
	White	х		•	(0.32)	_	_		
	vville	у		-	(0.34)	-	_		


(Measurement condition: HITACHI standard)

Note 3: Measurement Condition

(Note 4~7): See page 6-2/2


Note 1 : Driving Condition

Display Pattern: White Raster LED Current: 20mA / Part Measurement of the following 9 places on the display.




Note 2: Definition of the brightness tolerance

(Min. brightness August 100 Max. brightness



KAOHSIUNG HITACHI		Jun.17,'04	Sh.	7B64PS 2706-TX09D50VM1CCA-1	PAGE	6-1/2
ELECTRONICS CO.,LTD.	DATE		No.	7B04F3 2700-1A09D30VW1CCA-1	I AGL	0-1/2


Note 4 : Definition of  $\theta$  and  $\phi$  (Normal)




Note 6: Definition of contrast "K"

K= White Brightness
Black Brightness


Note 5: Definition of Viewing angle \$\phi\$1 and \$\phi\$2




Contrast ratio "K" vs Viewing angle "  $\phi$ "




Note 7: Definition Optical Response Time





KAOHSIUNG	HI	TACHI
<b>ELECTRONIC</b>	S	CO.,LTD.

# 7.BLOCK DIAGRAM



KAOHSIUNG HITACHI		Sh. Jun.17,'04	7B64PS 2707-TX09D50VM1CCA-1	DVCE	7_1/1
ELECTRONICS CO.,LTD.	DATE	No.	7604FS 2707-1X09D30VW1CCA-1	IAOL	7-1/1


# 8. INTERFACE TIMING

# 8.1 INTERFACE TIMING


	MIN.	TYP.	MAX.	UNIT	SYMBOL
Vertical Total	-	(327)	-	Line	T0
Vertical Sync Width	1	1	_	Line	T1
Vertical Sync Start	-	(322)	-	Line	T2
Vertical Sync End	-	(323)	-	Line	Т3
Vertical Blank Time	5	(7)	-	Line	T4
Vertical Display End	-	(320)	_	Line	T5
Horizontal Total	<u>-</u>	(273)	_	Pixel Clock	T6
Horizontal Sync Width	-	(5)	-	Pixel Clock	T7
Horizontal Sync Start	-	(251)	-	Pixel Clock	T8
Horizontal Sync End	-	(256)	-	Pixel Clock	Т9
Horizontal Blank Time	-	(33)	_	Pixel Clock	T10
Horizontal Display End	_	(240)	_	Pixel Clock	T11

Note: Vertical total should be set to odd.

KAOHSIUNG HITACHI		Sh.	7D04D0 0700 TV00D50V444004 4 D4 05 0 4/5	$\dashv$
ELECTRONICS CO.,LTD.	DATE	Jun.17,'04 No.	7B64PS 2708-TX09D50VM1CCA-1 PAGE 8-1/5	



# 8.3 POWER ON/OFF SEQUEUCE



# 8.4 RELATIONSHIP BETWEEN DISPLAYED COLOR AND INPUT DATA

	COLOR & GRAY	GRAY SCALE								DA	TA S	SIGN	IAL							
	SCALE	LEVELS	R0	R1	R2	R3	R4	R5	G0	G1	G2	G3	G4	G5	В0	В1	B2	ВЗ	В4	B5
	Black	-	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
ļ	Blue	-	0	0	0	0	0	0	0	0	0	0	0	0_	1	1	1	1	1	1
1	Green	-	0	0	0	0	0	0	1	1	1	1_	1	1	0	0	0	0	0	0
Basic	Cyan		0	0	0	0	0	0	1	1	1	1	1	1	1	1_	1	1	1	1
Color	Red		1	1	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0
	Magenta	-	1	1	1_	1	1	1	0	0	0	0	0	0	1	1_	1	1	1	1
	Yellow	-	1	1	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0
	White	-	1	1_	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	Black	GS0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	<b>↑</b>	GS1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	Darker	Darker GS2				0	0	0	0	0	0	0	0	0	0	0	0	0	0_	0
Red	1 1	<u> </u>		<b>↓</b>																
INCO	į.	<u> </u>				<u> </u>						Ų.						<u>,                                      </u>	r—	
	Brighter	GS61	1	0	1	1	1	1	0	0	0	0	0	0	0	0	0	0_	0	0
	<u> </u>	GS62	0	1	1	1_	1	1	0	0	0	0	0	0	0	0	0	0	0	0
	Red	GS63_	1	1	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0_	0
	Black	GS0	0	0	0_	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	<b>1</b> 1	GS1	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0
	Darker	GS2	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0
Green	<b>1</b>					<u> </u>			<b>↓</b>								<u> </u>			
Green		<u> </u>				<u> </u>						<u> </u>					1	<u> </u>	r	
	Brighter	GS61_	0	0	0	0	0	0	1	0	1	1	1_	1	0	0	0	0	0	0
	<b>↓</b>	GS62	0	0	0	0	0	0	0	1	1	1	1_	1	0	0	0	0	0	0
	Green	GS63	0	0	0	0	0	0	1	1	1	1	1	1	0	0	0	0	0	0
	Black	GS0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	<b>↑</b>	GS1	0	0	0	0	0	0	0	0	0	0	0	0	1_	0	0	0	0	0
	Darker	GS2	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0
Blue	<b>1</b>	↓				<u> </u>						<u> </u>						<u> </u>		
Dide	↓	↓				<u> </u>	,				<del>, -</del> · · · ·	<u> </u>					ı	<del> </del>		T .
	Brighter	G\$61	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	1	1	1
	↓	GS62	0	0	0	0	0	0	0	0	0	0_	0	0	0	1	1	1_	1	1
	Blue	GS63	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	1	1


KAOHSIUNG HITACHI	DATE	Jun.17,'04	Sh.	7B64PS 2708-TX09D50VM1CCA-1 PA	\GE	8-4/5
ELECTRONICS CO.,LTD.	אלוב	Juli. 17, 04	No.	750-1 0 2700 1X00500 W1100X 11.7		


8.5 INTERNAL PIN CONNECTION CN1 JAE: FA5S040HF1(Suitable FPC: t0.3±0.03mm , 0.5±0.03mm pitch)


PIN No.	SIGNAL	FUNCTION
1	VDD	Power Supply for Logic
2	VDD	Power Supply for Logic
3	VDD	Power Supply for Logic
4	DCLK	Dot Clock
5	VSS	GND
6	HSYNC	Horizontal Sync Pulse
7	VSS	GND
8	DTMG	Timing Signal for Data
9	VSS	GND
10	NC	No Connection
11	VSS	GND
12	R5	
13	R4	Red Data
14	R3	
15	VSS	GND
16	R2	
17	R1	Red Data
18	R0	
19	VSS	GND
20	G5	
21	G4	Green Data
22	G3	
23	VSS	GND
24	G2	
25	G1	Green Data
26	G0	
27	VSS	GND
28	B5	
29	B4	Blue Data
30	B3	
31	VSS	GND
32	B2	
33	B1	Blue Data
34	B0	
35	PCI	Power Control In
36	VSS	GND
37	XR	Touch Panel Right Side
38	YL	Touch Panel Lower Side
39	XL	Touch Panel Left Side
40	YU	Touch Panel Upper Side


KAOHSIUNG HITACHI		1 47 10 A	Sh.	7B64PS 2708-TX09D50VM1CCA-1	DACE	8-5/5
ELECTRONICS CO.,LTD.	DATE	Jun.17,'04	No.	7864PS 2708-1X09D50VM1CCA-1	PAGE	0-0/0


# 9. DIMENSIONAL OUTLINE














Detail A

Scale: NTS Unit: mm

PAGE 9-1/1


KAOHSIUNG HITACHI	DATE	lup 17 '04	Sh.	7B63PS 2709-TX09D50VM1CCA-1
ELECTRONICS CO.,LTD.	DATE	Jun. 17, 04	No.	1 B03F3 2109-1 X09D30 VIVITCCA-1

## 10. APPEARANCE STANDARD


# 10.1 APPEARANCE INSPECTION CONDITION

Visual inspection should be done under the following condition.

- (1) The inspection should be done in a dark room.(More than 1000(lx) and non-directive)
- (2) The distance between eyes of an inspector and the LCD module is 30cm.
- (3) The viewing zone is shown the figure. Viewing angle ≤25°



#### 10.2 DEFINITION OF ZONE



KAOHSIUNG HITACHI ELECTRONICS CO.,LTD.	DATE	Jun 17 '04	Sh. No.	7B64PS 2710-TX09D50VM1CCA-1	PAGE	10-1/4	

# 10.3 APPEARANCE SPECIFICATION

(1)LCD Appearance

\*) If the problem related to this section occurs about this item, the responsible persons of both party (Customer and HITACHI) will discuss the matter in detail.

No.	ITEM	CRITERIA							
	Scratches	Length L(mm) L≦2.0	Widt W(mr		Maximum number acceptable ignored	A,B			
		L≦2.0 L>2.0	0.03 <w≦0. 0.05<w< td=""><td>4 none</td><td></td></w<></w≦0. 		4 none				
	Dent	Distinguished of (To be judged b				А			
	Wrinkles in Polarizer	Same as abov				A			
	Bubbles	· ·	diameter nm)	ľ	Maximum number acceptable	- A			
	}	D≦	0.3		2	<b>」 ^  </b>			
		0.3	< <u>D</u>	_	none	<u> </u>			
	Stains		Filamentou			_			
	Foreign	Length	Widt		Maximum number				
	Materials	L(mm)	W(mr		acceptable	- A,B			
1		L<2.0	W≦0. 0.05 <w< td=""><td></td><td>2</td><td>_</td></w<>		2	_			
	Dark spot	L≦1.0							
L			"- "-	und(Dot_shape) nm)					
		Average dia	meter D(mm)						
С			<b>≦</b> 0.15		acceptable 6				
D		0.15 <d< td=""><td></td><td colspan="2">4</td><td>A,B</td></d<>		4		A,B			
		0.2<			-				
		The total		Fila	7				
	Color Tone		hose wiped out easily are acceptable o be judged by HITACHI STANDARD						
	Color Uniformity	Same as above				Α			
	Dot Defect				Maximum number				
				4 4-4	acceptable	-			
		Sparkle mod	le	1 dot	2(sets)				
			L	2 dots Total	2(Sets) 4				
		Plack mode		1 dot	4	А,В			
		Black mode	Ī	2 dots	2(sets)	-			
			<u> </u>	Total	4				
		Sparkle mod		2 dots	2(sets)				
		a Diagramio	···	Total	6				

KAOHSIUNG HITACHI		Jun.17,'04	Sh.	7B64PS 2710-TX09D50VM1CCA-1 PAGE 10-2/4
ELECTRONICS CO.,LTD.	DATE	Juli. 17, 04	No.	7504 C 27 C 1700200 W. CO. C.

# (2)Touch panel appearance

Visual inspection should be done under the following condition.

- \*) The inspection should be done in a dark room. (more than 500 (lx) and non-directive)
- \*) The distance between eyes of an inspector and the LCD module is 30 cm.
- \*) The viewing angle ≤ 60°.


No.	ITEM		CRITE	ERIA		APPLIED ZONE	
	Scratches	Length L(mm)	Width W(mm		Maximum number acceptable		
				0.05	ignored	] A,B	
		10 <l< td=""><td>0.05≦W&lt;</td><td>(0.1</td><td>none</td><td></td></l<>	0.05≦W<	(0.1	none		
		**	0.1≦W	1	none		
	Foreign		Filamentous	(Line sh	nape)	_	
T 0	Materials	Length L(mm)	Width W(mm		Maximum number acceptable		
U	Dark Spot	_	W<0.05		Ignored	A,B	
C		L>3	0.05≦W≦	<u>≨0.1</u>	none		
Н		-	W≧0.1		Round		
P			e)				
A N		Average diame	eter D(mm)	M	A,B		
E		D≦0.:	25		ignored		
L		0.25 <d≦< td=""><td>≦0.35</td><td></td><td>6</td><td>В</td></d≦<>	≦0.35		6	В	
		0.35<	D		none	A,B	
	Newton Ring (Touch Panel)	To be judged by H	To be judged by HITACHI standard				
	Touch Panel Uncleanness	No conspicuous d	irt			Α	
	Rubbing Scratch	To be judged by h	To be judged by HITACHI standard				

# (3) Glass indentation


ITEM	SPECIFICATIONS							
Common Indentation	X	X     Y     Z       ≤5.0     ≤3.0     ≤t						
Corner Broken	Z	X     Y     Z       ≤3.0     ≤3.0     ≤t						
Proceeding Crack		None						

KACHCHING HITACHI			Sh			
KAOHSIUNG HITACHI	DATE	Jun.17,'04	SII.	7B64PS 2710-TX09D50VM1CCA-1	PAGE	10-3/4
ELECTRONICS CO.,LTD.		oun. IT, or	No.			

Note 1: Definition of average diameter (D)




Note 2: Definition of length (L) and width (W)



Note 3: Definition of dot defect

- (a) Dot Defect : Defect Area > 1/2 dot
- (b) Sparkle mode: Brightness of dot is more than 30% at Black raster.
- (c) Black mode: Brightness of dot is less than 70% at R.G.B raster.
- (d) 1 dot: Defect dot is isolated, not attached to other defect dot.
- (e) N dot: N defect dots are consecutive (fig.1).

  (N means the number of defect dots.)



2 dots defect included defect dot "X" is defined as follows.

Adjacent dots to defect dot "X":


- (f) Counting definition of adjacent dots(1 sets): same as 1 dot defect.
- (g) Those wiped out easily are acceptable

KAOHSIUNG HITACHI	DATE	Jun.17,'04		7B64PS 2710-TX09D50VM1CCA-1	PAGE	10-4/4
ELECTRONICS CO.,LTD.	· · · · · ·	, N	No.			

#### 11. PRECAUTION IN DESIGN

#### 11.1 MOUNTING PRECAUTION

(1) When assembling the Touch Panel and you case, please refer to the figure below.



- (2) The clearance between the Touch Panel and case shall be designed so that the case edge never presses the input screen when it is deformed by heat or other causes.
- (3) The case shall be designed not to touch the tail portion (FPC for Touch Panel).
- (4) The boundary space between the effective area and the insulated area is unstable. Touching this area may effect the operation of the Touch Panel.

  The case must be designed so that it does not touch the boundary space.

# 11.2 PRECAUTIONS AGAINST ELECTROSTATIC DISCHARGE

As this module contains C-MOS LSIs, it is not strong against electrostatic discharge. Make certain that the operator's body is connected to the ground through a list band, etc.

And don't touch I/F pins directly.

#### 11.3 HANDLING PRECAUTIONS

(1) Since the Touch Panel on the top, and the frame on the bottom tend to be easily damaged, they should be with full care so as not to get them touched, pushed or rubbed by a piece on glass, tweezers and anything else which are harder a pencil lead 3H.

KAOHSIUNG	HITACHI ICS COLTD.	DATE	Jun.17,'04	Sh. No.	7B64PS 2711-TX09D50VM1CCA-1	PAGE	11-1/3

(2) As the adhesives used for adhering upper/lower polarizer's and frame are made of organic substances which will be deteriorated by a chemical reaction with such chemicals as acetone, toluene, ethanol and isopropyl alcohol. The following are recommended for use:

normal hexane

Please contact with us when it is necessary for you to use chemicals other than the above.

(3) Lightly wipe to clean the dirty surface with absorbent cotton or other soft material like chamois, soaked in the recommended chemicals without scrubbing it hardly.

Always wipe the surface horizontally or vertically. Never give a wipe in a circle.

To prevent the display surface from damage and keep the appearance in good state, it is sufficient, in general, to wipe it with absorbent cotton.

- (4) Immediately wipe off saliva or water drop attached on the display area because it may cause deformation or faded color.
- (5) Fogy dew deposited on the surface may cause a damage, stain or dirt to the polarizer. When you need to take out the LCD module from some place at low temperature for test, etc.

It is required to be warmed them up to temperature higher than room temperature before taking them out.

- (6) Touching the display area or I/F pins with bare hands or contaminating them are prohibited, because the stain on the display area and poor insulation between terminals are often caused by being touched with bare hands.

  (Some cosmetics are detrimental to polarizer's.)
- (7) In general, the glass is fragile so that, especially on its periphery, tends to be cracked or chipped in handling. Please not give the LCD module sharp shocks by falling, etc.
- (8) Maximum pressure to the surface must be less than 1.96×10<sup>4</sup> Pa.

  And if the pressure area is less than 1cm<sup>2</sup>, maximum pressure must be less than 1.96N.
- (9) Since the metal width is narrow on these locations (see page 9-1/1), please careful with handling.
- (10) Top sheets shall be cleaned gently using a soft cloth such as those used for glasses. Hard wiping accumulated dust will leave scars on the surface even using a cloth.

#### 11.4 OPERATION PRECAUTION

(1) Using a LCM module beyond its maximum ratings may result in its permanent destruction.

LCM module's should usually be used under recommended operating conditions shown in chapter 4. Exceeding any of these conditions may adversely affect its reliability.

KAOHSIUNG HITACHI	DATE	Jun.17,'04	7B64PS 2711-TX09D50VM1CCA-1	PAGE	11-2/3	
ELECTRONICS CO.,LTD.	אלוב	No.	, Boar o Zi i i ixooboo iii o o i i i			l

- (2) Response time will be extremely delayed at lower temperature than the specified operating temperature range and on the other hand LCD's shows dark blue at higher temperature.

  However those phenomena do not main defects of the LCD module. Those phenomena will disappear in the specified operating temperature range.
- (3) If the display area is pushed hard during operation, some display patterns will be abnormally display.
- (4) A slight dew depositing on terminals may cause electrochemical reaction which leads to terminal open circuit. Please operate the LCD module under the relative condition of 40°C 85%RH.
- (5) Resistance range: Your controller shall be set up to allow the resistance range of Touch Panel specified in our CAS.
- (6) Pointed position of Touch Panel may shift owing to a change in resistance of Touch Panel depending on the operation condition. To compensate this shift, the set shall be given a calibration function.
- (7) Input shall be made with a stylus pen (polyacetal, R0.8). Chances are very high that use of a metal piece including a ball point pen or sharp edge will impair accuracy.
- (8) The Touch Panel is an auxiliary input device. The system shall be designed to have other input device.

#### 11.5 STORAGE

In case of storing LCD module for a long period of time (for instance, for years) for the purpose of replacement use, the following precautions necessary.

- (1) Store the LCD modules in a dark place; do not expose them to sunlight or ultraviolet rays.
- (2) Keep the temperature between -20°C and 60°C at normal humidity.
- (3) Store the LCD modules in the container which is used for shipping from us.
- (4) No articles shall be left on the surface over an extended period of time.

#### 11.6 SAFETY


Wear finger cots or gloves whenever handling or assembling a Touch Panel its glass edges are sharp.


KAOHSIUNG HITACHI		1 47 10 4	Sh.	700 400 0744 TV00050VA400A 4	DACE	44 2/2
ELECTRONICS CO.,LTD.	DATE	Jun.17,'04	No.	7B64PS 2711-TX09D50VM1CCA-1	PAGE	11-3/3

# 12.DESIGNATION OF LOT MARK

#### 12.1 LOT MARK

Lot mark is consisted of 4 light for production lot 6 or 7 digits for production control..







Year	Mark
2004	4
2005	5
2006	6
2007	7
2008	8

Month	Jan.	Feb.	Mar.	Apr.	May	Jun.
Mark	01	02	03	04	05	06
Month	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
Mark	07	08	09	10	11	12

Week (Day In Calendar)	Figure In Lot Mark
01~07	1
08~14	2
15~21	3
22~28	4
29~31	5

12.2 Location of Label: On the FPC





			_			
KAOHSIUNG HITACHI ELECTRONICS CO.,LTD.	DATE	Jun.17,'04	Sh. No.	7B64PS 2712-TX09D50VM1CCA-1	PAGE	12-1/1

#### 13. PRECAUTION FOR USE

- (1) A limit sample should be provided by the both parities on an occasion when the both parties agree to its necessity.
  Judgement by a limit sample shall take effect after the limit sample has been established and confirmed by the both parties.
- (2) On the following occasions, the handling of the problem should be decided through discussion and agreement between responsible persons of the both parties.
  - 1) When a question is arisen in the specifications.
  - 2) When a new problem is arisen which is not specified in this specifications.
  - 3) When an inspection specifications change or operating condition change by customer is reported to HITACHI, and some problem is arisen in the specification due to the change.
  - 4) When a new problem is arisen at the customer's operating set for sample evaluation.
- (3) Regarding the treatment for maintenance and repairing, both parties will discuss it in six months later after latest delivery of this product.

The precaution that should be observed when handling LCM have been explained above.

If any points are unclear or if you have any requests, please contact with HITACHI.