

# T8301 Internet Protocol Telephone Phone-On-A-Chip™ IP Solution DSP

#### 1 Introduction

Lucent Technologies' *Phone-On-A-Chip* IP Solution is a highly integrated set of IC chips that form the basic building blocks for an internet protocol telephone (IPT), residing on a local area network (LAN).

The IPT presently consists of two ICs—the T8301 (IPT\_DSP) and the T8302 (IPT\_ARM\*).

The T8301 provides the audio processing engine for voice compression and decompression, speaker-phone echo cancellation, digital-to-analog and analog-to-digital converters, low-pass filters, and amplifiers to drive standard business telephone handsets and speakerphone hardware.

The general-purpose processor chip T8302 controls system I/O (Ethernet, USB, IrDA, etc.) and provides general telephone control features (LED control, keypad button scanning, LCD module interface, etc.).

A block diagram of the T8301 can be found in Figure 3 on page 8.

Since the DSP1627 is an integral part of the T8301, we will refer to the *DSP1627 Digital Signal Processor* Data Sheet throughout this discussion.

#### 1.1 Features

- DSP1627 core with bit manipulation unit.
- DSP clock speeds up to 80 MHz.
- Instruction ROM, 32K x 16 (zero wait-state at 80 MHz).

- Dual-port RAM, 6K x 16 (zero wait-state at 80 MHz).
- Internal SRAM, 16K x 16 (single wait-state at 80 MHz).
- 16-bit analog-to-digital converter.
- Programmable gain amplifier on audio input.
- Fixed gain differential microphone input.
- Analog input SRAM buffer, 512 x 16.
- Timed DMA for analog input SRAM.
- Two 16-bit digital-to-analog converters.
- Independent simultaneous speaker and handset outputs.
- Two integrated differential speaker driver outputs.
- Two analog output SRAM buffers, 512 x 16 each.
- Two timed DMA outputs for simultaneous handset and speaker audio output.
- Low-pass filtering on audio inputs and outputs.
- Serial I/O interface.
- General-purpose timer counter.
- Bit I/O interface.
- JTAG test and debugging control.
- Implementation in 0.35 µm, 5 V silicon technology.
- Packaged in 100-pin TQFP.

<sup>\*</sup> ARM is a registered trademark of Advanced RISC Machines Limited.

# **Table of Contents**

Contents	Page	Tables I	Page
1 Introduction	1	Table 1. Pin Description	4
1.1 Features		Table 2. SIO Interface Signals	
2 Pin Information		Table 3. DSP1627 INTON and INT1N	
2.1 T8301 100-Pin TQFP Pin Diagram		Table 4. T8301 Instruction/Coefficient	
2.2 Pinout Information		Memory Map	13
3 Overview		Table 5. T8301 Memory-Mapped Peripherals	
4 DSP1600 Core		Table 6. Data Memory Area: I/O,	
4.1 Bit Manipulation Unit (BMU)		Register, and Memory	15
4.2 Timer		Table 7. Programmable Gain Amplifier Maximum	
4.3 Clock PLL Control	9	Table 8. Tone Ringer Control Register (trc_reg)	
4.4 Bit Input/Output (BIO)		Table 9. Tone Ringer Amplitude	10
4.5 Serial Input/Output (SIO)		Control Encoding	10
4.6 Interrupts and Traps		Table 10. Tone Ringer Frequency Encoding	
4.7 Power Management		Table 11. aioc_reg Analog Audio I/O Control	
4.8 External Memory Interface (EMI)		Table 11. aloc_reg Analog Addio i/O Control Table 12. Audio Codec Clock	21
4.9 T8301 Memory Mapping		Control Register (aclkc_reg)	22
4.10 Y Space Memory Map		Table 13. Audio Clock Encoding	
5 Audio Input/Output Circuitry			
5.1 Analog Audio Input Channels		Table 14. DMA Control Register dmac_reg	24
5.2 Programmable Gain Amplifier (PGA)		Table 15. DMA Starting Address	24
5.3 Analog Audio Output Channels		Register setadr_reg	24
5.4 Tone Ringer		Table 16. DMA Transfer Count	2.4
5.5 Audio Codec Block		Register setcnt_reg	24
		Table 17. DMA Address Increment	0.5
5.6 Audio Codec Control Registers		Register adrinc_reg	25
6 DMA Input/Output Channels		Table 18. DMA Transfer Decrement Register	0.5
6.1 DMA Operation		cntdec_reg	
6.2 DMA Registers		Table 19. config_compander Register	
7 Hardware Compander		Table 20. write_linear Register	
8 Electrical Specifications		Table 21. write_companded Register	
8.1 Operating Range Specifications		Table 22. read_linear Register	
8.2 Analog and Codec Specifications		Table 23. read_companded Register	
8.3 Crystal Specification	29	Table 24. Operating Range Specifications	
9 JTAG and Hardware	00	Table 25. AINAN Specifications	
Development System (HDS)		Table 26. AINCP, AINCN Specifications	
9.1 TMODE Control for JCS/Boundary-Sca		Table 27. AOUTA Specifications	
Operation		Table 28. Speaker#1, Speaker#2 Specifications	
9.1.1 Mode 7 Operation (TMODE = 7) .		Table 29. Digital Low-Pass Filters Specifications	29
9.1.2 Mode 6 operation (TMODE = $6$ ).	30	Table 30. Digital-to-Analog Converter	
9.2 The Principle of Boundary-Scan		Specifications	29
Architecture	30	Table 31. Analog-to-Digital Converter	
9.2.1 Boundary-Scan		Specifications	
Instruction Register	32	Table 32. Boundary-Scan Pin Functions	
	_	Table 33. Debug Mode	
Figures	Page	Table 34. Boundary-Scan Instruction Register	
Figure 1. T8301 TQFP Pin Diagram	7 8 9 20 m27	Table 35. Boundary-Scan Register Description	33

### 2 Pin Information

### 2.1 T8301 100-Pin TQFP Pin Diagram




Figure 1. T8301 TQFP Pin Diagram

# 2 Pin Information (continued)

### 2.2 Pinout Information

In the following table, reference 1 refers to sections in the T8301 data sheet (this data sheet) and reference 2 refers to sections in the DSP1627 data sheet.

**Table 1. Pin Description** 

Pin#	Name	Description	Reference 1	Reference 2
1	Vdd	_	_	_
2	BIO0	BIT I/O 0	4.4	4.9
3	BIO1	BIT I/O 1	4.4	4.9
4	BIO2	BIT I/O 2	4.4	4.9
5	BIO3	BIT I/O 3	4.4	4.9
6	INT0N	DSP interrupt 0, active -low	4.6	4.3
7	INT1N	DSP interrupt 1, active -low	4.6	4.3
8	STOPN	Controls the internal processor clock, active -ow	_	4.13
9	DI1	Serial input/output unit (SIO) data in	4.5	4.7
10	Vss	_	_	_
11	VDD	_	_	_
12	DO1	Serial input/output unit (SIO) data out	4.5	4.7
13	SYNC	Serial input/output unit (SIO) sync	4.5	4.7
14	IOLD	Serial input/output unit (SIO) input load/output load	4.5	4.7
15	IOCK	Serial input/output unit (SIO) input clock/output clock	4.5	4.7
16	Vss	-	_	_
17	VDDPLL	OSC and PLL VDD	_	_
18	CKI1	XTL1 input/CMOS clock	4.3	4.12
19	CKI2	XTL2 input/CMOS clock	4.3	4.12
20	VssPLL	OSC and PLL Vss	_	_
21	A15	EMI address bus 15	4.9	_
22	A14	EMI address bus 14	4.9	4.5, 6.2
23	A13	EMI address bus 13	4.9	4.5, 6.2
24	A12	EMI address bus 12	4.9	4.5, 6.2
25	Vss	-	_	_
26	VDD	-	_	_
27	A11	EMI address bus 11	4.9	4.5, 6.2
28	A10	EMI address bus 10	4.9	4.5, 6.2
29	A9	EMI address bus 9	4.9	4.5, 6.2
30	A8	EMI address bus 8	4.9	4.5, 6.2
31	A7	EMI address bus 7	4.9	4.5, 6.2
32	A6	EMI address bus 6	4.9	4.5, 6.2
33	A5	EMI address bus 5	4.9	4.5, 6.2
34	A4	EMI address bus 4	4.9	4.5, 6.2
35	Vss	_	_	_
36	VDD	_	_	_
37	A3	EMI address bus 3	4.9	4.5, 6.2

# 2 Pin Information (continued)

Table 1. Pin Description (continued)

38	Pin #	Name	Description	Reference 1	Reference 2
A0	38	A2	EMI address bus 2	4.9	4.5, 6.2
A1	39	A1	EMI address bus 1	4.9	4.5, 6.2
42         M_CSN         ARM memory chip select, active-low         4.10, Table 6         —           43         X_CSN         External memory chip select, active-low         4.10, Table 6         —           44         RWN         Read/write, active-low         —         4.5, 6.2           45         Vss         —         —         —           46         VDD         —         —         —           47         D15         EMI data bus 15         3         4.5, 6.2           48         D14         EMI data bus 14         3         4.5, 6.2           49         D13         EMI data bus 13         3         4.5, 6.2           50         D12         EMI data bus 12         3         4.5, 6.2           51         D11         EMI data bus 13         3         4.5, 6.2           52         D10         EMI data bus 1         3         4.5, 6.2           52         D10         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 9         3         4.5, 6.2           55         Vss         —         —         —           56         Vsb         —         —         — <td>40</td> <td>A0</td> <td>EMI address bus 0</td> <td>4.9</td> <td>4.5, 6.2</td>	40	A0	EMI address bus 0	4.9	4.5, 6.2
43         X_CSN         External memory chip select, active-low         4.10, Table 6         —           44         RWN         Read/write, active-low         —         4.5, 6.2           45         Vss         —         —         —           46         VbD         —         —         —           47         D15         EMI data bus 15         3         4.5, 6.2           48         D14         EMI data bus 13         3         4.5, 6.2           49         D13         EMI data bus 13         3         4.5, 6.2           50         D12         EMI data bus 12         3         4.5, 6.2           51         D11         EMI data bus 10         3         4.5, 6.2           51         D10         EMI data bus 10         3         4.5, 6.2           53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           55         Vss         —         —         —           56         VbD         —         —         —           57         D7         EMI data bus 6         3         4.5, 6.2           59 <td>41</td> <td>I_CSN</td> <td>ARM interrupt chip select, active-low</td> <td>4.10, Table 6</td> <td>_</td>	41	I_CSN	ARM interrupt chip select, active-low	4.10, Table 6	_
44         RWN         Read/write, active-low         —         4.5, 6.2           45         Vss         —         —         —           46         VDD         —         —         —           47         D15         EMI data bus 15         3         4.5, 6.2           48         D14         EMI data bus 14         3         4.5, 6.2           49         D13         EMI data bus 13         3         4.5, 6.2           50         D12         EMI data bus 12         3         4.5, 6.2           51         D11         EMI data bus 11         3         4.5, 6.2           52         D10         EMI data bus 10         3         4.5, 6.2           53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           55         Vss         —         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2	42	M_CSN	ARM memory chip select, active-low	4.10, Table 6	_
45	43	X_CSN	External memory chip select, active-low	4.10, Table 6	_
46	44	RWN	Read/write, active-low	_	4.5, 6.2
47         D15         EMI data bus 15         3         4.5, 6.2           48         D14         EMI data bus 14         3         4.5, 6.2           49         D13         EMI data bus 13         3         4.5, 6.2           50         D12         EMI data bus 12         3         4.5, 6.2           51         D11         EMI data bus 11         3         4.5, 6.2           52         D10         EMI data bus 10         3         4.5, 6.2           53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 9         3         4.5, 6.2           55         Vss         —         —         —         —           56         VbD         —         —         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2         5         5         5         5         5         5         5         6         2         5         6         4.5, 6.2         6         6         3         4.5, 6.2         6         6         4.5, 6.2         6         6         5         3         4.5, 6.2         6         6	45	Vss	_	_	_
48         D14         EMI data bus 14         3         4.5, 6.2           49         D13         EMI data bus 13         3         4.5, 6.2           50         D12         EMI data bus 12         3         4.5, 6.2           51         D11         EMI data bus 11         3         4.5, 6.2           52         D10         EMI data bus 10         3         4.5, 6.2           53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 9         3         4.5, 6.2           55         Vss         —         —         —           56         VbD         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 6         3         4.5, 6.2           60         D4         EMI data bus 3         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 1         3         4.5, 6.2           63	46	Vdd	_	_	_
Mathematical Part	47	D15	EMI data bus 15	3	4.5, 6.2
50         D12         EMI data bus 12         3         4.5, 6.2           51         D11         EMI data bus 11         3         4.5, 6.2           52         D10         EMI data bus 10         3         4.5, 6.2           53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           55         Vss         —         —         —           56         VDD         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 4         3         4.5, 6.2           60         D4         EMI data bus 3         3         4.5, 6.2           61         D3         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 0         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65	48	D14	EMI data bus 14	3	4.5, 6.2
51         D11         EMI data bus 11         3         4.5, 6.2           52         D10         EMI data bus 10         3         4.5, 6.2           53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           55         Vss         —         —         —           56         VDD         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 6         3         4.5, 6.2           60         D4         EMI data bus 3         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 1         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VpD	49	D13	EMI data bus 13	3	4.5, 6.2
52         D10         EMI data bus 10         3         4.5, 6.2           53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           55         Vss         —         —         —           56         VDD         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 5         3         4.5, 6.2           60         D4         EMI data bus 3         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VbD         —         —         —           67         CK8KHZ         Test clock <td>50</td> <td>D12</td> <td>EMI data bus 12</td> <td>3</td> <td>4.5, 6.2</td>	50	D12	EMI data bus 12	3	4.5, 6.2
53         D9         EMI data bus 9         3         4.5, 6.2           54         D8         EMI data bus 8         3         4.5, 6.2           55         Vss         —         —         —           56         VDD         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 5         3         4.5, 6.2           60         D4         EMI data bus 4         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 1         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VDD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock* <td>51</td> <td>D11</td> <td></td> <td>3</td> <td>4.5, 6.2</td>	51	D11		3	4.5, 6.2
54         D8         EMI data bus 8         3         4.5, 6.2           55         Vss         —         —         —           56         VDD         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 5         3         4.5, 6.2           60         D4         EMI data bus 4         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         Vob         —         —         —           67         CK8KHZ         Test clock         9.1         —           69         STO1         Serial test clock*         —         —         —           70         STI1         Seri	52	D10	EMI data bus 10	3	4.5, 6.2
55         Vss         —	53	D9	EMI data bus 9	3	4.5, 6.2
56         VDD         —         —         —           57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 5         3         4.5, 6.2           60         D4         EMI data bus 4         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VDD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         STO1         Serial test out 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —<	54	D8	EMI data bus 8	3	4.5, 6.2
57         D7         EMI data bus 7         3         4.5, 6.2           58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 5         3         4.5, 6.2           60         D4         EMI data bus 4         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VbD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           70         STI1         Serial test in 1*         —         —           71         VbDGB <td>55</td> <td>Vss</td> <td>_</td> <td>_</td> <td>_</td>	55	Vss	_	_	_
58         D6         EMI data bus 6         3         4.5, 6.2           59         D5         EMI data bus 5         3         4.5, 6.2           60         D4         EMI data bus 4         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VbD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VbDGB         —         —         —           72         VssGB         — <td>56</td> <td>VDD</td> <td>_</td> <td>_</td> <td>_</td>	56	VDD	_	_	_
59         D5         EMI data bus 5         3         4.5, 6.2           60         D4         EMI data bus 4         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VbD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           75         AINCP <t< td=""><td>57</td><td>D7</td><td>EMI data bus 7</td><td>3</td><td>4.5, 6.2</td></t<>	57	D7	EMI data bus 7	3	4.5, 6.2
60         D4         EMI data bus 4         3         4.5, 6.2           61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         Vpb         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         9.1         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VpdBB         —         —         —           72         VssGB         —         —         —           73         AlNAN         (Handset) single-ended microphone input         5.1         —           74         AINCP         (Speakerphone) microphone differential input positive         5.1         —           75	58	D6	EMI data bus 6	3	4.5, 6.2
61         D3         EMI data bus 3         3         4.5, 6.2           62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VDD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         ST01         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           74         AINCP         (Speakerphone) microphone differential input negative         5.1         —           75         AINCP         (Speakerphone) microphone differential input positive         5.1         — <td>59</td> <td>D5</td> <td>EMI data bus 5</td> <td>3</td> <td>4.5, 6.2</td>	59	D5	EMI data bus 5	3	4.5, 6.2
62         D2         EMI data bus 2         3         4.5, 6.2           63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VbD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         ST01         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VbdB         —         —         —           72         VssGB         —         —         —           73         AlNAN         (Handset) single-ended microphone input         5.1         —           74         AlNCN         (Speakerphone) microphone differential input negative         5.1         —           75         AlNCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         — <tr< td=""><td>60</td><td>D4</td><td>EMI data bus 4</td><td>3</td><td>4.5, 6.2</td></tr<>	60	D4	EMI data bus 4	3	4.5, 6.2
63         D1         EMI data bus 1         3         4.5, 6.2           64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         VDD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           74         AINCP         (Speakerphone) microphone differential input negative         5.1         —           75         AINCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         —           77         AOUTA         (Handset) single-ended speaker output         5.3         —<	61	D3	EMI data bus 3	3	4.5, 6.2
64         D0         EMI data bus 0         3         4.5, 6.2           65         Vss         —         —         —           66         Vdd         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         ST01         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         Vdd         P         —         —           72         VssGB         —         —         —           73         AlNAN         (Handset) single-ended microphone input         5.1         —           74         AlNCN         (Speakerphone) microphone differential input negative         5.1         —           75         AlNCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         —           77         AOUTA         (Handset) single-ended speaker output         5.3         —	62	D2	EMI data bus 2	3	4.5, 6.2
65         Vss         —         —         —           66         VDD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           74         AINCN         (Speakerphone) microphone differential input negative         5.1         —           75         AINCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         —           77         AOUTA         (Handset) single-ended speaker output         5.3         —	63	D1	EMI data bus 1	3	4.5, 6.2
66         VDD         —         —         —           67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           74         AINCN         (Speakerphone) microphone differential input negative         5.1         —           75         AINCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         —           77         AOUTA         (Handset) single-ended speaker output         5.3         —	64	D0	EMI data bus 0	3	4.5, 6.2
67         CK8KHZ         Test clock         9.1         —           68         STCK         Serial test clock*         —         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           74         AINCN         (Speakerphone) microphone differential input negative         5.1         —           75         AINCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         —           77         AOUTA         (Handset) single-ended speaker output         5.3         —	65	Vss	_	_	_
68         STCK         Serial test clock*         —         —         —           69         STO1         Serial test out 1*         —         —           70         STI1         Serial test in 1*         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           74         AINCN         (Speakerphone) microphone differential input negative         5.1         —           75         AINCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         —           77         AOUTA         (Handset) single-ended speaker output         5.3         —	66	Vdd	_	_	_
69         STO1         Serial test out 1*         —         —         —           70         STI1         Serial test in 1*         —         —         —           71         VDDGB         —         —         —           72         VssGB         —         —         —           73         AINAN         (Handset) single-ended microphone input         5.1         —           74         AINCN         (Speakerphone) microphone differential input negative         5.1         —           75         AINCP         (Speakerphone) microphone differential input positive         5.1         —           76         GNDA         —         —         —           77         AOUTA         (Handset) single-ended speaker output         5.3         —	67	CK8KHZ		9.1	_
70 STI1 Serial test in 1* — —   71 VDDGB — — —   72 VssGB — — —   73 AINAN (Handset) single-ended microphone input 5.1 —   74 AINCN (Speakerphone) microphone differential input negative 5.1 —   75 AINCP (Speakerphone) microphone differential input positive 5.1 —   76 GNDA — — —   77 AOUTA (Handset) single-ended speaker output 5.3 —	68	STCK	Serial test clock*	_	_
71     VDDGB     —     —       72     VssGB     —     —       73     AINAN     (Handset) single-ended microphone input     5.1     —       74     AINCN     (Speakerphone) microphone differential input negative     5.1     —       75     AINCP     (Speakerphone) microphone differential input positive     5.1     —       76     GNDA     —     —     —       77     AOUTA     (Handset) single-ended speaker output     5.3     —	69	STO1		_	_
72       VssGB       —       —         73       AINAN       (Handset) single-ended microphone input       5.1       —         74       AINCN       (Speakerphone) microphone differential input negative       5.1       —         75       AINCP       (Speakerphone) microphone differential input positive       5.1       —         76       GNDA       —       —         77       AOUTA       (Handset) single-ended speaker output       5.3       —	70	STI1	Serial test in 1*	_	_
73       AINAN       (Handset) single-ended microphone input       5.1       —         74       AINCN       (Speakerphone) microphone differential input negative       5.1       —         75       AINCP       (Speakerphone) microphone differential input positive       5.1       —         76       GNDA       —       —       —         77       AOUTA       (Handset) single-ended speaker output       5.3       —	71	VDDGB	_	_	_
74     AINCN     (Speakerphone) microphone differential input negative     5.1     —       75     AINCP     (Speakerphone) microphone differential input positive     5.1     —       76     GNDA     —     —     —       77     AOUTA     (Handset) single-ended speaker output     5.3     —	72	VssGB	_	_	
75 AINCP (Speakerphone) microphone differential input positive 5.1 —  76 GNDA — — —  77 AOUTA (Handset) single-ended speaker output 5.3 —	73	AINAN		5.1	
76   GNDA   —   —     77   AOUTA   (Handset) single-ended speaker output   5.3   —	74	AINCN	1 ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '	5.1	
77 AOUTA (Handset) single-ended speaker output 5.3 —	75	AINCP	(Speakerphone) microphone differential input positive	5.1	
, , ,	76	GNDA	_	_	
78 VDDA — — —	77	AOUTA	(Handset) single-ended speaker output	5.3	
1 1 1	78	VDDA	_	_	_

<sup>\*</sup> Leave open, this is for test purposes only.

# 2 Pin Information (continued)

Table 1. Pin Description (continued)

Pin#	Name	Description	Reference 1	Reference 2
79	SVDD	_	_	_
80	SPKDRV1A	(Speakerphone) speaker#1 differential output driver A	5.3	_
81	SPKDRV1B	(Speakerphone) speaker#1 differential output driver B	5.3	_
82	SVss	_	_	_
83	SVss	_	_	_
84	SPKDRV2B	(Speakerphone) speaker#2 differential output driver B	5.3	_
85	SPKDRV2A	(Speakerphone) speaker#2 differential output driver A	5.3	_
86	SVDD	_	_	_
87	VssGB	_	_	_
88	VddGB	_	_	_
89	TRSTN	JTAG test reset input, active-low	9.2	_
90	TMODEN0	Test mode 0	9.1	_
91	TMODEN1	Test mode 1	9.1	_
92	TMODEN2	Test mode 2	9.1	_
93	RESETN	Chip reset, active-low	_	10.2
94	TDO	JTAG test data out	9.2	6.6
95	TCK	JTAG test clock	9.2	6.6
96	TMS	JTAG mode select	9.2	6.6
97	TDI	JTAG test data in	9.2	6.6
98	CK2MHZ	Clock out	9.1	_
99	CKO	DSP clock out	9.1	4.12
100	Vss	_	_	_

#### 3 Overview

The T8301 (DSP) interfaces with the T8302 (*ARM*) to form the basic building blocks for an internet protocol telephone (IPT), residing on a local area network (LAN); see Figure 2.

At the heart of the T8301 integrated circuit is the Lucent Technologies Microelectronics Group DSP1627 digital signal processor core. The DSP1627's high-performance (80 MIPS) and single-cycle multiply accumulate instruction provide excellent support for execution of voice compression/decompression and echo cancellation algorithms. The DSP1627 core and the analog audio circuitry included on the T8301 IC provide a low-cost silicon solution for the IP exchange telephone's audio requirements. A block diagram of the T8301 integrated circuit is shown in Figure 3.

The DSP1627 core contains the DSP1600 core processor, bit manipulation unit (BMU), dual-port RAM (DPRAM), instruction/coefficient ROM (IROM), bit I/O (BIO), serial I/O (SIO), timer, clock PLL control, vectored interrupts and traps, power management, external memory interface (EMI) with wait-state control, and a JTAG interface with integral hardware development system support.

The DSP1627 peripherals communicate with the DSP1627 core through the (D-IDB bus), which is 16 bits wide. The DSP1627 core's Harvard architecture allows efficient memory utilization by supporting separate instruction (XDB, XAB) and data (YDB, YAB) address spaces. The dual-port RAM (DPRAM) is connected to both address and data buses XDB, YDB, XAB, and YAB, while the instruction ROM is only connected to the XDB and XAB memory bus. The external memory interface provides a mechanism to access I/O devices and memories that are not part of the core DSP1627 hardware.

For a complete description of the DSP1627 core and its peripherals, refer to the *DSP1627 Digital Signal Processor* Data Sheet. A brief description of the functionality of the DSP1627 is provided in the following section. Where necessary, comments are made which reflect differences between the operation of the DSP1627 and the T8301. Please refer to the DSP1627 data sheet for further explanation.





Figure 2. DSP/ARM Interface Block Diagram

## 3 Overview (continued)



5-8210 (F)

Figure 3. T8301 Block Diagram

#### 4 DSP1600 Core

The discussions in this section pertain to circuitry that is inside of the dotted outline in Figure 3. For additional resources, please refer to the *DSP1627 Digital Signal Processor* Data Sheet.

The DSP1600 core includes a data arithmetic unit, memory addressing units, cache, and a control section. In combination, these elements support a diverse instruction set for implementing users' algorithms.

### 4.1 Bit Manipulation Unit (BMU)

The BMU provides extensive bit manipulation capabilities that increase the DSP1627's efficiency in processing data.


#### 4.2 Timer

The DSP1627 core contains a programmable interrupt timer that can be configured to count over a wide range of frequencies. This timer provides flexibility in timing events.

#### 4.3 Clock PLL Control

The DSP1627 powers up with the input clock (**CKI1/CKI2** in the T8301 IC) as the source for the processor clock. An on-chip clock synthesizer (PLL) can also be used to generate the system clock for the DSP1627, which will run at a frequency multiple of the input clock. The clock synthesizer is deselected and powered down on reset. For low-power operation, an internally generated slow clock can be used to drive the DSP1627. If both the clock synthesizer and the internally generated slow clock are selected, the slow clock will drive the DSP1627; however, the synthesizer will continue to run.

The clock synthesizer and other programmable clock sources are discussed in the DSP1627 data sheet. The use of these programmable clock sources for power management is also discussed in the DSP1627 data sheet. Board designers should refer to the section on VDDA and VSSA connections in the data sheet for specific connection and filtering requirements on the clock synthesizer power and ground leads.



Note: The 12,288 KHz is required as shown. Variations from this crystal frequency will cause detrimental effects to speech quality.

Figure 4. Crystal Oscillator

### 4.4 Bit Input/Output (BIO)

The BIO provides convenient and efficient monitoring and control of four individually configurable pins. When configured as outputs, the pins can be individually set, cleared, or toggled. When configured as inputs, individual pins or combinations of pins can be tested for patterns. Flags returned by the BIO mesh seamlessly with conditional instructions. Although the DSP1627 has eight BIOs available, the T8301 makes the four low-order BIOs available on pins.

### 4.5 Serial Input/Output (SIO)

The serial I/O interface (SIO) of the T8301 closely follows the serial interface of the DSP1627. The T8301 multiplexes certain DSP1627 SIO pins and eliminates some others to reduce the total pin count. Hysteresis input buffers are used for the SIO clocks on this device (IOLD, IOCK, and SYNC). The table below shows the signals that comprise the T8301 SIO interface.

**Table 2. SIO Interface Signals** 

Symbol	Type	Function
DI1	I	Serial data in 1.
DO1	0	Serial data out 1.
IOLD*	I/O	Input/output load for SIO 1.
IOCK	I/O	Input/output clock for SIO 1.
SYNC	I/O	Sync for SIO 1 and 2.

<sup>\*</sup> IOLD is comprised of the ILD1 and the OLD1 signals from the DSP1627 core tied together. By default, the IOLD signal is an input, which corresponds to the two DSP1627 load signals configured as passive. However, input load 1 (ILD1) may be configured as active, which then configures the IOLD signal as an output. In this case, the internal input load 1 (ILD1) drives the output load signal (OLD1.)

**IOCK** is analogous to **IOLD**. Input clock 1 can be configured as an output, which would then drive **IOCK** and **OCK1**. If the PLL is enabled, care should be taken if using **IOCK** as an output since there may be an unacceptable amount of jitter on the clock.

The **SYNC** signal is intended to provide synchronization of the serial bus with an external 8 kHz frame clock. When **SYNC** is configured as an input and asserted, the SIO load counter is reset and **IOLD** is asserted (if configured as an output).

For typical applications, the SIO will be configured to have **SYNC** and **IOCK** as inputs and **IOLD** as an output (from the DSP1627 core). In this configuration, there are thirty-two 8-bit (sixteen 16-bit) time slots for each SIO channel and **SYNC** provides the 8 kHz SIO frame timing. The timing relationship for this configuration can be found in the DSP1627 data sheet.

### 4.6 Interrupts and Traps

The DSP1627 supports prioritized, vectored interrupts, and a trap. There are eight internal hardware sources for program interrupt and two external interrupt pins. Additionally, there is a trap signal from the hardware development system (HDS). Each of the sources has a unique vector address and priority assigned to it. Refer to the DSP1627 data sheet for more information.

The use of the two external DSP1627 core interrupts is shown in Table 3 and in Figure 2.

INTON is dedicated to the *ARM* DCC interrupts in the DSP's mask ROM. INT1N is internally ORed with the DMA interrupt. The DSP's mask ROM for INT1 is dedicated to DMA servicing. It is recommended that INT1N float (internal pull up on pin).

Table 3. DSP1627 INTON and INT1N

Interrupt	Function	Interrupt Priority
INT1N	Interrupt from DMA block or external interrupt 1, active-low.	4 (higher)
INT0N	External interrupt input 0, active-low.	2

### 4.7 Power Management

There are three different power management control mechanisms: the **power control register** (**POWERC**), the stop pin (**STOPN**), and the **AWAIT** bit in the **ALF register**. Refer to the DSP1627 data sheet for more information concerning these registers and their usage.

### 4.8 External Memory Interface (EMI)

The T8301 external memory interface is used to access the non-DSP1627 core features provided in the T8301 integrated circuit. The external memory interface is also used to access off-chip resources such as the interprocessor communication memories contained in the IPT\_ARM integrated circuit.

The T8301 external memory interface requires one wait-state to access on-chip resources and two wait-states to access 15 ns or faster off-chip resources when operating at 80 MHz.

#### 4.9 T8301 Memory Mapping

The T8301 contains various types of memory modules, all with varying characteristics, aside from their memory map location. As a Harvard architecture, the device has two address/data buses; these are referred to as X and Y. The X system is used for program instructions and data, and the Y system is typically for data and memory mapped I/O. Memory is 16 bits wide.

The DSP1627 can vary the X bus memory map based on the logic levels on two signals: **EXM** and **LOWPR**. However, the T8301 has **EXM** tied low internally, reducing the possibilities to two. The two memory maps are the DSP1627's MAP1 and MAP3. **LOWPR** is software controllable. When using the DSP1627 software tools (with JCS i.e., JTAG communications system) the tools will configure **LOWPR** automatically based upon the link time compile options of the *.if* file. Map1 is the default map. The basic difference of the two maps is the type of memory at the reset vector (0x0000). MAP1 has ROM at 0x0000, and MAP3 has RAM at 0x0000. The Y map is fixed.

The T8301 is a masked ROM-coded device and contains no flash memory. MAP 1 is typically used for production, and Map 3 is typically used for code development. When used in conjunction to the T8302 *ARM* embedded processor, the *ARM* will be required to pass all code and data to the DSP's ram at power up reset. A hardware/software protocol must be instituted to allow the ARM to successfully load code into the DSP.

Note: All X memory references are MAP 3.

- Internal ROM, IROM—32K x 16:
  - Responds only to the X data bus, the X memory location is 0x4000—0xBFFF. This block will operate with zero wait-states.

- Dual-port (core) RAM, DPRAM—6K x 16:
  - This block is a true dual-port memory and is accessible simultaneously by both the X and Y bus system. Two locations can be either read or written in the same instruction execution. This memory block resides at locations 0x0000—0x17FF on both the X and Y maps. This block will operate with zero wait states. The DPRAM contains 6K x 16-bit words of zero wait-state memory, which is organized into six banks of 1K x 16-bit words. Each bank has separate ports to the instruction/coefficient and data memory spaces. Dual accesses to both memory spaces in separate banks incur no wait-states; however, accesses to the same bank from both spaces will add one wait-state to the total access time.
- Internal SRAM, ISRAM—16K x 16:
  - Although this is a dual-port RAM, there is only one bus system to the RAM itself. The X and Y bus is multiplexed before the RAM and is actually addressed via the external memory interface (EMI). Two locations can be **either** read **or** written in the same instruction execution, but will require two clock cycles. The X memory location is at 0xC000—0xFFFF and the Y memory location is at 0x8000—0xBFFF, and also at 0xC000—0xFFFF. (Referred to as mirrored. A write to 0x8000 on the Y map will also write to 0xC000). There is only one block of 16K; however, it appears twice on the Y map. **There is one wait-state required for both the X and Y bus to access this RAM**.
- External SRAM, XSRAM—12K x 16:
  - Responds only to the Y data bus. The T8301 generates a chip select called X\_CSN (active-low), pin 43. It uses the EMI to generate the address and data. There is one wait-state required for both the X and Y bus to access this RAM.

Table 4. T8301 Instruction/Coefficient Memory Map

Address	X MAP1	X MAP3	Address	Y MAP
0x0000			0x0000	
0x0800		Dual-port RAM 6K	0x0800	Dual-port RAM 6K
0x1000		(DPRAM)	0x1000	(DPRAM)
0x1800			0x1800	
0x2000	Internal ROM 32K		0x2000	
0x2800	(IROM)	Reserved 10K	0x2800	Reserved 10K
0x3000			0x3000	
0x3800			0x3800	
0x4000	(Instructions		0x4000	I/O and ERAMLO (See Table 5.)
0x4800	and constants)		0x4800	ERAMLO (See Table 5.)
0x5000			0x5000	
0x5800			0x5800	ERAMLO External chip select
0x6000		Internal ROM 32K	0x6000	X_CSN (external SRAM) 12K
0x6800		(IROM)	0x6800	
0x7000			0x7000	
0x7800			0x7800	
0x8000		(Instructions	0x8000	
0x8800		and constants)	0x8800	
0x9000	Internal SRAM 16K		0x9000	Internal SRAM 16K
0x9800	(ISRAM)		0x9800	(1K—16K block mirrored)
0xA000			0xA000	(ISRAM)
0xA800			0xA800	
0xB000			0xB000	
0xB800			0xB800	
0xC000			0xC000	
0xC800	Dual-port RAM 6K		0xC800	
0xD000	(DPRAM)	Internal SRAM 16K	0xD000	Internal SRAM 16K
0xD800		(ISRAM)	0xD800	(1K—16K block mirrored)
0xE000			0xE000	(ISRAM)
0xE800	Reserved 10K		0xE800	
0xF000			0xF000	
0xF800			0xF800	

Table 5. T8301 Memory-Mapped Peripherals

Address	Y MAP
0x4000	Analog I/O devices
0x4100	(I_CSN) DCC control interface
0x4200	Audio input, SRAM (512) read only
0x4300	
0x4400	Handset audio output, SRAM (512) write only
0x4500	
0x4600	Speaker audio output, SRAM (512) write only
0x4700	
0x4800	M_CSN
0x4900	ARM-to-DSP
0x4A00	Buffer (1K)
0x4B00	
0x4C00	M_CSN
0x4D00	DSP-to-ARM
0x4E00	Buffer (1K)
0x4F00	

# 4.10 Y Space Memory Map

The table below shows the Y space memory map. This is the area can be addressed via the DSP1627's R0, R1, R2, and R3 registers, and also by direct (Y-based) addressing.

Table 6. Data Memory Area: I/O, Register, and Memory

Address	R/W	DSP CS	Function	Description	Size (words)
0x0:0x17FF	R/W	Internal	Internal RAM	_	6K
0x4000	R/W	I/O	aioc_reg	Analog audio I/O control register, see Table 11.	1
0x4001	R/W	I/O	act1_reg	Audio codec test register 1.	1
0x4002	R/W	I/O	act2_reg	Audio codec test register 2.	1
0x4003	R/W	I/O	aclkc_reg	Audio codec clock control register, see Table 12.	1
0x4008	R/W	I/O	trc_reg	Tone ringer control register, see Table 8.	1
0x4010	R/W	I/O	dmac_reg	DMA control register, see Table 14.	1
0x4014	R/W	I/O	AlNsetadr_reg	Audio in DMA starting address register, see Table 15.	1
0x4015	R/W	I/O	AINsetcnt_reg	Audio in DMA transfer count registers, see Table 16.	1
0x4016	R/W	I/O	AlNadrinc_reg	Audio in DMA address increment registers, see Table 17.	1
0x4017	R/W	I/O	AINcntdec_reg	Audio in DMA transfer count decrement register, see Table 18.	1
0x4018	R/W	I/O	HNDsetadr_reg	Handset DMA starting address register, see Table 15.	1
0x4019	R/W	I/O	HNDsetcnt_reg	Handset DMA transfer count register, see Table 16.	1
0x401A	R/W	I/O	HNDadrinc_reg	Handset DMA address increment register, (see Table 17).	1
Ox401B	R/W	I/O	HNDcntdec_reg	Handset DMA transfer count decrement register, see Table 18.	1
0x401C	R/W	I/O	SPKsetadr_reg	Speaker DMA starting address register, see Table 15.	1
0x401D	R/W	I/O	SPKsetcnt_reg	Speaker DMA transfer count register, see Table 16.	1
0x401E	R/W	I/O	SPKadrinc_reg	Speaker DMA address increment register, see Table 17.	1
0x401F	R/W	I/O	SPKcntdec_reg	Speaker DMA transfer count decrement register, see Table 18.	1
0x4040	R/W	I/O	config_compander	Compander configuration register, see Table 19.	1
0x4041	W	I/O	write_companded	Write companded value register, see Table 21.	1
0x4041	R	I/O	read_linear	Read linear value register, see Table 22.	1
0x4042	W	I/O	write_linear	Write linear value register, see Table 20.	1

Table 6. Data Memory Area: I/O, Register, and Memory (continued)

Address	R/W	DSP CS	Function	Description	Size
					(words)
0x4042	R	I/O	read_companded	Read companded value register,	1
				see Table 23.	
0x4100:0x4107	R/W	ERAMLO	I_CSN	External chip select to access token registers.	8
0x4108:x410B	R/W	ERAMLO	I_CSN	External chip select to access ARM interrupt	4
				register.	
0x410C:0x410F	R/W	ERAMLO	I_CSN	External chip select to access DSP interrupt	4
				register.	
0x4110:0x41FF	R/W	ERAMLO	I_CSN	Reserved.	240
0x4200:0x43FF	R	ERAMLO	AIN SRAM	Audio input SRAM buffer.	512
0x4400:0x45FF	W	ERAMLO	AOUTA SRAM	Handset audio out SRAM buffer.	512
0x4600:0x47FF	W	ERAMLO	SOUT SRAM	Speaker audio out SRAM buffer.	512
0x4800:0x4BFF	R	ERAMLO	M_CSN	External chip select to access ARM to DSP	1K
				RAM (in the T8302 IPT_ARM chip).	
0x4C00:0x4FFF	W	ERAMLO	M_CSN	External chip select to access DSP to ARM	1K
				RAM (in the T8302 IPT_ARM chip).	
0x5000:0x7FFF	R/W	ERAMLO	X_CSN	External spare chip select.	12K
0x8000:0xBFFF	R/W	ERAMHI	ISRAM	Internal SRAM.	16K

## 5 Audio Input/Output Circuitry

The discussions in this section pertain to circuitry that is outside of the dotted outline in Figure 3 on page 8.

### 5.1 Analog Audio Input Channels

The T8301 contains analog interfaces designed to support a 150  $\Omega$  handset as well as an additional microphone and two speakers.

The T8301 integrated circuit contains two audio analog inputs. There is a single-ended input (AINAN) to be connected to a standard business telephone handset receiver. There is a differential input (AINCP, AINCN) to be connected to a microphone. This provides the T8301 with the input circuitry to implement a speakerphone. The differential input is directly connected to a 30 dB amplifier. The input select multiplexer routes AINAN or the output of the fixed 30 dB amplifier to a programmable gain amplifier (PGA). The programmable gain amplifier is adjustable from 0 dB to 21 dB in 3 dB steps. The signal output from the programmable gain amplifier is then routed to the audio codec block to be digitized.

Each of the input signals **AINAN**, **AINCP**, and **AINCN** are ac-coupled to their T8301 inputs by a  $0.2~\mu$ F capacitor. The maximum signal input to the codec is 2.5~Vp-p. If the user sets the amplification to a value that would produce a larger signal than 2.5~Vp-p, the audio codec will saturate and clip the input waveform.

The maximum input signal from the handset or from the microphone that can be supported for each gain setting is listed in Table 7. Since the microphone amplifier has a maximum specified signal of 40 mV, the maximum microphone input is not supported for PGA settings of 0 dB and 3 dB.

## 5.2 Programmable Gain Amplifier (PGA)

The programmable gain amplifier is using the PGAS[2:0] bits of the **aioc\_reg** (see Table 11 on page 21). The settable gain values and their tolerances are shown below as well as the maximum allowed input signal voltage from each of the input signals. Inputs greater than these values will saturate the input codec and produce clipped waveforms.

**Table 7. Programmable Gain Amplifier Maximum** 

Bit Code	Gain	Max Input Signal		
		AINAN	AINCN, AINCP	
000	0 dB ± 0.5 dB	2.500 Vp-p	Not supported	
001	$3 \text{ dB} \pm 0.5 \text{ dB}$	1.770 Vp-p	Not supported	
010	6 dB ± 0.5 dB	1.250 Vp-p	40.0 mVp-p	
011	9 dB ± 0.5 dB	0.844 Vp-p	28.3 mVp-p	
100	12 dB ± 0.5 dB	0.625 Vp-p	20.0 mVp-p	
101	15 dB ± 1.0 dB	0.442 Vp-p	14.2 mVp-p	
110	18 dB ± 1.0 dB	0.313 Vp-p	10.0 mVp-p	
111	21 dB ± 1.5 dB	0.221 Vp-p	7.1 mVp-p	

## **5.3 Analog Audio Output Channels**

The T8301 contains two independent analog audio output ports. There is a single-ended output signal, **AOUTA**, that can be connected to the speaker of a standard 150  $\Omega$  business telephone handset or to a differential speaker driver **SPKDRV2**. Differential speaker driver, **SPKDRV1**, can be set up to ring the phone by adding in the tone ringer output into its audio path.

Differential speaker driver output pins (**SPKDRV1A**, **SPKDRV1B** and **SPKDRV2A**, **SPKDRV2B**) should be connected to 45  $\Omega$  speakers. Both outputs receive their analog signals from the audio codec block, which converts the two digital input streams to analog signals.

The maximum signal from the codec is 2.5 Vp-p. The **AOUTA** signal has a maximum 2.5 Vp-p signal swing. It should maintain a midlevel bias to prevent load noises when the driver is re-enabled. The speaker outputs (**SPKDRV1A**, **SPKDRV1B** and **SPKDRV2A**, **SPKDRV2B**) each have 3 Vp-p signal swing. Since these outputs are of opposite polarity, the differential signal output is 6 Vp-p. This is a 6 dB effective amplification of the codec output signal. The signals should be biased such that, when power is re-enabled, no audible noises occur.

The differential speaker output driver does not have to produce a full 6 Vp-p signal without distortion. Signals above 5 Vp-p measured from **SPKDRVxA** to **SPKDRVxB** may be in the nonlinear range of the differential amplifier and exhibit a flattening or clipping characteristic at the output.

**AOUTA** is ac coupled to the handset speaker using a 2  $\mu$ F capacitor. The speaker driver outputs (**SPKDRV1A**, **SPKDRV2B**) are direct coupled to 45  $\Omega$  speakers.

### 5.4 Tone Ringer

The T8301 analog circuitry contains a tone ringer generator. When this circuit is powered up and enabled, the ringing tone output is added to the current analog speaker signal and output through the differential speaker driver. Custom tones may be generated by modifying the T8301 firmware.

Tana Bingar Cantral Bagistor (tra. 100) Address (0v.4009)

Table 8. Tone Ringer Control Register (trc\_reg)

	ione Ringer Control Register (trc_reg) Address (UX4008)							
Bit #	15:13	12	12 11:8 7:0					
Name	RSVD	TR_EN	TR_AC[3:0]	TR_FC[7:0]				
Bit #	Name	Description						
15:13	RSVD	Reserved.						
12	TR_EN	Tone ringer output enable.  If 1, the tone ringer's output is added into the speaker output path.  If 0, the tone ringer's output is disconnected from the speaker output path.						
11:8	TR_AC[3:0]	Tone ringer amplitude control, see Table 9.						
7:0	TR_FC[7:0]	Tone ringer frequency control, see Table 10. (The tone ringer frequencies are listed in hex format).						

**Table 9. Tone Ringer Amplitude Control Encoding** 

Bit# TR_AC[3:0]	Volts Out (p-p)	dB Relative to Maximum Level	Tolerance (dB from Nominal)
0 0 0 0	Silent	dc to midvoltage reference	Not applicable
0 0 0 1	0.023 V	-40.60	±0.75
0 0 1 0	0.032 V	-37.74	±0.75
0 0 1 1	0.045 V	-34.88	±0.75
0100	0.063 V	-32.02	±0.50
0101	0.087 V	-29.16	±0.50
0110	0.120 V	-26.30	±0.50
0111	0.170 V	-23.44	±0.25
1000	0.230 V	-20.58	±0.25
1001	0.330 V	-17.72	±0.25
1010	0.460 V	-14.86	±0.25
1011	0.620 V	-12.00	±0.25
1100	0.880 V	-9.00	±0.25
1 1 0 1	1.250 V	-6.00	±0.25
1110	1.770 V	-3.00	±0.25
1111	2.500 V	0	Not applicable

**Table 10. Tone Ringer Frequency Encoding** 

	Tone Ringer Frequency Encoding										
Hz	Hex	Hz	Hex	Hz	Hex	Hz	Hex	Hz	Hex	Hz	Hex
24,000	3F	1,067	1D	545.5	35	366.4	6C	277.5	2A	223.3	C5
16,000	1F	1,043	0E	539.3	9A	363.6	36	275.9	95	222.2	62
12,000	0F	1,021	07	533.3	4D	360.9	1B	274.3	CA	221.2	31
9,600	87	1,000	03	527.5	A6	358.2	8D	272.7	E5	220.2	18
8,000	43	979.5	81	521.7	D3	355.5	C6	271.2	72	219.2	0C
6,857	A1	960.0	C0	516.1	69	352.9	E3	269.7	B9	218.2	06
6,000	D0	941.2	60	510.6	34	350.4	F1	268.2	DC	217.2	83
5,333	E8	923.1	30	505.3	1A	347.8	78	266.7	EE	216.2	C1
4,800	F4	905.6	98	500.0	0D	345.3	3C	265.2	77	215.3	E0
4,364	7A	888.9	4C	494.8	86	342.8	9E	263.7	BB	214.3	70
4,000	3D	872.7	26	489.8	C3	340.4	CF	262.3	DD	213.3	B8
3,692	1E	857.1	93	484.9	E1	338.0	E7	260.9	6E	212.4	5C
3,429	8F	842.1	49	480.0	F0	335.7	73	259.5	37	211.5	AE
3,200	C7	827.6	24	475.2	F8	333.3	39	258.1	9B	210.5	57
3,000	63	813.6	92	470.6	7C	331.0	9C	256.7	CD	209.6	AB
2,824	B1	800.0	C9	466.0	BE	328.8	CE	255.3	E6	208.7	55
2,667	58	786.9	64	461.5	DF	326.5	67	253.9	F3	207.8	AA
2,526	2C	774.2	B2	457.1	6F	324.3	33	252.6	79	206.9	D5
2,400	16	761.9	D9	452.8	В7	322.1	19	251.3	ВС	206.0	EA
2,286	0B	750.0	EC	448.6	DB	320.0	8C	250.0	DE	205.1	F5
2,182	05	738.5	76	444.4	ED	317.9	46	248.7	EF	204.3	FA

Table 10. Tone Ringer Frequency Encoding (continued)

	Tone Ringer Frequency Encoding										
Hz	Hex	Hz	Hex	Hz	Hex	Hz	Hex	Hz	Hex	Hz	Hex
2,087	02	727.3	3B	440.4	F6	315.8	А3	247.4	F7	203.4	7D
2,000	01	716.4	9D	436.4	7B	313.7	D1	246.2	FB	202.5	3E
1,920	80	705.9	4E	432.4	BD	311.7	68	244.9	FD	201.7	9F
1,846	40	695.7	27	428.6	5E	309.7	B4	243.7	7E	200.8	4F
1,778	20	685.7	13	424.8	AF	307.7	5A	242.4	BF	200.0	A7
1,714	10	676.1	09	421.1	D7	305.7	2D	241.2	5F	199.2	53
1,655	88	666.7	04	417.4	EB	303.8	96	240.0	2F	198.3	29
1,600	C4	657.5	82	413.8	75	301.9	4B	238.8	97	197.5	14
1,548	E2	648.6	41	410.3	BA	300.0	25	237.6	СВ	196.7	0A
1,500	71	640.0	A0	406.8	5D	298.1	12	236.5	65	195.9	85
1,455	38	631.6	50	403.4	2E	296.3	89	235.3	32	195.1	42
1,412	1C	623.4	A8	400.0	17	294.5	44	234.1	99	194.3	21
1,371	8E	615.4	D4	396.7	8B	292.7	A2	233.0	CC	193.5	90
1,333	47	607.6	6A	393.4	45	290.9	51	231.9	66	192.8	C8
1,297	23	600.0	B5	390.2	22	289.2	28	230.8	B3	192.0	E4
1,263	91	592.6	DA	387.1	11	287.4	94	229.7	59	191.2	F2
1,231	48	585.4	6D	384.0	80	285.7	4A	228.6	AC	190.5	F9
1,200	A4	578.3	B6	380.9	84	284.0	A5	227.5	56	189.7	FC
1,171	D2	571.4	5B	377.9	C2	282.4	52	226.4	2B	189.0	FE
1,143	E9	564.7	AD	375.0	61	280.7	A9	225.4	15	188.2	FF
1,116	74	558.2	D6	372.1	B0	279.1	54	224.3	8A	_	
1,091	3A	551.7	6B	369.2	D8	<u> </u>	_				_

#### 5.5 Audio Codec Block

The T8301 contains a 16-bit analog-to-digital converter and two 16-bit digital-to-audio converters. These converters each contain appropriate antialiasing or smoothing filters. A block diagram of the audio codec block is shown below.




Figure 5. Audio Codec Block Diagram

## 5.6 Audio Codec Control Registers

The analog audio input and output control register (aioc\_reg) is used to select the active and enabled inputs and outputs. Through this register the input and output channels can also have the clocks shut down to conserve power.

Table 11. aioc\_reg Analog Audio I/O Control

	Analog Audio Input and Output Control Register (aioc_reg): Address (0x4000)									
Bit #	15	14	13	12	11	10	9:8			
Name	MPWRD	SPKFB	HNDFB	AINFB	SPK2EN	OLE	RSVD			
Bit #	7	6	5	4	3	2	1:0			
Name	RSVD	PGAS(2)	PGAS(1)	PGAS (0)	SPKEN	AOUTAEN	AINSS[1:0]			

Bit #	Name	Value at Reset	Description
15	MPWRD	1	Main powerdown.  If 1, powerdown.  If 0, powerup.
14	SPKFB	0*	Speaker #1 output filter bypass.  If 1, the transmit LPF is bypassed in the speaker path; set the corresponding DMA clock to 16 kHz.  If 0, the transmit LPF is enabled in the speaker path.  Note: The SOC bits in the audio codec clock control register should also be modified.
13	HNDFB	0*	Handset output filter bypass.  If 1, the transmit LPF is bypassed in the handset path; set the corresponding DMA clock to 16 kHz.  If 0, the transmit LPF is enabled in the handset path.  Note: The HOC bits in the audio codec clock control register should also be modified.
12	AINFB	0*	Analog input filter bypass.  If 1, the receive BPF is bypassed in the audio input path; set the corresponding DMA clock to 16 kHz.  If 0, the receive BPF is enabled in the audio input path.  Note: The AINC bits in the audio codec clock control register should also be modified.
11	SPK2EN	0	Enables speaker #2 output channel.  If 1, the speaker's output driver is enabled.  If 0, the output driver for the speaker output channel is disabled.
10	OLE	0	Output limit enable. When set, this bit causes the nominal full-scale output for the analog outputs to be limited to approximately half the normal value of 2.5 Vp-p Setting this bit has no effect on the receive gain.
9:7	RSVD		Reserved.

<sup>\*</sup> If the BPF is bypassed, output from the decimator must be shifted right by 2 bits (6 dB attenuation) to avoid saturation going into the compander. Similarly, if the LPF is bypassed in the speaker or handset path, input into the interpolator must be shifted left by 2 bits.

Table 11. aioc\_reg Analog Audio I/O Control (continued)

Bit #	Name	Value at Reset	Description
6:4	PGAS[2:0]	000	PGA gain select. Selects the gain for the programmable gain amplifier. See Table 7 on page 17 for an explanation of the coding.
3	SPKEN	0	Enables the speaker output channel.  If 1, the speaker's output driver is enabled.  If 0, the output driver for the speaker output channel is disabled.
2	AOUTAEN	0	Enables the handset output channel.  If 1, the handset output driver is enabled.  If 0, the output driver for the handset output channel is disabled.
1:0	AINSS	00	Analog input source select.  If 11, reserved.  If 10, analog input source is from the microphone (AINCN, AINCP).  If 01, analog input source is from the handset (AINAN).  If 00, mute (default after reset or powerup).

### Table 12. Audio Codec Clock Control Register (aclkc\_reg)

Audio Codec Clock Control Register (aclkc_reg) Address (0x4003)								
Bit #	15:9	8:6	5:3	2:0				
Name	RSVD	SOC(2:0)	HOC(2:0)	AINC(2:0)				

Bit #	Name	Description	
15:9	RSVD	Reserved.	
8:6	SOC(2:0)	Please refer to Table 13 for bit field description.	
5:3	HOC(2:0)	Please refer to Table 13 for bit field description.	
2:0	AINC(2:0)	Please refer to Table 13 for bit field description.	

## **Table 13. Audio Clock Encoding**

	Audio Clock Encoding SOC, HOC, AINC						
Bit Code	Description						
000	0 Hz. The clock for the channel is stopped.						
001	8 kHz clock is used for all audio codes except G.722.						
010	16 kHz clock is used for G.722 (must bypass filters).						
011	Reserved.						
100	Reserved.						
101	Reserved.						
110	Reserved.						
111	Supplies 1 MHz clock to DMA. Reserved for testing only.						

## 6 DMA Input/Output Channels

The discussions in this section pertain to circuitry that is outside of the dotted outline in Figure 3 on page 8.

There are three timed DMA transfer blocks, each of which transfers data to/from the audio codec block from/to a 512 x 16-bit SRAM. These SRAMs are two-port devices. One port is connected to the DSP1627 address and data bus, and the other is accessed by the DMA controller. These memories transfer data to/from the audio codec block or **AOUTA**, **AIN**, and **SOUT**. These DMA blocks are capable of transferring a 16-bit word to/from the device's A/D or D/A at the following rates, which are set up by programming the **audio codec clock control register**:

- 8 kHz
- 16 kHz

Each channel initiates a transfer between the audio codec block and its respective SRAM on the rising edge of the selected transfer clock.

### 6.1 DMA Operation

The T8301 has three timed DMA transfer channels. The DSP sets up a DMA channel by writing a starting address and a transfer count into the **setadr\_reg** (see Table 15) and **setcnt\_reg** (see Table 16). The DSP then sets the channel's **GO** bit in the **dmac\_reg** (see Table 14). When the DMA finishes its current transfer operation, indicated by the **BSY** bit in the **dmac\_reg** going low, the DMA will transfer the contents of the **setadr\_reg** (see Table 15) to the **adrinc\_reg** (see Table 17) and the **cntdec\_reg** (see Table 18) respectively. The **GO** bit will be reset to zero and the **BSY** bit will be set to one, in the **dmac\_reg** on completion of this transfer. When the rising edge of the transfer clock is detected, the DMA controller will transfer a single word to/from memory and the audio codec block. The DMA channel will then increment its address pointer **adrinc\_reg** and decrement its counter **cntdec\_reg**. At the completion of the number of transfers written into the transfer counter (**cntdec\_reg** = 0), the DMA block will set its **ION** bit in the **dmac\_reg** to 1 and reset its **BSY** bit to zero. If its **IEN** bit is set, an interrupt to the DSP will occur. If the DSP has set the **GO** bit which indicates that it has set up a new transfer or if the DSP responds (sets up a new transfer count and re-enables transfers) before the next rising edge of the transfer clock, data can be continuously transferred at the clocked rate.

If the DSP is reading or writing to the memory that a timed DMA is transferring to/from, the DMA can be delayed by a clock cycle to allow the DSP to finish its access.

#### 6.2 DMA Registers

Each DMA channel has the following four registers:

- Starting address register
- Transfer count register
- Working address increment register (read only)
- Working count decrement register (read only)

In addition, there is a control and status register that supports all three DMA channels.

# 6 DMA Input/Output Channels (continued)

Table 14. DMA Control Register dmac\_reg

	DMA Control Register (dmac_reg) Address (0x4010)									
Bit #	15	14	13	12	11	10	9	8		
Name	RSVD	IENSPK	IENHND	IENAIN	RSVD	IONSPK	IONHND	IONAIN		
Bit #	7	6	5	4	3	2	1	0		
Name	RSVD	SPKBSY	HNDBSY	AINBSY	RSVD	SPKGO	HNDGO	AINGO		

Bit #	Name	Description
15	RSVD	Reserved.
14	IENSPK	Interrupt enable speaker output channel.
13	IENHND	Interrupt enable handset output channel.
12	IENAIN	Interrupt enable analog input channel.
11	RSVD	Reserved.
10	IONSPK	Interrupt on speaker DMA channel. Indicates a transfer has completed. A physical interrupt to the DSP will only occur if the <b>IENSPK</b> bit is also set. The interrupt is cleared by a read operation.
9	IONHND	Interrupt on handset DMA channel. Indicates a transfer has completed. A physical interrupt to the DSP will only occur if the <b>IENHND</b> bit is also set. The interrupt is cleared by a read operation.
8	IONAIN	Interrupt on analog input DMA channel. Indicates a transfer has completed. A physical interrupt to the DSP will only occur if the <b>IENAIN</b> bit is also set. The interrupt is cleared by a read operation.
7	RSVD	Reserved.
6	SPKBSY	Speaker DMA channel busy (read only).
5	HNDBSY	Handset DMA channel busy (read only).
4	AINBSY	Analog input DMA channel busy (read only).
3	RSVD	Reserved.
2	SPKGO	DMA start. Starts the DMA channel when set to 1, automatically reset to zero when a count of zero is reached by the DMA transfer counter.
1	HNDGO	DMA start. Starts the DMA channel when set to 1, automatically reset to zero when a count of zero is reached by the DMA transfer counter.
0	AINGO	DMA start. Starts the DMA channel when set to 1, automatically reset to zero when a count of zero is reached by the DMA transfer counter.

## Table 15. DMA Starting Address Register setadr\_reg

Set DMA A	Set DMA Address Registers [AlNsetadr_reg Address (0x4014)] [HNDsetadr_reg Address (0x4018)] [SPKsetadr_reg Address (0x401C)]						
Bit #	15:9	8:0					
Name	RSVD	DMA_ADDRESS_SET_UP[8:0]					

### Table 16. DMA Transfer Count Register setcnt\_reg

Set DMA Count Registers [AINsetcnt_reg Address (0x4015)] [HNDsetcnt_reg Address (0x4019)]  [SPKsetcnt_reg Address (0x401D)]		
Bit #	15:9	8:0
Name	RSVD	DMA_COUNT_SET_UP[8:0]

# 6 DMA Input/Output Channels (continued)

Table 17. DMA Address Increment Register adrinc\_reg

DMA Address Increment Registers (Read Only) [AlNadrinc_reg Address (0x4016)] [HNDadrinc_reg Address (0x401A)] [SPKadrinc_reg Address (0x401E)]					
Bit #	15:9	8:0			
Name	Name RSVD DMA_ADDRESS[8:0]				

## Table 18. DMA Transfer Decrement Register cntdec\_reg

DMA Count Decrement Registers (Read Only) [AlNcntdec_reg Address (0x4017)] [HNDcntdec_reg Address (0x401B)] [SPKcntdec_reg Address (0x401F)]		
Bit #	15:9	8:0
Name RSVD DMA_COUNT[8:0]		DMA_COUNT[8:0]

## 7 Hardware Compander

The discussions in this section pertain to circuitry that is outside of the dotted outline in Figure 3 on page 8.

The hardware compander performs companded-to-linear and linear-to-companded conversions. This alleviates the DSP from performing the functions in firmware. The compander supports both  $\mu$ -law and A-law operations.

A block diagram of the compander is shown in Figure 6 on page 27. The compander consists of two write-only registers: write\_linear and write\_companded. A configuration register (config\_compander) and two read registers (read \_linear and read\_ companded) read the results. Config\_compand configures the compander for either μ-law or A-law conversion. Upon reset, the register defaults to μ-law. The DSP performs a linear-to-companded conversion by writing the write\_linear register and then reading the read-companded buffer. The companded value at the read buffer remains the same until a new linear value is written to the write\_linear register. Similarly, companded to linear is done by write\_companded then read\_linear.

Table 19. config\_compander Register

Compander Configuration Register (config_compander)						
Bit	<b>Bit</b> 15:1 0					
Field	Reserved	μ–Law				
After Reset	X	1 = μ–Law				
0 = A-Law						

#### Table 20. write\_linear Register

write_linear		
Bit 15:0		
_	Linear value	

#### Table 21. write\_companded Register

write_companded		
Bit 15:0		
_	Companded value	


#### Table 22. read\_linear Register

read_linear		
Bit	15:0	
_	Linear value	

#### Table 23. read companded Register

read_companded		
<b>Bit</b> 15:0		
— Companded value		

# 7 Hardware Compander (continued)



5-8209(F)

Figure 6. Hardware Compander Block Diagram

The **Config\_compander** register configures the compander for either  $\mu$ -law or A-law conversion. Upon reset, the register defaults to  $\mu$ -law, see Table 19 on page 26.

# 8 Electrical Specifications

## 8.1 Operating Range Specifications

**Table 24. Operating Range Specifications** 

Parameter	Symbol	Min	Max	Unit
Ambient Temperature Range	TA	0	70	°C
Operating Supply Voltage	VDD	4.75	5.25	V
Power Consumption	Р	_	900	mW

## 8.2 Analog and Codec Specifications

**Table 25. AINAN Specifications** 

Parameter	Conditions	Value
Source Impedance*	ac-coupled with a 0.2 μF capacitor	1 kΩ—3 kΩ
Input Impedance	With ac-coupled +2.5 Vp-p input signal (max PGA gain)	6 kΩ—12 kΩ
Total Harmonic Distortion	Input signals 100 mV—2.5 Vp-p	≤2%
Transmit Idle Channel Noise	PGA set 12 dB	≤20 dBrnC
Power Supply Rejection Ratio	_	≥50 dB

<sup>\*</sup> Parameter supplied for reference purposes.

### **Table 26. AINCP, AINCN Specifications**

Parameter	Conditions	Value
Source Impedance*	ac-coupled w/ 0.2 μF capacitor	1 kΩ— 3 kΩ
Input Impedance	With ac-coupled 40 mVp-p	12 kΩ—20 kΩ
Total Gain	_	30 dB ± 1 dB
Total Harmonic Distortion	Input signals 1 mV—40 mV ≤2%	Total harmonic distortion input signals 1 mV—40 mV ≤2%

<sup>\*</sup> Parameter supplied for reference purposes.

### **Table 27. AOUTA Specifications**

Parameter	Conditions	Value
Vouт	0 dBm0	0.618 Vrms (±0.5 dB)
Vouт	3.14 dBm0	2.50 Vp-p typical
Device impedance	_	150 Ω
Total harmonic distortion (3.0 dBm0)	–35 dB max (μA limit)	-40 dB max
Total harmonic distortion (0.0 dBm0)	0.0 dB max (μA limit)	-65 dB max

# 8 Electrical Specifications (continued)

Table 28. Speaker#1, Speaker#2 Specifications

Parameter	Conditions	Value
Vout	0 dBm0	1.236 Vrms (±0.5 dB)
Vout	3.14 dBm0	5.00 Vp-p typical
Device Impedance	_	45 Ω
Total Gain	_	6 dB ± 0.25 dB
Total Harmonic Distortion	–35 dB max (μA limit)	-40 dB max
Total Harmonic Distortion	0.0 dB max (μA limit)	−65 dB max

Note: Maximum digital-to-analog converter range = 2.5 V. This translates into a peak-to-peak differential signal of 5.0 V. All signals measured differentially.

Table 29. Digital Low-Pass Filters Specifications

Parameter	Conditions	Value
Maximum Ripple Pass-Band	300 Hz ≤ signal frequency ≤ 3.0 kHz	3%
Minimum Attenuation	4 kHz	30 dB

Table 30. Digital-to-Analog Converter Specifications

Parameter	Conditions	Value	
Range	_	16-bit	
Monotonicity	Full operating range	Monotonic	
Accuracy	Full operating range	TBD	
Full Scale Output	_	2.5 Vp-p	
Max Voltage Change 1-bit Change	_	1.5 LSB	
Input Code	_	Two's complement	

**Table 31. Analog-to-Digital Converter Specifications** 

Parameter	Conditions	Value
Range	_	16-bit
Monotonicity	Full operating range	Monotonic
Accuracy	Full operating range	TBD
Max Step-to-step Size	_	1.5 LSB
Full Scale Input	_	2.5 Vp-p
Output Code	_	Two's complement

## 8.3 Crystal Specification

See the DSP1627 Digital Signal Processor Data Sheet for further information.

## 9 JTAG and Hardware Development System (HDS)

The JTAG block contains logic for implementing the JTAG/IEEE\* P1149.1 standard. A four-signal test port provides a mechanism for accessing the DSP1627 core from remote test equipment or a remote hardware development system. The on-chip HDS performs instruction breakpointing and branch tracing at full speed. Using the JTAG port, the breakpointing is set up and the trace history is read back.

#### 9.1 TMODE Control for JCS/Boundary-Scan Operation

TMODEN0, TMODEN1, and TMODEN2 are inputs used to determine test mode operation. Of the eight possible combinations, modes 6 and 7 are significant during the development and production phases.

### 9.1.1 Mode 7 Operation (TMODE = 7)

This is the production mode. Internal pull-up resistors (approximately 50 k $\Omega$ ) will provide the logic level required. The three pins can be left floating (no external resistors are required). In this mode, boundary-scan is active. The CK8KHz (pin 67), the CK2MHz (pin 98), and the CKO (pin 99) are all dormant (high).

#### 9.1.2 Mode 6 Operation (TMODE = 6)

The JCS tools (JTAG communications system) are used in this mode. TMODEN0 must be pulled low externally, TMODEN1, and TMODEN2 can both be left floating to enter this mode. The CK8KHz (pin 67), the CK2MHz (pin 98), and the CKO (pin 99) are active.


Should the user require access to any or all of the three clocks in production and still require boundary-scan capabilities for production test, a strong (external) pull-down resistor would be required on TMODEN0 (1 k $\Omega$ ). The production test must be able to pull TMODEN0 high to allow access to the boundary-scan test. After the test is complete, the pin would normally be low (TMODE 6) allowing the clocks to be active.

#### 9.2 The Principle of Boundary-Scan Architecture

Each primary input signal and primary output signal is supplemented with a multipurpose memory element called a boundary-scan cell. Cells on device primary inputs are referred to as input cells and cells on primary outputs are referred to as output cells. Input and output is relative to the core logic of the device.

At any time, only one register can be connected from TDI to TDO, e.g., the instruction register (IR), BYPASS, boundary-scan, IDENT, or even some appropriate register internal to the core logic; see Figure 7. The selected register is identified by the decoded output of the instruction register. Certain instructions are mandatory, such as EXTEST (boundary-scan register selected), whereas others are optional, such as the IDCODE instruction (IDENT register selected).

<sup>\*</sup> IEEE is a registered trademark of The Institute of Electrical and Electronics Engineers, Inc.



IEEE 1149.1 CHIP ARCHITECTURE

Figure 7. Boundary-Scan Architecture

Figure 7 shows the following elements:

- A set of four dedicated test pins, test data in (TDI), test mode select (TMS), test clock (TCK), test data out (TDO), and one optional test pin test reset (TRSTN). These pins are collectively referred to as the test access port (TAP).
- A boundary-scan cell on each device's primary input and primary output pin, connected internally to form a serial boundary-scan register (boundary-scan).
- A finite-state machine TAP controller with inputs TCK and TMS.
- $\blacksquare$  An n-bit (n = 4) instruction register (IR), holding the current instruction.
- A 1-bit bypass register (BYPASS).
- An optional 32-bit identification register (IDENT) capable of being loaded with a permanent device identification code.

Access to JTAG (joint test action group) and boundary-scan will be initially provided through a single set of JTAG pins. The pin definitions are as follows.

Table 32. Boundary-Scan Pin Functions

Pin	Boundary-Scan	Debug	Comments
94	TDO (bscan)	TDO (debug)	_
95	TCK (bscan)	TCK (debug)	Pulled high internally
96	TMS (bscan)	TMS (debug)	Pulled high internally
97	TDI (bscan)	TDI (debug)	_
89	TRSTN (bscan)	TRSTN (debug)	Pulled high internally

Debug mode, or boundary-scan mode is selected via the TMODE pins as shown below.

Table 33. Debug Mode

Pin	Name	Description	Comments
90	TMODEN0	If 7 = boundary-scan	Pulled high internally
91	TMODEN1	If 6 = debug	Pulled high internally
92	TMODEN2		Pulled high internally

#### 9.2.1 Boundary-Scan Instruction Register

The boundary-scan instruction register is 4 bits long and the capture value is 0001.

Table 34. Boundary-Scan Instruction Register

Instruction	Binary Code	Description		
EXTEST	0000	Places the boundary-scan register in EXTEST mode.		
SAMPLE	0001	Places the boundary-scan register in sample mode.		
IDCODE	0101	Identification code.		
BYPASS	1111	Places the bypass register in the scan chain.		

The idcode values are as follows:

Version = 0000 (0x0)

Part = 0011011101000110 (0x 3746)

Manufacturer = 00000011101 (0x1D)

Table 35. Boundary-Scan Register Description

Boundary-Scan Register Bit Pin	Pin Name	Ball	Enabled State	Pin Grouping	Control	Disable Value
0	BIO_E(0)		Controller	_	_	_
1	BIO(0)	2	I/O	BIO_E(0)	0	High Impedance
2	BIO_E(1)		Controller	_	_	<u> </u>
3	BIO(1)	3	I/O	BIO_E(1)	0	High Impedance
4	BIO_E(2)	_	Controller	_	_	_
5	BIO(2)	4	I/O	BIO_E(2)	0	High Impedance
6	BIO_E(3)	_	Controller	_	_	_
7	BIO(3)	5	I/O	BIO_E(3)	0	High Impedance
8	INT0N	6	Input	_	_	_
9	INT1N	7	Input	_	_	_
10	STOPN	8	Input	_	_	_
11	DI1	9	Input	_	_	_
12	DO1_E	_	Controller	_	_	_
13	DO1	12	I/O	DO1_E	0	High Impedance
14	SYNC_E	_	Controller	_	_	_
15	SYNC	13	I/O	SYNC_E	0	High Impedance
16	IOLD_E	_	Controller	_	_	_
17	IOLD	14	I/O	IOLD_E	0	High Impedance
18	IOCK_E	_	Controller	_	_	_
19	IOCK	15	I/O	IOCK_E	0	High Impedance
20	DSP_A_E	_	Controller	_	_	_
21	A(15)	21	I/O	A_E	0	High Impedance
22	A(14)	22	I/O	A_E	0	High Impedance
23	A(13)	23	I/O	A_E	0	High Impedance
24	A(12)	24	I/O	A_E	0	High Impedance
25	A(11)	27	I/O	A_E	0	High Impedance
26	A(10)	28	I/O	A_E	0	High Impedance
27	A(9)	29	I/O	A_E	0	High Impedance
28	A(8)	30	I/O	A_E	0	High Impedance
29	A(7)	31	I/O	A_E	0	High Impedance
30	A(6)	32	I/O	A_E	0	High Impedance
31	A(5)	33	I/O	A_E	0	High Impedance
32	A(4)	34	I/O	A_E	0	High Impedance
33	A(3)	37	I/O	A_E	0	High Impedance
34	A(2)	38	I/O	A_E	0	High Impedance
35	A(1)	39	I/O	A_E	0	High Impedance
36	A(0)	40	I/O	A_E	0	High Impedance
37	I_CSN	41	I/O	A_E	0	High Impedance
38	M_CSN	42	I/O	A_E	0	High Impedance
39	X_CSN	43	I/O	A_E	0	High Impedance
40	RWN	44	I/O	A_E	0	High Impedance

Table 35. Boundary-Scan Register Description (continued)

Boundary-Scan Register Bit Pin	Pin Name	Ball	Enabled State	Pin Grouping	Control	Disable Value
41	D_E	_	Controller	_		_
42	D(15)	47	I/O	D_E	0	High Impedance
43	D(14)	48	I/O	D_E	0	High Impedance
44	D(13)	49	I/O	D_E	0	High Impedance
45	D(12)	50	I/O	D_E	0	High Impedance
46	D(11)	51	I/O	D_E	0	High Impedance
47	D(10)	52	I/O	D_E	0	High Impedance
48	D(9)	53	I/O	D_E	0	High Impedance
49	D(8)	54	I/O	D_E	0	High Impedance
50	D(7)	57	I/O	D_E	0	High Impedance
51	D(6)	58	I/O	D_E	0	High Impedance
52	D(5)	59	I/O	D_E	0	High Impedance
53	D(4)	60	I/O	D_E	0	High Impedance
54	D(3)	61	I/O	D_E	0	High Impedance
55	D(2)	62	I/O	D_E	0	High Impedance
56	D(1)	63	I/O	D_E	0	High Impedance
57	D(0)	64	I/O	D_E	0	High Impedance
58	CLK_E	_	Controller	_	_	_
59	CK8KHZ	67	I/O	CLK_E	0	High Impedance
60	STCK_E	_	Controller	_		_
61	STCK	68	I/O	STCK_E	0	High Impedance
62	STI_E	_	Controller	_	_	_
63	STI1	70	I/O	STI_E	0	High Impedance
64	STO_E	_	Controller	_	_	_
65	STO1	69	I/O	STO_E	0	High Impedance
66	RESETN_E	_	Controller	_		_
67	RESETN	93	I/O	RESETN_E	0	High Impedance
68	CK2MHZ	98	I/O	CLK_E	0	High Impedance
69	СКО	99	I/O	CLK_E	0	High Impedance

**Notes** 

For additional information, contact your Microelectronics Group Account Manager or the following:

INTERNET: http://www.lucent.com/micro F-MAII · docmaster@micro.lucent.com

Microelectronics Group, Lucent Technologies Inc., 555 Union Boulevard, Room 30L-15P-BA, Allentown, PA 18109-3286 1-800-372-2447, FAX 610-712-4106 (In CANADA: 1-800-553-2448, FAX 610-712-4106) N. AMERICA:

ASIA PACIFIC: Microelectronics Group, Lucent Technologies Singapore Pte. Ltd., 77 Science Park Drive, #03-18 Cintech III, Singapore 118256 Tel. (65) 778 8833, FAX (65) 777 7495

Microelectronics Group, Lucent Technologies (China) Co., Ltd., A-F2, 23/F, Zao Fong Universe Building, 1800 Zhong Shan Xi Road, Shanghai 200233 P. R. China Tel. (86) 21 6440 0468, ext. 325, FAX (86) 21 6440 0652 CHINA:

Microelectronics Group, Lucent Technologies Japan Ltd., 7-18, Higashi-Gotanda 2-chome, Shinagawa-ku, Tokyo 141, Japan Tel. (81) 3 5421 1600, FAX (81) 3 5421 1700 JAPAN:

**EUROPE:** 

Data Requests: MICROELECTRONICS GROUP DATALINE: Tel. (44) 7000 582 368, FAX (44) 1189 328 148

Technical Inquiries: GERMANY: (49) 89 95086 0 (Munich), UNITED KINGDOM: (44) 1344 865 900 (Ascot),
FRANCE: (33) 1 40 83 68 00 (Paris), SWEDEN: (46) 8 594 607 00 (Stockholm), FINLAND: (358) 9 3507670 (Helsinki),

ITALY: (39) 02 6608131 (Milan), SPAIN: (34) 1 807 1441 (Madrid)

Lucent Technologies Inc. reserves the right to make changes to the product(s) or information contained herein without notice. No liability is assumed as a result of their use or application. No rights under any patent accompany the sale of any such product(s) or information. Phone-On-A-Chip is a trademark of Lucent Technologies Inc.

Copyright © 2000 Lucent Technologies Inc. All Rights Reserved Printed in U.S.A.

**Lucent Technologies** 

microelectronics group





# **DSP1627 Digital Signal Processor**

### 1 Features

- Optimized for digital cellular applications with a bit manipulation unit for higher coding efficiency.
- On-chip, programmable, PLL clock synthesizer.
- 14 ns and 11 ns instruction cycle times at 5 V, 10 ns instruction cycle time at 3.0 V, and 20 ns and 12.5 ns instruction cycle times at 2.7 V, respectively.
- Mask-programmable memory map option: The DSP1627x36 features 36 Kwords on-chip ROM. The DSP1627x32 features 32 Kwords on-chip ROM and access to 16 Kwords external ROM in the same map. Both feature 6 Kwords on-chip, dual-port RAM and a secure option for on-chip ROM.
- Low power consumption:
  - <5.5 mW/MIPS typical at 5 V.</p>
  - <1.5 mW/MIPS typical at 2.7 V.
- Flexible power management modes:
  - Standard sleep: 0.5 mW/MIPS at 5 V.
     0.12 mW/MIPS at 2.7 V.
  - Sleep with slow internal clock: 1.4 mW at 5 V.
     0.4 mW at 2.7 V.
  - Hardware STOP (pin halts DSP): <20 μA.</p>
- Mask-programmable clock options: crystal oscillator, small signal, and CMOS.
- Low-profile TQFP package (1.5 mm) available.
- Sequenced accesses to X and Y external memory.
- Object code compatible with the DSP1617.
- Single-cycle squaring.
- 16 x 16-bit multiplication and 36-bit accumulation in one instruction cycle.
- Instruction cache for high-speed, program-efficient, zerooverhead looping.
- Dual 25 Mbits/s serial I/O ports with multiprocessor capability—16-bit data channel, 8-bit protocol channel.
- 8-bit parallel host interface:
  - Supports 8- or 16-bit transfers.
  - Motorola\* or Intel† compatible.
- 8-bit control I/O interface.
- 256 memory-mapped I/O ports.
- IEEE<sup>‡</sup> P1149.1 test port (JTAG boundary scan).
- \* Motorola is a registered trademark of Motorola, Inc.
- † Intel is a registered trademark of Intel Corp.
- ‡ IEEE is a registered trademark of The Institute of Electrical and Electronics Engineers, Inc.

- Full-speed in-circuit emulation hardware development system on-chip.
- Supported by DSP1627 software and hardware development tools.

# 2 Description

The DSP1627 is Lucent Technologies Microelectronics Group first digital signal processor offering 100 MIPS operation at 3.0 V and 80 MIPS operation at 2.7 V with a reduction in power consumption. Designed specifically for applications requiring low power dissipation in digital cellular systems, the DSP1627 is a signal-coding device that can be programmed to perform a wide variety of fixed-point signal processing functions. The device is based on the DSP1600 core with a bit manipulation unit for enhanced signal coding efficiency. The DSP1627 includes a mix of peripherals specifically intended to support processing-intensive but cost-sensitive applications in the area of digital wireless communications.

The DSP1627x36 contains 36 Kwords of internal ROM (IROM), but it doesn't support the use of IROM and external ROM (EROM) in the same memory map. The DSP1627x32 supports the use of 32 Kwords of IROM with 16 Kwords of EROM in the same map. Both devices contain 6 Kwords of dual-port RAM (DPRAM), which allows simultaneous access to two RAM locations in a single instruction cycle.

The DSP1627 is object code compatible with the DSP1617, while providing more memory and architectural enhancements including an on-chip clock synthesizer and an 8-bit parallel host interface for hardware flexibility.

The DSP1627 supports 2.7 V, 3.0 V, and 5 V operation and flexible power management modes required for portable cellular terminals. Several control mechanisms achieve low-power operation, including a STOP pin for placing the DSP into a fully static, halted state and a programmable power control register used to power down unused on-chip I/O units. These power management modes allow for trade-offs between power reduction and wake-up latency requirements. During system standby, power consumption is reduced to less than 20  $\mu\text{A}.$ 

The on-chip clock synthesizer can be driven by an external clock whose frequency is a fraction of the instruction rate.

The device is packaged in a 100-pin BQFP or a 100-pin TQFP and is available with 14 ns and 11 ns instruction cycle times at 5 V, 10 ns instruction cycle times at 3.0 V, and 20 ns and 12.5 ns instruction cycle times at 2.7 V, respectively.

# **Table of Contents**

Co	nten	ts Pa	age	Co	ontents Pag	ge
1	Featu	ıres	1		10.4 JTAG I/O Specifications	79
2	Desci	ription	1		10.5 Interrupt	
3	Pin In	formation	3		10.6 Bit Input/Output (BIO)	81
4	Hard	ware Architecture	. 7		10.7 External Memory Interface	
	4.1	DSP1627 Architectural Overview	7		10.8 PHIF Specifications	
	4.2	DSP1600 Core Architectural Overview	10		10.9 Serial I/O Specifications	
	4.3	Interrupts and Trap	11		10.10 Multiprocessor Communication	
	4.4	Memory Maps and Wait-States		11		
	4.5	External Memory Interface (EMI)	18		11.1 DSP Clock Generation	99
	4.6	Bit Manipulation Unit (BMU)			11.2 Reset Circuit 1	00
	4.7	Serial I/O Units (SIOs)	19		11.3 Reset Synchronization 1	01
	4.8	Parallel Host Interface (PHIF)			11.4 JTAG I/O Specifications 1	02
	4.9	Bit Input/Output Unit (BIO)			11.5 Interrupt 1	
	4.10	Timer			11.6 Bit Input/Output (BIO) 1	
	4.11	JTAG Test Port	24		11.7 External Memory Interface 1	
	4.12	Clock Synthesis	26		11.8 PHIF Specifications 1	09
	4.13	Power Management			11.9 Serial I/O Specifications 1	
5	Softw	rare Architecture			11.10 Multiprocessor Communication 1	20
	5.1	Instruction Set	36	12	2 Timing Characteristics for 2.7 V Operation 1	21
	5.2	Register Settings	45		12.1 DSP Clock Generation 1	22
	5.3	Instruction Set Formats			12.2 Reset Circuit 1	23
6	Signa	al Descriptions	61		12.3 Reset Synchronization 1	24
	6.1	System Interface			12.4 JTAG I/O Specifications 1	
	6.2	External Memory Interface			12.5 Interrupt 1	
	6.3	Serial Interface #1	64		12.6 Bit Input/Output (BIO) 1	27
	6.4	Parallel Host Interface or Serial			12.7 External Memory Interface 1	28
		Interface #2 and Control I/O Interface	65		12.8 PHIF Specifications 1	32
	6.5	Control I/O Interface	65		12.9 Serial I/O Specifications 1	38
	6.6	JTAG Test Interface	66		12.10 Multiprocessor Communication 1	43
7	Mask	-Programmable Options	67	13	3 Crystal Electrical Characteristics and	
	7.1	Input Clock Options	67		Requirements1	44
	7.2	Memory Map Options	67		13.1 External Components for the Crystal	
	7.3	ROM Security Options	67		Oscillator1	44
8	Devic	e Characteristics	68		13.2 Power Dissipation 1	44
	8.1	Absolute Maximum Ratings	68		13.3 LC Network Design for Third	
	8.2	Handling Precautions	68		Overtone Crystal Circuits 1	47
	8.3	Recommended Operating Conditions	68		13.4 Frequency Accuracy Considerations 1	49
	8.4	Package Thermal Considerations	69	14	1 Outline Diagrams 1	52
9	Electi	rical Characteristics and Requirements	70		14.1 100-Pin BQFP (Bumpered Quad	
	9.1	Power Dissipation	73		Flat Pack) 1	52
10	Timin	g Characteristics for 5 V Operation	75		14.2 100-Pin TQFP (Thin Quad Flat Pack) 1	53
	10.1	DSP Clock Generation	76			
	10.2	Reset Circuit	77			
	10.3	Reset Synchronization	78			

## 3 Pin Information




Figure 1. DSP1627 BQFP Pin Diagram

5-4218 (F).b

# 3 Pin Information (continued)




Figure 2. DSP1627 TQFP Pin Diagram

# 3 Pin Information (continued)

Functional descriptions of pins 1—100 are found in Section 6, Signal Descriptions. The functionality of pins 61 and 62 (TQFP pins 48 and 49) are mask-programmable (see Section 7, Mask-Programmable Options). Input levels on all I and I/O type pins are designed to remain at full CMOS levels when not driven by the DSP.

**Table 1. Pin Descriptions** 

BQFP Pin	TQFP Pin	Symbol	Туре			Name/Function			
1, 2, 3, 4,	88, 89, 90,	DB[15:0]	I/O*	External Mei	mory Data	Bus DB[15:0].			
5, 7, 8, 9,	91, 92, 94,								
10, 11, 12,	95, 96, 97,								
15, 16, 17,	98, 99, 2,								
18, 19	3, 4, 5, 6								
20	7	Ю	O <sup>†</sup>			to 0x40FF I/O Enable.			
21	8	ERAMHI	O <sup>†</sup>			to 0xFFFF External RAM Enable			
23	10	ERAMLO	O <sup>†</sup>			to 0x7FFF External RAM Enable	).		
24	11	EROM	O <sup>†</sup>			rnal ROM Enable.			
25	12	RWN	O <sup>†</sup>	Read/Write I	Not.				
27	14	EXM		External RO	M Enable.				
28, 29, 31,	15, 16, 18,	AB[15:0]	O*	External Mei	mory Addr	ess Bus 15—0.			
32, 33, 34,	19, 20, 21,								
35, 36, 37,	22, 23, 24,								
40, 41, 42,	27, 28, 29,								
43, 44, 45,	30, 31, 32,								
46	33								
47	34	INT1		Vectored Inte	•				
48	35	INT0	I	Vectored Inte	•				
50	37	IACK	0*	Interrupt Ack		•			
51	38	STOP	I	STOP Input					
52	39	TRAP	I/O*		e Program	Trap/Breakpoint Indication.			
53	40	RSTB	I.	Reset Bar.					
54	41	CKO	O <sup>†</sup>	Processor C	•	ıt.			
56	43	TCK	ı	JTAG Text C					
57	44	TMS	<b> </b> ‡	JTAG Test N					
58	45	TDO	O§	JTAG Test D	•	t.			
59	46	TDI	l‡	JTAG Test D	-				
						ammable Input Clock Option			
				CMOS	Small	Crystal	01/00		
		Oldina		010	Signal	Oscillator	CMOS		
61	48	CKI**	<u> </u>	CKI	VAC	XLO, 10 pF capacitor to Vss	CKI		
62	49	CKI2**	1/0*	VSSA VCM XHI, 10 pF capacitor to Vss Open					
65	52	VEC0/IOBIT7	I/O*	' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '					
66	53	VEC1/IOBIT6	I/O*	Vectored Interrupt Indication 1/Status/Control Bit 6.					
67	54	VEC2/IOBIT5	I/O*	Vectored Interrupt Indication 2/Status/Control Bit 5.					
68	55	VEC3/IOBIT4	I/O*	Vectored Interrupt Indication 3/Status/Control Bit 4.					

<sup>3</sup>-states when RSTB = 0, or by JTAG control.

<sup>† 3-</sup>states when RSTB = 0 and INT0 = 1. Output = 1 when RSTB = 0 and INT0 = 0, except CKO which is free-running.

<sup>‡</sup> Pull-up devices on input.

<sup>§ 3-</sup>states by JTAG control.

\*\* See Section 7. Mask-Proc See Section 7, Mask-Programmable Options.

<sup>††</sup> For SIO multiprocessor applications, add 5 k $\Omega$  external pull-up resistors to SADD1 and/or SADD2 for proper initialization.

# 3 Pin Information (continued)

Functional descriptions of pins 1—100 are found in Section 6, Signal Descriptions.

Table 1. Pin Descriptions (continued)

BQFP Pin	TQFP Pin	Symbol	Туре	Name/Function
69	56	IOBIT3/PB7	I/O*	Status/Control Bit 3/PHIF Data Bus Bit 7.
70	57	IOBIT2/PB6	I/O*	Status/Control Bit 2/PHIF Data Bus Bit 6.
71	58	IOBIT1/PB5	I/O*	Status/Control Bit 1/PHIF Data Bus Bit 5.
72	59	IOBIT0/PB4	I/O*	Status/Control Bit 0/PHIF Data Bus Bit 4.
74	61	SADD2/PB3 <sup>††</sup>	I/O*	SIO2 Multiprocessor Address/PHIF Data Bus Bit 3.
75	62	DOEN2/PB2	I/O*	SIO2 Data Output Enable/PHIF Data Bus Bit 2.
77	64	DI2/PB1	I/O*	SIO2 Data Input/PHIF Data Bus Bit 1.
78	65	ICK2/PB0	I/O*	SIO2 Input Clock/PHIF Data Bus Bit 0.
79	66	OBE2/POBE	O*	SIO2 Output Buffer Empty/PHIF Output Buffer Empty.
80	67	IBF2/PIBF	O*	SIO2 Input Buffer Full/PHIF Input Buffer Full.
81	68	OLD2/PODS	I/O*	SIO2 Output Load/PHIF Output Data Strobe.
82	69	ILD2/PIDS	I/O*	SIO2 Input Load/PHIF Input Data Strobe.
83	70	SYNC2/PBSEL	I/O*	SIO2 Multiprocessor Synchronization/PHIF Byte Select.
84	71	DO2/PSTAT	I/O*	SIO2 Data Output/PHIF Status Register Select.
85	72	OCK2/PCSN	I/O*	SIO2 Output Clock/PHIF Chip Select Not.
86	73	DOEN1	I/O*	SIO1 Data Output Enable.
87	74	SADD1 <sup>††</sup>	I/O*	SIO1 Multiprocessor Address.
90	77	SYNC1	I/O*	SIO1 Multiprocessor Synchronization.
91	78	DO1	O*	SIO1 Data Output.
92	79	OLD1	I/O*	SIO1 Output Load.
93	80	OCK1	I/O*	SIO1 Output Clock.
94	81	ICK1	I/O*	SIO1 Input Clock.
95	82	ILD1	I/O*	SIO1 Input Load.
96	83	DI1	I	SIO1 Data Input.
98	85	IBF1	O*	SIO1 Input Buffer Full.
99	86	OBE1	O*	SIO1 Output Buffer Empty.
6, 15, 26,	93, 1, 13,	Vss	Р	Ground.
38, 49, 64,	25, 36, 51,			
76, 89, 97	63, 76, 84			
14, 22, 30,	100, 9, 17,	VDD	Р	Power Supply.
39, 55, 73,	26, 42, 60,			
88, 100	75, 87	\/pp.		Analan Dawar Cunniy
60	47	VDDA	Р	Analog Power Supply.
63	50	Vssa	Р	Analog Ground.

<sup>3</sup>-states when RSTB = 0, or by JTAG control.

 $<sup>\</sup>dagger$  3-states when RSTB = 0 and INT0 = 1. Output = 1 when RSTB = 0 and INT0 = 0.

<sup>§</sup> Pull-up devices on input.

<sup>3-</sup>states by JTAG control.\*\* See Section 7, Mask-Programmable Options.

<sup>††</sup> For SIO multiprocessor applications, add 5 k $\Omega$  external pull-up resistors to SADD1 and/or SADD2 for proper initialization.

## **4 Hardware Architecture**

The DSP1627 device is a 16-bit, fixed-point programmable digital signal processor (DSP). The DSP1627 consists of a DSP1600 core together with on-chip memory and peripherals. Added architectural features give the DSP1627 high program efficiency for signal coding applications.

#### 4.1 DSP1627 Architectural Overview

Figure 3 shows a block diagram of the DSP1627. The following modules make up the DSP1627.

#### DSP1600 Core

The DSP1600 core is the heart of the DSP1627 chip. The core contains data and address arithmetic units, and control for on-chip memory and peripherals. The core provides support for external memory wait-states and on-chip, dual-port RAM and features vectored interrupts and a trap mechanism.

#### **Dual-Port RAM (DPRAM)**

This module contains six banks of zero wait-state memory. Each bank consists of 1K 16-bit words and has separate address and data ports to the instruction/coefficient and data memory spaces. A program can reference memory from either space. The DSP1600 core automatically performs the required multiplexing. If references to both ports of a single bank are made simultaneously, the DSP1600 core automatically inserts a wait-state and performs the data port access first, followed by the instruction/coefficient port access.

A program can be downloaded from slow, off-chip memory into DPRAM, and then executed without wait-states. DPRAM is also useful for improving convolution performance in cases where the coefficients are adaptive. Since DPRAM can be downloaded through the JTAG port, full-speed remote in-circuit emulation is possible. DPRAM can also be used for downloading self-test code via the JTAG port.

#### Read-Only Memory (ROM)

The DSP1627x36 contains 36K 16-bit words of zero wait-state mask-programmable ROM for program and fixed coefficients. Similarly, the DSP1627x32 has 32K 16-bit words of ROM and access to 16 Kwords of external ROM.

#### **External Memory Multiplexer (EMUX)**

The EMUX is used to connect the DSP1627 to external memory and I/O devices. It supports read/write operations from/to instruction/coefficient memory (X memory space) and data memory (Y memory space). The DSP1600 core automatically controls the EMUX. Instructucent Technologies Inc.

tions can transparently reference external memory from either set of internal buses. A sequencer allows a single instruction to access both the X and the Y external memory spaces.

## **Clock Synthesis**

The DSP powers up with a 1X input clock (CKI/CKI2) as the source for the processor clock. An on-chip clock synthesizer (PLL) can also be used to generate the system clock for the DSP, which will run at a frequency multiple of the input clock. The clock synthesizer is deselected and powered down on reset. For low-power operation, an internally generated slow clock can be used to drive the DSP. If both the clock synthesizer and the internally generated slow clock are selected, the slow clock will drive the DSP; however, the synthesizer will continue to run.

The clock synthesizer and other programmable clock sources are discussed in Section 4.12. The use of these programmable clock sources for power management is discussed in Section 4.13.

### Bit Manipulation Unit (BMU)

The BMU extends the DSP1600 core instruction set to provide more efficient bit operations on accumulators. The BMU contains logic for barrel shifting, normalization, and bit field insertion/extraction. The unit also contains a set of 36-bit alternate accumulators. The data in the alternate accumulators can be shuffled with the data in the main accumulators. Flags returned by the BMU mesh seamlessly with the DSP1600 conditional instructions.


#### **Bit Input/Output (BIO)**

The BIO provides convenient and efficient monitoring and control of eight individually configurable pins. When configured as outputs, the pins can be individually set, cleared, or toggled. When configured as inputs, individual pins or combinations of pins can be tested for patterns. Flags returned by the BIO mesh seamlessly with conditional instructions.

#### Serial Input/Output Units (SIO and SIO2)

SIO and SIO2 offer asynchronous, full-duplex, double-buffered channels that operate at up to 25 Mbits/s (for 20 ns instruction cycle in a nonmultiprocessor configuration), and easily interface with other Lucent Technologies fixed-point DSPs in a multiple-processor environment. Commercially available codecs and time-division multiplex (TDM) channels can be interfaced to the serial I/O ports with few, if any, additional components. SIO2 is identical to SIO.

An 8-bit serial protocol channel may be transmitted in addition to the address of the called processor in multiprocessor mode. This feature is useful for transmitting high-level framing information or for error detection and correction. SIO2 and BIO are pin-multiplexed with the PHIF.



5-4142 (F).f

- \* These registers are accessible through the pins only.
- $\dagger$  36K x 16 for the DSP1627x36; 32K x 16 for the DSP1627x32.

Figure 3. DSP1627 Block Diagram

Table 2. DSP1627 Block Diagram Legend

Symbol	Name
aa<0—1>	Alternate Accumulators.
ar<0—3>	Auxiliary BMU Registers.
BIO	Bit Input/Output Unit.
BMU	Bit Manipulation Unit.
BREAKPOINT	Four Instruction Breakpoint Registers.
BYPASS	JTAG Bypass Register.
cbit	Control Register for BIO.
EMUX	External Memory Multiplexer.
HDS	Hardware Development System.
ID	JTAG Device Identification Register.
IDB	Internal Data Bus.
ioc	I/O Configuration Register.
JCON	JTAG Configuration Registers.
jtag	16-bit Serial/Parallel Register.
pdx0(in)	Parallel Data Transmit Input Register 0.
pdx0(out)	Parallel Data Transmit Output Register 0.
PHIF	Parallel Host Interface.
phifc	Parallel Host Interface Control Register.
pllc	Phase-Locked Loop Control Register.
powerc	Power Control Register.
PSTAT	Parallel Host Interface Status Register.
ROM	Internal ROM (36 Kwords for DSP1627x36, 32 Kwords for DSP1627x32).
saddx	Multiprocessor Protocol Register.
saddx2	Multiprocessor Protocol Register for SIO2.
sbit	Status Register for BIO.
sdx(in)	Serial Data Transmit Input Register.
sdx2(in)	Serial Data Transmit Input Register for SIO2.
sdx(out)	Serial Data Transmit Output Register.
sdx2(out)	Serial Data Transmit Output Register for SIO2.
SIO	Serial Input/Output Unit.
SIO2	Serial Input/Output Unit #2.
sioc	Serial I/O Control Register.
sioc2	Serial I/O Control Register for SIO2.
srta	Serial Receive/Transmit Address Register.
srta2	Serial Receive/Transmit Address Register for SIO2.
tdms	Serial I/O Time-division Multiplex Signal Control Register.
tdms2	Serial I/O Time-division Multiplex Signal Control Register for SIO2.
TIMER	Programmable Timer.
timer0	Timer Running Count Register.
timerc	Timer Control Register.
TRACE	Program Discontinuity Trace Buffer.
XAB	Program Memory Address Bus.
XDB	Program Memory Data Bus.
YAB	Data Memory Address Bus.
YDB	Data Memory Data Bus.

#### Parallel Host Interface (PHIF)

The PHIF is a passive, 8-bit parallel port which can interface to an 8-bit bus containing other Lucent Technologies DSPs (e.g., DSP1620, DSP1627, DSP1628, DSP1629, DSP1611, DSP1616, DSP1617, DSP1618), microprocessors, or peripheral I/O devices. The PHIF port supports either *Motorola* or *Intel* protocols, as well as 8-bit or 16-bit transfers, configured in software. The port data rate depends upon the instruction cycle rate. A 25 ns instruction cycle allows the PHIF to support data rates up to 11.85 Mbytes/s, assuming the external host device can transfer 1 byte of data in 25 ns.

The PHIF is accessed in two basic modes: 8-bit or 16-bit mode. In 16-bit mode, the host determines an access of the high or low byte. In 8-bit mode, only the low byte is accessed. Software-programmable features allow for a glueless host interface to microprocessors (see Section 4.8, Parallel Host Interface).

#### **Timer**

The timer can be used to provide an interrupt at the expiration of a programmed interval. The interrupt may be single or repetitive. More than nine orders of magnitude of interval selection are provided. The timer may be stopped and restarted at any time.

### Hardware Development System (HDS) Module

The on-chip HDS performs instruction breakpointing and branch tracing at full speed without additional off-chip hardware. Using the JTAG port, the breakpointing is set up, and the trace history is read back. The port works in conjunction with the HDS code in the on-chip ROM and the hardware and software in a remote computer. The HDS code must be linked to the user's application code and reside in the first 4 Kwords of ROM. The on-chip HDS cannot be used with the secure ROM masking option (see Section 7.3, ROM Security Options).

Four hardware breakpoints can be set on instruction addresses. A counter can be preset with the number of breakpoints to receive before trapping the core. Breakpoints can be set in interrupt service routines. Alternately, the counter can be preset with the number of cache instructions to execute before trapping the core.

Every time the program branches instead of executing the next sequential instruction, the addresses of the instructions executed before and after the branch are caught in circular memory. The memory contains the last four pairs of program discontinuities for hardware tracing. In systems with multiple processors, the processors may be configured such that any processor reaching a breakpoint will cause all the other processors to be trapped (see Section 4.3, Interrupts and Trap).

### **Pin Multiplexing**

In order to allow flexible device interfacing while maintaining a low package pin count, the DSP1627 multiplexes 16 package pins between BIO, PHIF, VEC[3:0], and SIO2.

Upon reset, the vectored interrupt indication signals, VEC[3:0], are connected to the package pins while IOBIT[4:7] are disconnected. Setting bit 12, EBIOH, of the ioc register connects IOBIT[4:7] to the package pins and disconnects VEC[3:0].

Upon reset, the parallel host interface (PHIF) is connected to the package pins while the second serial port (SIO2) and IOBIT[3:0] are disconnected. Setting bit 10, ESIO2, of the ioc register connects the SIO2 and IOBIT[3:0] and disconnects the PHIF.

### **Power Management**

Many applications, such as portable cellular terminals, require programmable sleep modes for power management. There are three different control mechanisms for achieving low-power operation: the powerc control register, the STOP pin, and the AWAIT bit in the alf register. The AWAIT bit in the alf register allows the processor to go into a power-saving standby mode until an interrupt occurs. The powerc register configures various power-saving modes by controlling internal clocks and peripheral I/O units. The STOP pin controls the internal processor clock. The various power management options may be chosen based on power consumption and/or wake-up latency requirements.

#### 4.2 DSP1600 Core Architectural Overview

Figure 4 shows a block diagram of the DSP1600 core.

### System Cache and Control Section (SYS)

This section of the core contains a 15-word cache memory and controls the instruction sequencing. It handles vectored interrupts and traps, and also provides decoding for registers outside of the DSP1600 core. SYS stretches the processor cycle if wait-states are required (wait-states are programmable for external memory accesses). SYS sequences downloading via JTAG of self-test programs to on-chip, dual-port RAM.

The cache loop iteration count can be specified at run time under program control as well as at assembly time.

### Data Arithmetic Unit (DAU)

The data arithmetic unit (DAU) contains a 16 x 16-bit parallel multiplier that generates a full 32-bit product in one instruction cycle. The product can be accumulated with one of two 36-bit accumulators. The accumulator data can be directly loaded from, or stored to, memory in two 16-bit words with optional saturation on overflow. The arithmetic logic unit (ALU) supports a full set of arithmetic and logical operations on either 16- or 32-bit data. A standard set of flags can be tested for conditional ALU operations, branches, and subroutine calls. This procedure allows the processor to perform as a powerful 16- or 32-bit microprocessor for logical and control applications. The available instruction set is fully compatible with the DSP1617 instruction set. See Section 5.1 for more information on the instruction set.

The user also has access to two additional DAU registers. The psw register contains status information from the DAU (see Table 26, Processor Status Word Register). The arithmetic control register, auc, is used to configure some of the features of the DAU (see Table 27) including single-cycle squaring. The auc register alignment field supports an arithmetic shift left by one and left or right by two. The auc register is cleared by reset.

The counters c0 to c2 are signed, 8 bits wide, and may be used to count events such as the number of times the program has executed a sequence of code. They are controlled by the conditional instructions and provide a convenient method of program looping.

### Y Space Address Arithmetic Unit (YAAU)

The YAAU supports high-speed, register-indirect, compound, and direct addressing of data (Y) memory. Four general-purpose, 16-bit registers, r0 to r3, are available in the YAAU. These registers can be used to supply the read or write addresses for Y space data. The YAAU also decodes the 16-bit data memory address and outputs individual memory enables for the data access. The YAAU can address the six 1 Kword banks of onchip DPRAM or three external data memory segments. Up to 48 Kwords of off-chip RAM are addressable, with 16K addresses reserved for internal RAM.

Two 16-bit registers, rb and re, allow zero-overhead modulo addressing of data for efficient filter implementations. Two 16-bit signed registers, j and k, are used to hold user-defined postmodification increments. Fixed increments of +1, -1, and +2 are also available. Four compound-addressing modes are provided to make read/write operations more efficient.

The YAAU allows direct (or indexed) addressing of data memory. In direct addressing, the 16-bit base register (ybase) supplies the 11 most significant bits of the address. The direct data instruction supplies the remaining 5 bits to form an address to Y memory space and also specifies one of 16 registers for the source or destination.

#### X Space Address Arithmetic Unit (XAAU)

The XAAU supports high-speed, register-indirect, instruction/coefficient memory addressing with postmodification of the register. The 16-bit pt register is used for addressing coefficients. The signed register i holds a user-defined postincrement. A fixed postincrement of +1 is also available. Register PC is the program counter. Registers pr and pi hold the return address for subroutine calls and interrupts, respectively.


The XAAU decodes the 16-bit instruction/coefficient address and produces enable signals for the appropriate X memory segment. The addressable X segments are internal ROM (up to 36 Kwords for the DSP1627x36, up to 32 Kwords for the DSP1627x32), six 1K banks of DPRAM, and external ROM.

The locations of these memory segments depend upon the memory map selected (see Table 5). A security mode can be selected by mask option. This prevents unauthorized access to the contents of on-chip ROM (see Section 7, Mask-Programmable Options).

## 4.3 Interrupts and Trap

The DSP1627 supports prioritized, vectored interrupts and a trap. The device has eight internal hardware sources of program interrupt and two external interrupt pins. Additionally, there is a trap pin and a trap signal from the hardware development system (HDS). A software interrupt is available through the **icall** instruction. The **icall** instruction is reserved for use by the HDS. Each of these sources of interrupt and trap has a unique vector address and priority assigned to it. DSP16A interrupt compatibility is not maintained.

The software interrupt and the traps are always enabled and do not have a corresponding bit in the ins register. Other vectored interrupts are enabled in the inc register (see Table 29, Interrupt Control (inc) Register) and monitored in the ins register (see Table 30, Interrupt Status (ins) Register). When the DSP1627 goes into an interrupt or trap service routine, the IACK pin is asserted. In addition, pins VEC[3:0] encode which interrupt/ trap is being serviced. Table 4 details the encoding used for VEC[3:0].



5-1741 (F).b

Figure 4. DSP1600 Core Block Diagram

Table 3. DSP1600 Core Block Diagram Legend

Symbol	Name
16 x 16 MPY	16-bit x 16-bit Multiplier.
a0—a1	Accumulators 0 and 1 (16-bit halves specified as a0, a0l, a1, and a1l)*.
alf	AWAIT, LOWPR, Flags.
ALU/SHIFT	Arithmetic Logic Unit/Shifter.
auc	Arithmetic Unit Control.
c0—c2	Counters 0—2.
cloop	Cache Loop Count.
CMP	Comparator.
DAU	Digital Arithmetic Unit.
i	Increment Register for the X Address Space.
IDB	Internal Data Bus.
inc	Interrupt Control.
ins	Interrupt Status.
j	Increment Register for the Y Address Space.
k	Increment Register for the Y Address Space.
MUX	Multiplexer.
mwait	External Memory Wait-states Register.
р	Product Register (16-bit halves specified as p, pl).
PC	Program Counter.
pi	Program Interrupt Return Register.
pr	Program Return Register.
psw	Processor Status Word.
pt	X Address Space Pointer.
r0—r3	Y Address Space Pointers.
rb	Modulo Addressing Register (begin address).
re	Modulo Addressing Register (end address).
SYS	System Cache and Control Section.
X	Multiplier Input Register.
XAAU	X Space Address Arithmetic Unit.
XAB	X Space Address Bus.
XDB	X Space Data Bus.
YAAU	Y Space Address Arithmetic Unit.
YAB	Y Space Address Bus.
YDB	Y Space Data Bus.
ybase	Direct Addressing Base Register.
у	DAU Register (16-bit halves specified as y, yl).

<sup>\*</sup> F3 ALU instructions with immediates require specifying the high half of the accumulators as a0h and a1h.

### Interruptibility

Vectored interrupts are serviced only after the execution of an interruptible instruction. If more than one vectored interrupt is asserted at the same time, the interrupts are serviced sequentially according to their assigned priorities. See Table 4 for the priorities assigned to the vectored interrupts. Interrupt service routines, branch and conditional branch instructions, cache loops, and instructions that only decrement one of the RAM pointers, r0 to r3 (e.g., \*r3--), are not interruptible.

A trap is similar to an interrupt, but it gains control of the processor by branching to the trap service routine even when the current instruction is noninterruptible. It may not be possible to return to normal instruction execution from the trap service routine since the machine state cannot always be saved. In particular, program execution cannot be continued from a trapped cache loop or interrupt service routine. While in a trap service routine, another trap is ignored.

When set to 1, the status bits in the ins register indicate that an interrupt has occurred. The processor must reach an interruptible state (completion of an interruptible instruction) before an enabled vectored interrupt will be acted on. An interrupt will not be serviced if it is not enabled. Polled interrupt service can be implemented by disabling the interrupt in the inc register and then polling the ins register for the expected event.

## **Vectored Interrupts**

Tables 29 and 30 show the inc and ins registers. A logic 1 written to any bit of inc enables (or unmasks) the associated interrupt. If the bit is cleared to a logic 0, the interrupt is masked. Note that neither the software interrupt nor traps can be masked.

The occurrence of an interrupt that is not masked will cause the program execution to transfer to the memory location pointed to by that interrupt's vector address, assuming no other interrupt is being serviced (see Table 4, Interrupt Vector Table). The occurrence of an interrupt that is masked causes no automatic processor action, but will set the corresponding status bit in the ins register. If a masked interrupt occurs, it is latched in the ins register, but the interrupt is not taken. When unlatched, this latched interrupt will initiate automatic processor interrupt action. See the DSP1611/17/18/27 Digital Signal Processor Information Manual for a more detailed description of the interrupts.

### Signaling Interrupt Service Status

Five pins of DSP1627 are devoted to signaling interrupt service status. The IACK pin goes high while any interrupt or user trap is being serviced, and goes low when the ireturn instruction from the service routine is issued. Four pins, VEC[3:0], carry a code indicating which of the interrupts or trap is being serviced. Table 4 contains the encodings used by each interrupt.

Traps due to HDS breakpoints have no effect on either the IACK or VEC[3:0] pins. Instead, they show the interrupt state or interrupt source of the DSP when the trap occurred.

#### **Clearing Interrupts**

The PHIF interrupts (PIBF and POBE) are cleared by reading or writing the parallel host interface data transmit registers pdx0[in] and pdx0[out], respectively. The SIO and SIO2 interrupts (IBF, IBF2, OBE, and OBE2) are cleared by reading or writing, as appropriate, the serial data registers sdx[in], sdx2[in], sdx[out], and sdx2[out]. The JTAG interrupt (JINT) is cleared by reading the jtag register.

Three of the vectored interrupts are cleared by writing to the ins register. Writing a 1 to the INTO, INT1, or TIME bits in the ins will cause the corresponding interrupt status bit to be cleared to a logic 0. The status bit for these vectored interrupts is also cleared when the ireturn instruction is executed, leaving set any other vectored interrupts that are pending.

# **Traps**

The TRAP pin of the DSP1627 is a bidirectional signal. At reset, it is configured as an input to the processor. Asserting the TRAP pin will force a user trap. The trap mechanism is used for two purposes. It can be used by an application to rapidly gain control of the processor for asynchronous time-critical event handling (typically for catastrophic error recovery). It is also used by the HDS for breakpointing and gaining control of the processor. Separate vectors are provided for the user trap (0x46) and the HDS trap (0x3). Traps are not maskable.

**Table 4. Interrupt Vector Table** 

Source	Vector	Priority	VEC[3:0]	Issued by
No Interrupt	_	_	0x0	_
Software Interrupt	0x2	1	0x1	icall
INT0	0x1	2	0x2	pin
JINT	0x42	3	0x8	jtag in
INT1	0x4	4	0x9	pin
TIME	0x10	7	0xc	timer
IBF2	0x14	8	0xd	SIO2 in
OBE2	0x18	9	0xe	SIO2 out
Reserved	0x1c	10	0x0	_
Reserved	0x20	11	0x1	_
Reserved	0x24	12	0x2	_
IBF	0x2c	14	0x3	SIO in
OBE	0x30	15	0x4	SIO out
PIBF	0x34	16	0x5	PHIF in
POBE	0x38	17	0x6	PHIF out
TRAP from HDS	0x3	18	_*	breakpoint, jtag, or pin
TRAP from User	0x46	19 = highest	0x7	pin

<sup>\*</sup> Traps due to HDS breakpoints have no effect on VEC[3:0] pins.

A trap has four cycles of latency. At most, two instructions will execute from the time the trap is received at the pin to when it gains control. An instruction that is executing when a trap occurs is allowed to complete before the trap service routine is entered. (Note that the instruction could be lengthened by wait-states.) During normal program execution, the pi register contains either the address of the next instruction (two-cycle instruction executing) or the address following the next instruction (one-cycle instruction executing). In an interrupt service routine, pi contains the interrupt return address. When a trap occurs during an interrupt service routine, the value of the pi register may be overwritten. Specifically, it is not possible to return to an interrupt service routine from a user trap (0x46) service routine. Continuing program execution when a trap occurs during a cache loop is also not possible.

The HDS trap causes circuitry to force the program memory map to MAP1 (with on-chip ROM starting at address 0x0) when the trap is taken. The previous memory map is restored when the trap service routine exits by issuing an ireturn. The map is forced to MAP1 because the HDS code, if present, resides in the on-chip ROM.

Using the Lucent Technologies development tools, the TRAP pin may be configured to be an output, or an input vectoring to address 0x3. In a multiprocessor environment, the TRAP pins of all the DSPs present can be tied together. During HDS operations, one DSP is selected by the host software to be the master. The master processor's TRAP pin is configured to be an output.

The TRAP pins of the slave processors are configured as inputs. When the master processor reaches a breakpoint, the master's TRAP pin is asserted. The slave processors will respond to their TRAP input by beginning to execute the HDS code.

### **AWAIT Interrupt (Standby or Sleep Mode)**

Setting the AWAIT bit (bit 15) of the alf register (alf = 0x8000) causes the processor to go into a power-saving standby or sleep mode. Only the minimum circuitry on the chip required to process an incoming interrupt remains active. After the AWAIT bit is set, one additional instruction will be executed before the stand-by power-saving mode is entered. A PHIF or SIO word transfer will complete if already in progress. The AWAIT bit is reset when the first interrupt occurs. The chip then wakes up and continues executing.

Two **nop** instructions should be programmed after the AWAIT bit is set. The first **nop** (one cycle) will be executed before sleeping; the second will be executed after the interrupt signal awakens the DSP and before the interrupt service routine is executed.

The AWAIT bit should be set from within the cache if the code which is executing resides in external ROM where more than one wait-state has been programmed. This ensures that an interrupt will not disturb the device from completely entering the sleep state.

For additional power savings, set ioc = 0x0180 and timerc = 0x0040 in addition to setting alf = 0x8000. This will hold the CKO pin low and shut down the timer and prescaler (see Table 38 and Table 31).

For a description of the control mechanisms for putting the DSP into low-power modes, see Section 4.13, Power Management.

# 4.4 Memory Maps and Wait-States

The DSP1600 core implements a modified Harvard architecture that has separate on-chip 16-bit address and data buses for the instruction/coefficient (X) and data (Y) memory spaces. Table 5 shows the instruction/coefficient memory space maps for both the DSP1627x36 and DSP1627x32.

The differences between the x36 and x32 memory maps can be seen by comparing the respective MAP1 and MAP3. For instance, MAP1 of the x36 provides for 36 Kwords of IROM and 6 Kwords of dual-port RAM (DPRAM), whereas MAP1 of the x32 provides for 32 Kwords of IROM, 6 Kwords of DPRAM, and 16 Kwords of EROM.

The DSP1627 provides a multiplexed external bus which accesses external RAM (ERAM) and ROM (EROM). Programmable wait-states are provided for external memory accesses. The instruction/coefficient memory map is configurable to provide application flexibility. Table 6 shows the data memory space, which has one map.

### **Instruction/Coefficient Memory Map Selection**

In determining which memory map to use, the processor evaluates the state of two parameters. The first is the LOWPR bit (bit 14) of the alf register. The LOWPR bit of the alf register is initialized to 0 automatically at reset. LOWPR controls the starting address in memory assigned to the six 1K banks of dual-port RAM. If LOWPR is low, internal dual-port RAM begins at address 0xC000. If LOWPR is high, internal dual-port RAM begins at address 0x0. LOWPR also moves IROM from 0x0 in MAP1 to 0x4000 in MAP3, and EROM from 0x0 in MAP2 to 0x4000 in MAP4.

The second parameter is the value at reset of the EXM pin (pin 27 or pin 14, depending upon the package type). EXM determines whether the internal 36 Kwords ROM (IROM) will be addressable in the memory map.

The Lucent Technologies development system tools, together with the on-chip HDS circuitry and the JTAG port, can independently set the memory map. Specifically, during an HDS trap, the memory map is forced to

MAP1. The user's map selection is restored when the trap service routine has completed execution.

#### MAP1

MAP1 has the IROM starting at 0x0 and six 1 Kword banks of DPRAM starting at 0xC000. Additionally, MAP1 for the x32 has 16 Kwords of EROM starting at 0x8000. MAP1 is used if DSP1627 has EXM low at reset and the LOWPR parameter is programmed to zero. It is also used during an HDS trap.

#### MAP2

MAP2 differs from MAP1 in that the lowest 48 Kwords reference external ROM (EROM). MAP2 is used if EXM is high at reset, the LOWPR parameter is programmed to zero, and an HDS trap is not in progress.

#### MAP3

MAP3 has the six 1 Kword banks of DPRAM starting at address 0x0. In MAP3 of the x36, the 36 Kwords of IROM start at 0x4000. Similarly, for the x32, 32 Kwords of IROM start at 0x4000. Additionally, MAP3 for the x32 has 16 Kwords of EROM starting at 0xC000. MAP3 is used if EXM is low at reset, the LOWPR bit is programmed to 1, and an HDS trap is not in progress. Note that this map is not available if the secure mask-programmable option has been ordered.

#### MAP4

MAP4 differs from MAP3 in that addresses above 0x4000 reference external ROM (EROM). This map is used if the LOWPR bit is programmed to 1, an HDS trap is not in progress, and, either EXM is high during reset, or the secure mask-programmable option has been ordered.

Whenever the chip is reset using the RSTB pin, the default memory map will be MAP1 or MAP2, depending upon the state of the EXM pin at reset. A reset through the HDS will not reinitialize the alf register, so the previous memory map is retained.

#### **Boot from External ROM**

After RSTB goes from low to high, the DSP1627 comes out of reset and fetches an instruction from address zero of the instruction/coefficient space. The physical location of address zero is determined by the memory map in effect. If EXM is high at the rising edge of RSTB, MAP2 is selected. MAP2 has EROM at location zero; thus, program execution begins from external memory. If EXM is high and INT1 is low when RSTB rises, the mwait register defaults to 15 wait-states for all external memory segments. If INT1 is high, the mwait register defaults to 0 wait-states.

**Table 5. Instruction/Coefficient Memory Maps** 

## DSP1627x36

X Address	AB[0:15]	MAP 1* EXM = 0 LOWPR = 0 <sup>†</sup>	MAP 2 EXM = 1 LOWPR = 0	MAP 3 <sup>‡</sup> EXM = 0 LOWPR = 1	MAP 4 EXM = 1 LOWPR = 1
0	0x0000	IROM	EROM	DPRAM	DPRAM
4K	0x1000	(36K)	(48K)	(6K)	(6K)
6K	0x1800			Reserved	Reserved
12K	0x3000			(10K)	(10K)
16K	0x4000			IROM	EROM
20K	0x5000			(36K)	(48K)
24K	0x6000				
28K	0x7000				
32K	0x8000				
36K	0x9000	Reserved			
40K	0xA000	(12K)			
44K	0xB000				
48K	0xC000	DPRAM	DPRAM		
52K	0xD000	(6K)	(6K)	Reserved	
54K	0xD800	Reserved	Reserved	(12K)	
56K	0xE000	(10K)	(10K)		
60K—64K	0xFFFF				

<sup>\*</sup> MAP1 is set automatically during an HDS trap. The user-selected map is restored at the end of the HDS trap service routine.

### DSP1627x32

X Address	AB[0:15]	MAP 1* EXM = 0 LOWPR = 0 <sup>†</sup>	MAP 2 EXM = 1 LOWPR = 0	MAP 3 <sup>‡</sup> EXM = 0 LOWPR = 1	MAP 4 EXM = 1 LOWPR = 1
0	0x0000	IROM	EROM	DPRAM	DPRAM
4K	0x1000	(32K)	(48K)	(6K)	(6K)
6K	0x1800			Reserved	Reserved
12K	0x3000			(10K)	(10K)
16K	0x4000	]		IROM	EROM
20K	0x5000	]		(32K)	(48K)
24K	0x6000	]			
28K	0x7000				
32K	0x8000	EROM			
36K	0x9000	(16K)			
40K	0xA000				
44K	0xB000				
48K	0xC000	DPRAM	DPRAM	EROM	
52K	0xD000	(6K)	(6K)	(16K)	
54K	0xD800	Reserved	Reserved		
56K	0xE000	(10K)	(10K)		
60K—64K	0xFFFF				

<sup>\*</sup> MAP1 is set automatically during an HDS trap. The user-selected map is restored at the end of the HDS trap service routine.

<sup>†</sup> LOWPR is an alf register bit. The Lucent Technologies development system tools can independently set the memory map.

<sup>‡</sup> MAP3 is not available if the secure mask-programmable option is selected.

<sup>†</sup> LOWPR is an alf register bit. The Lucent Technologies development system tools can independently set the memory map.

<sup>‡</sup> MAP3 is not available if the secure mask-programmable option is selected.

#### **Data Memory Mapping**

Table 6. Data Memory Map (Not to Scale)

Decimal Address	Address in r0, r1, r2, r3	Segment
0	0x0000	DPRAM[1:6]
6K	0x1800	Reserved (10K)
16K	0x4000	Ю
16,640	0x4100	ERAMLO
32K	0x8000	ERAMHI
64K – 1	0xFFFF	

On the data memory side (see Table 6), the six 1K banks of dual-port RAM are located starting at address 0. Addresses from 0x4000 to 0x40FF reference a 256-word memory-mapped I/O segment (IO). Addresses from 0x4100 to 0x7FFF reference the low external data RAM segment (ERAMLO). Addresses above 0x8000 reference high external data RAM (ERAMHI).

#### **Wait-States**

The number of wait-states (from 0 to 15) used when accessing each of the four external memory segments (ERAMLO, IO, ERAMHI, and EROM) is programmable in the mwait register (see Table 36). When the program references memory in one of the four external segments, the internal multiplexer is automatically switched to the appropriate set of internal buses, and the associated external enable of ERAMLO, IO, ERAMHI, or EROM is issued. The external memory cycle is automatically stretched by the number of wait-states configured in the appropriate field of the mwait register.

# 4.5 External Memory Interface (EMI)

The external memory interface supports read/write operations from instruction/coefficient memory, data memory, and memory-mapped I/O devices. The DSP1627 provides a 16-bit external address bus, AB[15:0], and a 16-bit external data bus, DB[15:0]. These buses are multiplexed between the internal buses for the instruction/coefficient memory and the data memory. Four external memory segment enables, ERAMLO, IO, ERAMHI, and EROM, select the external memory segment to be addressed.

If a data memory location with an address between 0x4100 and 0x7FFF is addressed, ERAMLO is asserted low.

If one of the 256 external data memory locations, with an address greater than or equal to 0x4000, and less than or equal to 0x40FF, is addressed, IO is asserted low. IO is intended for memory-mapped I/O.

If a data memory location with an address greater than or equal to 0x8000 is addressed, ERAMHI is asserted low. When the external instruction/coefficient memory is addressed, EROM is asserted low.

The flexibility provided by the programmable options of the external memory interface (see Table 36, mwait Register and Table 38, ioc Register) allows the DSP1627 to interface gluelessly with a variety of commercial memory chips.

Each of the four external memory segments, ERAMLO, IO, ERAMHI, and EROM, has a number of wait-states that is programmable (from 0 to 15) by writing to the mwait register. When the program references memory in one of the four external segments, the internal multiplexer is automatically switched to the appropriate set of internal buses, and the associated external enable of ERAMLO, IO, ERAMHI, or EROM is issued. The external memory cycle is automatically stretched by the number of wait-states in the appropriate field of the mwait register.

When writing to external memory, the RWN pin goes low for the external cycle. The external data bus, DB[15:0], is driven by the DSP1627 starting halfway through the cycle. The data driven on the external data bus is automatically held after the cycle unless an external read cycle immediately follows.

The DSP1627 has one external address bus and one external data bus for both memory spaces. Since some instructions provide the capability of simultaneous access to both X space and Y space, some provision must be made to avoid collisions for external accesses. The DSP1627 has a sequencer that does the external X access first, and then the external Y access, transparently to the programmer. Wait-states are maintained as

programmed in the mwait register. For example, let two instructions be executed: the first reads a coefficient from EROM and writes data to ERAM; the second reads a coefficient from EROM and reads data from ERAM. The sequencer carries out the following steps at the external memory interface: read EROM, write ERAM, read EROM, and read ERAM. Each step is done in sequential one-instruction cycle steps, assuming zero wait-states are programmed. Note that the number of instruction cycles taken by the two instructions is four. Also, in this case, the write hold time is zero.

The DSP1627 allows writing into external instruction/coefficient memory. By setting bit 11, WEROM, of the ioc register (see Table 38), writing to (or reading from) data memory or memory-mapped I/O asserts the EROM strobe instead of ERAMLO, IO, or ERAMHI. Therefore, with WEROM set, EROM appears in both Y space (replacing ERAM) and X space, in its normal position.

Bit 14 of the ioc register (see Table 38), EXTROM, may be used with WEROM to download to a full 64K of external memory. When WEROM and EXTROM are both asserted, address bit 15 (AB15) is held low, aliasing the upper 32K of external memory into the lower 32K.

When an access to internal memory is made, the AB[15:0] bus holds the last valid external memory address. Asserting the RSTB pin low 3-states the AB[15:0] bus. After reset, the AB[15:0] value is undefined.

The leading edge of the memory segment enables can be delayed by approximately one-half a CKO period by programming the ioc register (see Table 38). This is used to avoid a situation in which two devices drive the data bus simultaneously.

Bits 7, 8, and 13 of the ioc register select the mode of operation for the CKO pin (see Table 38). Available options are a free-running unstretched clock, a wait-stated sequenced clock (runs through two complete cycles during a sequenced external memory access), and a wait-stated clock based on the internal instruction cycle. These clocks drop to the low-speed internal ring oscillator when SLOWCKI is enabled (see 4.13, Power Management). The high-to-low transitions of the wait-stated clock are synchronized to the high-to-low transition of the free-running clock. Also, the CKO pin provides either a continuously high level, a continuously low level, or changes at the rate of the internal processor clock. This last option, only available with the crystal and small-signal input clock options, enables the DSP1627 CKI input buffer to deliver a full-rate clock to other devices while the DSP1627 itself is in one of the low-power modes.

### 4.6 Bit Manipulation Unit (BMU)

The BMU interfaces directly to the main accumulators in the DAU providing the following features:

- Barrel shifting—logical and arithmetic, left and right shift
- Normalization and extraction of exponent
- Bit-field extraction and insertion

These features increase the efficiency of the DSP in applications such as control or data encoding and decoding. For example, data packing and unpacking, in which short data words are packed into one 16-bit word for more efficient memory storage, is very easy.

In addition, the BMU provides two auxiliary accumulators, aa0 and aa1. In one instruction cycle, 36-bit data can be shuffled, or swapped, between one of the main accumulators and one of the alternate accumulators. The ar<0—3> registers are 16-bit registers that control the operations of the BMU. They store a value that determines the amount of shift or the width and offset fields for bit extraction or insertion. Certain operations in the BMU set flags in the DAU psw register and the alf register (see Table 26, Processor Status Word (psw) Register, and Table 35, alf Register). The ar<0—3> registers can also be used as general-purpose registers.

The BMU instructions are detailed in Section 5.1. For a thorough description of the BMU, see the *DSP1611/17/18/27 Digital Signal Processor Information Manual*.

### 4.7 Serial I/O Units (SIOs)

The serial I/O ports on the DSP1627 device provide a serial interface to many codecs and signal processors with little, if any, external hardware required. Each high-speed, double-buffered port (sdx and sdx2) supports back-to-back transmissions of data. SIO and SIO2 are identical. The output buffer empty (OBE and OBE2) and input buffer full (IBF and IBF2) flags facilitate the reading and/or writing of each serial I/O port by programor interrupt-driven I/O. There are four selectable active clock speeds.

A bit-reversal mode provides compatibility with either the most significant bit (MSB) first or least significant bit (LSB) first serial I/O formats (see Table 22, Serial I/O Control Registers (sioc and sioc2)). A multiprocessor I/O configuration is supported. This feature allows up to eight DSP161X devices to be connected together on an SIO port without requiring external glue logic.

The serial data may be internally looped back by setting the SIO loopback control bit, SIOLBC, of the ioc register. SIOLBC affects both the SIO and SIO2. The data output signals are wrapped around internally from the output to the input (DO1 to DI1 and DO2 to DI2). To exercise loopback, the SIO clocks (ICK1, ICK2, OCK1, and OCK2) should either all be in the active mode, 16-bit condition, or each pair should be driven from one external source in passive mode. Similarly, pins ILD1 (ILD2) and OLD1 (OLD2) must both be in active mode or tied together and driven from one external frame clock in passive mode. During loopback, DO1, DO2, DI1, DI2, ICK1, ICK2, OCK1, OCK2, ILD1, ILD2, OLD1, OLD2, SADD1, SADD2, SYNC1, SYNC2, DOEN1, and DOEN2 are 3-stated.

Setting DODLY = 1 (sioc and sioc2) delays DO by one phase of OCK so that DO changes on the falling edge of OCK instead of the rising edge (DODLY = 0). This reduces the time available for DO to drive DI and to be valid for the rising edge of ICK, but increases the hold time on DO by half a cycle on OCK.

### **Programmable Modes**

Programmable modes of operation for the SIO and SIO2 are controlled by the serial I/O control registers (sioc and sioc2). These registers, shown in Table 22, are used to set the ports into various configurations. Both input and output operations can be independently configured as either active or passive. When active, the DSP1627 generates load and clock signals. When passive, load and clock signal pins are inputs.

Since input and output can be independently configured, each SIO has four different modes of operation. Each of the sioc registers is also used to select the frequency of active clocks for that SIO. Finally, these registers are used to configure the serial I/O data formats. The data can be 8 or 16 bits long, and can also be input/output MSB first or LSB first. Input and output data formats can be independently configured.

### **Multiprocessor Mode**

The multiprocessor mode allows up to eight processors (DSP1629, DSP1628, DSP1627, DSP1620, DSP1618, DSP1617, DSP1616, DSP1611) to be connected together to provide data transmission among any of the DSPs in the system. Either SIO port (SIO or SIO2) may be independently used for the multiprocessor mode. The multiprocessor interface is a four-wire interface, consisting of a data channel, an address/protocol channel, a transmit/receive clock, and a sync signal (see Figure 5). The DI1 and DO1 pins of all the DSPs are connected to transmit and receive the data channel. The SADD1 pins of all the DSPs are connected to trans-

mit and receive the address/protocol channel. ICK1 and OCK1 should be tied together and driven from one source. The SYNC1 pins of all the DSPs are connected.

In the configuration shown in Figure 5, the master DSP (DSP0) generates active SYNC1 and OCK1 signals while the slave DSPs use the SYNC1 and OCK1 signals in passive mode to synchronize operations. In addition, all DSPs must have their ILD1 and OLD1 signals in active mode.

While ILD1 and OLD1 are not required externally for multiprocessor operation, they are used internally in the DSP's SIO. Setting the LD field of the master's sioc register to a logic level 1 will ensure that the active generation of SYNC1, ILD1, and OLD1 is derived from OCK1 (see Table 22). With this configuration, all DSPs should use ICK1 (tied to OCK1) in passive mode to avoid conflicts on the clock (CK) line (see the *DSP1611/17/18/27 Digital Signal Processor Information Manual* for more information).

Four registers (per SIO) configure the multiprocessor mode: the time-division multiplexed slot register (tdms or tdms2), the serial receive and transmit address register (srta or srta2), the serial data transmit register (sdx or sdx2), and the multiprocessor serial address/protocol register (saddx or saddx2).

Multiprocessor mode requires no external logic and uses a TDM interface with eight 16-bit time slots per frame. The transmission in any time slot consists of 16 bits of serial data in the data channel and 16 bits of address and protocol information in the address/protocol channel. The address information consists of the transmit address field of the srta register of the transmitting device. The address information is transmitted concurrently with the transmission of the first 8 bits of data. The protocol information consists of the transmit protocol field written to the saddx register and is transmitted concurrently with the last 8 bits of data (see Table 25, Multiprocessor Protocol Register). Data is received or recognized by other DSP(s) whose receive address matches the address in the address/protocol channel. Each SIO port has a user-programmable receive address and transmit address associated with it. The transmit and receive addresses are programmed in the srta register.

In multiprocessor mode, each device can send data in a unique time slot designated by the tdms register transmit slot field (bits 7—0). The tdms register has a fully decoded transmit slot field in order to allow one DSP1627 device to transmit in more than one time slot. This procedure is useful for multiprocessor systems with less than eight DSP1627 devices when a higher bandwidth is necessary between certain devices in that system. The DSP operating during time slot 0 also drives SYNC1.

In order to prevent multiple bus drivers, only one DSP can be programmed to transmit in a particular time slot. In addition, it is important to note that the address/protocol channel is 3-stated in any time slot that is not being driven.

Therefore, to prevent spurious inputs, the address/protocol channel should be pulled up to VDD with a 5 k $\Omega$  resistor, or it should be guaranteed that the bus is driven in every time slot. (If the SYNC1 signal is externally generated, then this pull-up is required for correct initialization.)

Each SIO also has a fully decoded transmitting address specified by the srta register transmit address field (bits 7—0). This is used to transmit information regarding the destination(s) of the data. The fully decoded receive address specified by the srta register receive address field (bits 15—8) determines which data will be received.

The SIO protocol channel data is controlled via the saddx register. When the saddx register is written, the lower 8 bits contain the 8-bit protocol field. On a read, the high-order 8 bits read from saddx are the most recently received protocol field sent from the transmitting DSP's saddx output register. The low-order 8 bits are read as 0s.

An example use of the protocol channel is to use the top 3 bits of the saddx value as an encoded source address for the DSPs on the multiprocessor bus. This leaves the remaining 5 bits available to convey additional control information, such as whether the associated field is an opcode or data, or whether it is the last word in a transfer, etc. These bits can also be used to transfer parity information about the data. Alternatively, the entire field can be used for data transmission, boosting the bandwidth of the port by 50%.

# **Using SIO2**

The SIO2 functions the same as the SIO. Please refer to Pin Multiplexing in Section 4.1 for a description of pin multiplexing of BIO, PHIF, VEC[3:0], and SIO2.




Figure 5. Multiprocessor Communication and Connections

### 4.8 Parallel Host Interface (PHIF)

The DSP1627 has an 8-bit parallel host interface for rapid transfer of data with external devices. This parallel port is passive (data strobes provided by an external device) and supports either *Motorola* or *Intel* microcontroller protocols. The PHIF also provides for 8-bit or 16-bit data transfers. As a flexible host interface, it requires little or no glue logic to interface to other devices (e.g., microcontrollers, microprocessors, or another DSP).

The data path of the PHIF consists of a 16-bit input buffer, **pdx0**(in), and a 16-bit output buffer, **pdx0**(out). Two output pins, parallel input buffer full (PIBF) and parallel output buffer empty (POBE), indicate the state of the buffers. In addition, there are two registers used to control and monitor the PHIF's operation: the parallel host interface control register (**phifc**, see Table 28), and the PHIF status register (PSTAT, see Table 8). The PSTAT register, which reflects the state of the PIBF and POBE flags, can only be read by an external device when the PSTAT input pin is asserted. The **phifc** register defines the programmable options for this port.

The function of the pins, PIDS and PODS, is programmable to support both the *Intel* and *Motorola* protocols. The pin, PCSN, is an input that, when low, enables PIDS and PODS (or PRWN and PDS, depending on the protocol used). While PCSN is high, the DSP1627 ignores any activity on PIDS and/or PODS. If a DSP1627 is intended to be continuously accessed through the PHIF port, PCSN should be grounded. If PCSN is low and their respective bits in the **inc** register are set, the assertion of PIDS and PODS by an external device causes the DSP1627 device to recognize an interrupt.

#### **Programmability**

The parallel host interface can be programmed for 8-bit or 16-bit data transfers using bit 0, PMODE, of the **phifc** 

register. Setting PMODE selects 16-bit transfer mode. An input pin controlled by the host, PBSEL, determines an access of either the high or low bytes. The assertion level of the PBSEL input pin is configurable in software using bit 3 of the **phifc** register, PBSELF. Table 7 summarizes the port's functionality as controlled by the PSTAT and PBSEL pins and the PBSELF and PMODE fields.

For 16-bit transfers, if PBSELF is zero, the PIBF and POBE flags are set after the high byte is transferred. If PBSELF is one, the flags are set after the low byte is transferred. In 8-bit mode, only the low byte is accessed, and every completion of an input or output access sets PIBF or POBE.

Bit 1 of the **phifc** register, PSTROBE, configures the port to operate either with an *Intel* protocol where only the chip select (PCSN) and either of the data strobes (PIDS or PODS) are needed to make an access, or with a *Motorola* protocol where the chip select (PCSN), a data strobe (PDS), and a read/write strobe (PRWN) are needed. PIDS and PODS are negative assertion data strobes while the assertion level of PDS is programmable through bit 2, PSTRB, of the **phifc** register.

Finally, the assertion level of the output pins, PIBF and POBE, is controlled through bit 4, PFLAG. When PFLAG is set low, PIBF and POBE output pins have positive assertion levels. By setting bit 5, PFLAGSEL, the logical OR of PIBF and POBE flags (positive assertion) is seen at the output pin PIBF. By setting bit 7 in **phifc**, PSOBEF, the polarity of the POBE flag in the status register, PSTAT, can be changed. PSOBEF has no effect on the POBE pin.

#### Pin Multiplexing

Please refer to Pin Multiplexing in Section 4.1 for a description of BIO, PHIF, VEC[3:0], and SIO2 pins.

Table 7. PHIF Function (	8-bit and 16-bit Modes)
--------------------------	-------------------------

PMODE Field	PSTAT Pin	PBSEL Pin	PBSELF Field = 0	PBSELF Field = 1
0 (8-bit)	0	0	pdx0 low byte	reserved
0	0	1	reserved	pdx0 low byte
0	1	0	PSTAT	reserved
0	1	1	reserved	PSTAT
1 (16-bit)	0	0	pdx0 low byte	pdx0 high byte
1	0	1	pdx0 high byte	pdx0 low byte
1	1	0	PSTAT	reserved
1	1	1	reserved	PSTAT

Table 8. pstat Register as Seen on PB[7:0]

Bit	7	6	5	4	3	2	1	0
Field			RES	PIBF	POBE			

# 4.9 Bit Input/Output Unit (BIO)

The BIO controls the directions of eight bidirectional control I/O pins, IOBIT[7:0]. If a pin is configured as an output, it can be individually set, cleared, or toggled. If a pin is configured as an input, it can be read and/or tested.

The lower half of the **sbit** register (see Table 33) contains current values (VALUE[7:0]) of the eight bidirectional pins IOBIT[7:0]. The upper half of the **sbit** register (DI-REC[7:0]) controls the direction of each of the pins. A logic 1 configures the corresponding pin as an output; a logic 0 configures it as an input. The upper half of the **sbit** register is cleared upon reset.

The **cbit** register (see Table 34) contains two 8-bit fields, MODE/MASK[7:0] and DATA/PAT[7:0]. The values of DATA/PAT[7:0] are cleared upon reset. The meaning of a bit in either field depends on whether it has been configured as an input or an output in **sbit**. If a pin has been configured to be an output, the meanings are MODE and DATA. For an input, the meanings are MASK and PAT (pattern). Table 9 shows the functionality of the MODE/MASK and DATA/PAT bits based on the direction selected for the associated IOBIT pin.

Those bits that have been configured as inputs can be individually tested for 1 or 0. For those inputs that are being tested, there are four flags produced: allt (all true), allf (all false), somet (some true), and somef (some false). These flags can be used for conditional branch or special instructions. The state of these flags can be saved and restored by reading and writing bits 0 to 3 of the **alf** register (see Table 35).

**Table 9. BIO Operations** 

DIREC[n]*	MODE/ MASK[n]	DATA/ PAT[n]	Action
1 (Output)	0	0	Clear
1 (Output)	0	1	Set
1 (Output)	1	0	No Change
1 (Output)	1	1	Toggle
0 (Input)	0	0	No Test
0 (Input)	0	1	No Test
0 (Input)	1	0	Test for Zero
0 (Input)	1	1	Test for One

<sup>\*</sup>  $0 \le n \le 7$ .

If a BIO pin is switched from being configured as an output to being configured as an input and then back to being configured as an output, the pin retains the previous output value.

### Pin Multiplexing

Please refer to Pin Multiplexing in Section 4.1 for a description of BIO, PHIF, VEC[3:0], and SIO2 pins.

### 4.10 Timer

The interrupt timer is composed of the timerc (control) register, the timer0 register, the prescaler, and the counter itself. The timer control register (see Table 31, timerc Register) sets up the operational state of the timer and prescaler. The timer0 register is used to hold the counter reload value (or period register) and to set the initial value of the counter. The prescaler slows the clock to the timer by a number of binary divisors to allow for a wide range of interrupt delay periods.

The counter is a 16-bit down counter that can be loaded with an arbitrary number from software. It counts down to 0 at the clock rate provided by the prescaler. Upon reaching 0 count, a vectored interrupt to program address 0x10 is issued to the DSP1627, providing the interrupt is enabled (bit 8 of inc and ins registers). The counter will then either wait in an inactive state for another command from software, or will automatically repeat the last interrupting period, depending upon the state of the RELOAD bit in the timerc register.

When RELOAD is 0, the counter counts down from its initial value to 0, interrupts the DSP1627, and then stops, remaining inactive until another value is written to the timer0 register. Writing to the timer0 register causes both the counter and the period register to be written with the specified 16-bit number. When RELOAD is 1, the counter counts down from its initial value to 0, interrupts the DSP1627, automatically reloads the specified initial value from the period register into the counter, and repeats indefinitely. This provides for either a single timed interrupt event or a regular interrupt clock of arbitrary period.

The timer can be stopped and started by software, and can be reloaded with a new period at any time. Its count value, at the time of the read, can also be read by software. Due to pipeline stages, stopping and starting the timer may result in one inaccurate count or prescaled period. When the DSP1627 is reset, the bottom 6 bits of the timerc register and the timer0 register and counter are initialized to 0. This sets the prescaler to CKO/2\*, turns off the reload feature, disables timer counting, and initializes the timer to its inactive state. The act of resetting the chip does not cause a timer interrupt. Note that the period register is not initialized on reset.

The T0EN bit of the timerc register enables the clock to the timer. When T0EN is a 1, the timer counts down towards 0. When T0EN is a 0, the timer holds its current count.

<sup>\*</sup> Frequency of CKO/2 is equivalent to either CKI/2 for the PLL bypassed or related to CKI by the PLL multiplying factors. See Section 4.12, Clock Synthesis.

The PRESCALE field of the timerc register selects one of 16 possible clock rates for the timer input clock (see Table 31, timerc Register).

Setting the DISABLE bit of the timerc register to a logic 1 shuts down the timer and the prescaler for power savings. Setting the TIMERDIS, bit 4, in the powerc register has the same effect of shutting down the timer. The DISABLE bit and the TIMERDIS bit are cleared by writing a 0 to their respective registers to restore the normal operating mode.

### 4.11 JTAG Test Port

The DSP1627 uses a JTAG/IEEE 1149.1 standard four-wire test port for self-test and hardware emulation. There is no separate TRST input pin. An instruction register, a boundary-scan register, a bypass register, and a device identification register have been implemented. The device identification register coding for the DSP1627 is shown in Table 37. The instruction register (IR) is 4 bits long. The instruction for accessing the device ID is 0xE (1110). The behavior of the instruction register is summarized in Table 10. Cell 0 is the LSB (closest to TDO).

**Table 10. JTAG Instruction Register** 

IR Cell #:	3	2	1	0
Parallel Input?	Υ	Υ	N	N
Always Logic 1?	N	N	N	Υ
Always Logic 0?	N	N	Υ	N

The first line shows the cells in the IR that capture from a parallel input in the capture-IR controller state. The second line shows the cells that always load a logic 1 in the capture-IR controller state. The third line shows the cells that always load a logic 0 in the capture-IR controller state. Cell 3 (MSB of IR) is tied to status signal PINT, and cell 2 is tied to status signal JINT. The state of these signals can therefore be captured during capture-IR and shifted out during SHIFT-IR controller states.

#### **Boundary-Scan Register**

All of the chip's inputs and outputs are incorporated in a JTAG scan path shown in Table 11. The types of boundary-scan cells are as follows:

- I = input cell
- O = 3-state output cell
- B = bidirectional (I/O) cell
- OE = 3-state control cell
- DC = bidirectional control cell

Note that the direction of shifting is from TDI to cell 104 to cell 103 . . . to cell 0 of TDO.

Table 11. JTAG Boundary-Scan Register

Cell	Туре	Signal Name/Function	Cell	Туре	Signal Name/Function
0	OE	Controls cells 1, 27—31	69	В	OCK2/PCSN*
1	0	СКО	70	DC	Controls cell 71
2	I	RSTB	71	В	DO2/PSTAT*
3	DC	Controls cell 4	72	DC	Controls cell 73
4	В	TRAP	73	В	SYNC2/PBSEL*
5	I	STOP <sup>†</sup>	74	DC	Controls cell 75
6	0	IACK	75	В	ILD2/PIDS*
7	I	INT0	76	DC	Controls cell 77
8	OE	Controls cells 6, 10—25, 49, 50, 78, 79	77	В	OLD2/PODS*
9	I	INT1	78	0	IBF2/PIBF*
10—25	0	AB[0:15]	79	0	OBE2/POBE*
26	I	EXM	80	DC	Controls cell 81
27	0	RWN	81	В	ICK2/PB0*
28—31	0	EROM, ERAMLO, ERAMHI, IO	82	DC	Controls cell 83
32—36	В	DB[0:4]	83	В	DI2/PB1*
37	DC	Controls cells 32—36, 38—48	84	DC	Controls cell 85
38—48	В	DB[5:15]	85	В	DOEN2/PB2*
49	0	OBE1	86	DC	Controls cell 87
50	0	IBF1	87	В	SADD2/PB3*
51	I	DI1	88	DC	Controls cell 89
52	DC	Controls cell 53	89	В	IOBIT0/PB4*
53	В	ILD1	90	DC	Controls cell 91
54	DC	Controls cell 55	91	В	IOBIT1/PB5*
55	В	ICK1	92	DC	Controls cell 93
56	DC	Controls cell 57	93	В	IOBIT2/PB6*
57	В	OCK1	94	DC	Controls cell 95
58	DC	Controls cell 59	95	В	IOBIT3/PB7*
59	В	OLD1	96	DC	Controls cell 97
60	OE	Controls cell 61	97	В	VEC3/IOBIT4*
61	0	DO1	98	DC	Controls cell 99
62	DC	Controls cell 63	99	В	VEC2/IOBIT5*
63	В	SYNC1	100	DC	Controls cell 101
64	DC	Controls cell 65	101	В	VEC1/IOBIT6*
65	В	SADD1	102	DC	Controls cell 103
66	DC	Controls cell 67	103	В	VEC0/IOBIT7*
67	В	DOEN1	104	I	CKI <sup>‡</sup>
68	DC	Controls cell 69		-	

<sup>\*</sup> Please refer to Pin Multiplexing in Section 4.1 for a description of pin multiplexing of BIO, PHIF, VEC[3:0], and SIO2.

<sup>†</sup> Note that shifting a zero into this cell in the mode to scan a zero into the chip will disable the processor clocks just as the STOP pin will.

<sup>‡</sup> When the JTAG SAMPLE instruction is used, this cell will have a logic one regardless of the state of the pin.

# 4.12 Clock Synthesis




Figure 6. Clock Source Block Diagram

The DSP1627 provides an on-chip, programmable clock synthesizer. Figure 6 is the clock source diagram. The 1X CKI input clock, the output of the synthesizer, or a slow internal ring oscillator can be used as the source for the internal DSP clock. The clock synthesizer is based on a phase-locked loop (PLL), and the terms clock synthesizer and PLL are used interchangeably.

On powerup, CKI is used as the clock source for the DSP. This clock is used to generate the internal processor clocks and CKO, where fcki = fcko. Setting the appropriate bits in the pllc control register (described in Table 32) will enable the clock synthesizer to become the clock source. The powerc register, which is discussed in Section 4.13, can override the selection to stop clocks or force the use of the slow clock for low-power operation.

#### **PLL Control Signals**

The input to the PLL comes from one of the three mask-programmable clock options: CMOS, crystal, or small-signal. The PLL cannot operate without an external input clock.

To use the PLL, the PLL must first be allowed to stabilize and lock to the programmed frequency. After the PLL has locked, the LOCK flag is set and the lock detect circuitry is disabled. The synthesizer can then be used as the clock source. Setting the PLLSEL bit in the pllc register will switch sources from fcki to fvco/2 without glitching. It is important to note that the setting of the pllc register must be maintained. Otherwise, the PLL will seek the new set point. Every time the pllc register is written, the LOCK flag is reset.

The frequency of the PLL output clock, fvco, is determined by the values loaded into the 3-bit N divider and the 5-bit M divider. When the PLL is selected and locked, the frequency of the internal processor clock is related to the frequency of CKI by the following equations:

$$fVCO = fCKI * M/N$$
  
 $fINTERNAL CLOCK = fCKO = fVCO ÷ 2$ 

The frequency of the VCO, fvco, must fall within the range listed in Table 63. Also note that fvco must be at least twice fcki.

The coding of the Mbits and Nbits is described as follows:

Mbits = 
$$M - 2$$
  
if  $(N == 1)$   
Nbits =  $0x7$   
else

where N ranges from 1 to 8 and M ranges from 2 to 20.

Nbits = N - 2

The loop filter bits LF[3:0] should be programmed according to Table 64.

Two other bits in the pllc register control the PLL. Clearing the PLLEN bit powers down the PLL; setting this bit powers up the PLL. Clearing the PLLSEL bit deselects the PLL so that the DSP is clocked by a 1X version of the CKI input; setting the PLLSEL bit selects the PLL-generated clock for the source of the DSP internal processor clock. The pllc register is cleared on reset and powerup. Therefore, the DSP comes out of reset with the PLL deselected and powered down. M and N should be changed only while the PLL is deselected. The values of M and N should not be changed when powering down or deselecting the PLL.

As previously mentioned, the PLL also provides a user flag, LOCK, to indicate when the loop has locked. When this flag is not asserted, the PLL output is unstable. The DSP should not be switched to the PLL-based clock without first checking that the lock flag is set. The lock flag is cleared by writing to the pllc register. When the PLL is deselected, it is necessary to wait for the PLL to relock before the DSP can be switched to the PLL-based clock. Before the input clock is stopped, the PLL should be powered down. Otherwise, the LOCK flag will not be reset and there may be no way to determine if the PLL is stable, once the input clock is applied again.

The lock-in time depends on the frequency of operation and the values programmed for M and N (see Table 64).

### **PLL Programming Examples**

The following section of code illustrates how the PLL would be initialized on powerup, assuming the following operating conditions:

- CKI input frequency = 10 MHz
- Internal clock and CKO frequency = 50 MHz
- VCO frequency = 100 MHz
- Input divide down count N = 2 (Set Nbits[2:0] = 000 to get N = 2, as described in Table 32.)
- Feedback down count M = 20 (Set **Mbits[4:0]** = 10010 to get M = 18 + 2 = 20, as described in Table 32.)

The device would come out of reset with the PLL disabled and deselected.

```
pllinit: pllc = 0x2912  /* Running CKI input clock at 10 MHz, set up counters in PLL */
    pllc = 0xA912  /* Power on PLL, but PLL remains deselected */
    call pllwait  /* Loop to check for LOCK flag assertion */
    pllc = 0xE912  /* Select high-speed, PLL clock */
    goto start  /* User's code, now running at 50 MHz */
pllwait: if lock return
    goto pllwait
```

Programming examples which illustrate how to use the PLL with the various power management modes are listed in Section 4.13.

### Latency

The switch between the CKI-based clock and the PLL-based clock is synchronous. This method results in the actual switch taking place several cycles after the PLLSEL bit is changed. During this time, actual code can be executed, but it will be at the previous clock rate. Table 12 shows the latency times for switching between CKI-based and PLL-based clocks. In the example given, the delay to switch to the PLL source is 1—4 CKO cycles and to switch back is 11—31 CKO cycles.

Table 12. Latency Times for Switching Between CKI and PLL-Based Clocks

	Minimum Latency (Cycles)	Maximum Latency (Cycles)
Switch to PLL-based clock	1	N + 2
Switch from PLL-based clock	M/N + 1	M + M/N + 1

#### Frequency Accuracy and Jitter

When using the PLL to multiply the input clock frequency up to the instruction clock rate, it is important to realize that although the average frequency of the internal clock and CKO will have about the same relative accuracy as the input clock, noise sources within the DSP will produce jitter on the PLL clock such that each individual clock period will have some error associated with it. The PLL is guaranteed only to have sufficiently low jitter to operate the DSP, and thus, this clock should not be used as an input to jitter-sensitive devices in the system.

### **VDDA and VSSA Connections**

The PLL has its own power and ground pins, VDDA and VSSA. Additional filtering should be provided for VDDA in the form of a ferrite bead connected from VDDA to VDD and two decoupling capacitors (4.7  $\mu$ F tantalum in parallel with a 0.01  $\mu$ F ceramic) from VDDA to VSS. VSSA can be connected directly to the main ground plane. This recommendation is subject to change and may need to be modified for specific applications depending on the characteristics of the supply noise.

Note: For devices with the CMOS clock input option, the CKI2 pin should be connected to VSSA.

### 4.13 Power Management

There are three different control mechanisms for putting the DSP1627 into low-power modes: the powerc control register, the STOP pin, and the AWAIT bit in the alf register. The PLL can also be disabled with the PLLEN bit of the pllc register for more power saving.

#### **Powerc Control Register Bits**

The powerc register has 10 bits that power down various portions of the chip and select the clock source:

XTLOFF: Assertion of the XTLOFF bit powers down the crystal oscillator or the small-signal input circuit, disabling the internal processor clock. Assertion of the XTLOFF bit to disable the crystal oscillator also prevents its use as a noninverting buffer. Since the oscillator and the small-signal input circuits take many cycles to stabilize, care must be taken with the turn-on sequence, as described later.

**SLOWCKI:** Assertion of the SLOWCKI bit selects the ring oscillator as the clock source for the internal processor clock instead of CKI or the PLL. When CKI or the PLL is selected, the ring oscillator is powered down. Switching of the clocks is synchronized so that no partial or short clock pulses occur. Two **nop**s should follow the instruction that sets or clears SLOWCKI.

**NOCK:** Assertion of the NOCK bit synchronously turns off the internal processor clock, regardless of whether its source is provided by CKI, the PLL, or the ring oscillator. The NOCK bit can be cleared by resetting the chip with the RSTB pin, or asserting the INT0 or INT1 pins. Two **nop**s should follow the instruction that sets NOCK. The PLL remains running, if enabled, while NOCK is set

**INT0EN:** This bit allows the INT0 pin to asynchronously clear the NOCK bit, thereby allowing the device to continue program execution from where it left off without any loss of state. No chip reset is required. It is recommended that, when INT0EN is to be used, the INT0 interrupt be disabled in the inc register so that an unintended interrupt does not occur. After the program resumes, the INT0 interrupt in the ins register should be cleared.

**INT1EN:** This bit enables the INT1 pin to be used as the NOCK clear, exactly like INT0EN previously described.

The following control bits power down the peripheral I/O units of the DSP. These bits can be used to further reduce the power consumption during standard sleep mode.

**SIO1 DIS:** This is a powerdown signal to the SIO1 I/O unit. It disables the clock input to the unit, thus eliminating any sleep power associated with the SIO1. Since the gating of the clocks may result in incomplete transactions, it is recommended that this option be used in applications where the SIO1 is not used or when reset may be used to reenable the SIO1 unit. Otherwise, the first transaction after reenabling the unit may be corrupted.

**SIO2DIS:** This bit powers down the SIO2 in the same way SIO1DIS powers down the SIO1.

PHIFDIS: This is a powerdown signal to the parallel host interface. It disables the clock input to the unit, thus eliminating any sleep power associated with the PHIF. Since the gating of the clocks may result in incomplete transactions, it is recommended that this option be used in applications where the PHIF is not used, or when reset may be used to reenable the PHIF. Otherwise, the first transaction after reenabling the unit may be corrupted.

**TIMERDIS:** This is a timer disable signal which disables the clock input to the timer unit. Its function is identical to the DISABLE field of the timerc control register. Writing a 0 to the TIMERDIS field will continue the timer operation.


Figure 7 shows a functional view of the effect of the bits of the powerc register on the clock circuitry. It shows only the high-level operation of each bit. Not shown are the bits that power down the peripheral units.

### **STOP Pin**

Assertion (active-low) of the STOP pin has the same effect as setting the NOCK bit in the powerc register. The internal processor clock is synchronously disabled until the STOP pin is returned high. Once the STOP pin is returned high, program execution will continue from where it left off without any loss of state. No chip reset is required. The PLL remains running, if enabled, during STOP assertion.

#### The pllc Register Bits

The PLLEN bit of the pllc register can be used to power down the clock synthesizer circuitry. Before shutting down the clock synthesizer circuitry, the system clock should be switched to either CKI using the PLLSEL bit of pllc, or to the ring oscillator using the SLOWCKI bit of powerc.



#### Notes:

The functions in the shaded ovals are bits in the powerc control register. The functions in the nonshaded ovals are bits in the pllc control register.

Deep sleep is the state arrived at either by a hardware or software stop of the internal processor clock.

The switching of the multiplexers and the synchronous gate is designed so that no partial clocks or glitching will occur.

When the deep sleep state is entered with the ring oscillator selected, the internal processor clock is turned off before the ring oscillator is powered down.

PLL select is the PLLSEL bit of pllc; PLL powerdown is the PLLEN bit of pllc.

Figure 7. Power Management Using the powerc and the pllc Registers

### Await Bit of the alf Register

Setting the AWAIT bit of the alf register causes the processor to go into the standard sleep state or power-saving standby mode. Operation of the AWAIT bit is the same as in the DSP1610, DSP1611, DSP1616, DSP1617, and DSP1618. In this mode, the minimum circuitry required to process an incoming interrupt remains active, and the PLL remains active if enabled. An interrupt will return the processor to the previous state, and program execution will continue. The action resulting from setting the AWAIT bit and the action resulting from setting bits in the powerc register are mostly independent. As long as the processor is receiving a clock, whether slow or fast, the DSP may be put into standard sleep mode with the AWAIT bit. Once the AWAIT bit is set, the STOP pin can be used to stop and later restart the processor clock, returning to the standard sleep state. If the processor clock is not running, however, the AWAIT bit cannot be set.

### **Power Management Sequencing**

There are important considerations for sequencing the power management modes. Both the crystal oscillator and the small-signal clock input circuits have start-up delays which must be taken into account, and the PLL requires a delay to reach lock-in. Also, the chip may or may not need to be reset following a return from a low-power state.

Devices with a crystal oscillator or small-signal input clocking option may use the XTLOFF bit in the powerc register to power down the on-chip oscillator or small-signal circuitry, thereby reducing the power dissipation. When reenabling the oscillator or the small-signal circuitry, it is important to bear in mind that a start-up interval exists during which time the clocks are not stable.

Two scenarios exist here:

- 1. Immediate Turn-Off, Turn-On with RSTB: This scenario applies to situations where the target device is not required to execute any code while the crystal oscillator or small-signal input circuit is powered down and where restart from a reset state can be tolerated. In this case, the processor clock derived from either the oscillator or the small-signal input is running when XTLOFF is asserted. This effectively stops the internal processor clock. When the system chooses to reenable the oscillator or small-signal input, a reset of the device will be required. The reset pulse must be of sufficient duration for the oscillator start-up interval to be satisfied. A similar interval is required for the small-signal input circuit to reach its dc operating point. A minimum reset pulse of 20 ms will be adequate. The falling edge of the reset signal, RSTB, will asynchronously clear the XTLOFF field, thus re-enabling the power to the oscillator or small-signal circuitry. The target DSP will then start execution from a reset state, following the rising edge of RSTB.
- 2. Running from Slow Clock While XTLOFF Active: The second scenario applies to situations where the device needs to continue execution of its target code when the crystal oscillator or small-signal input is powered down. In this case, the device switches to the slow ring oscillator clock first, by enabling the SLOWCKI field before writing a 1 to the XTLOFF field. Two **nop**s are needed in between the two write operations to the powerc register. The target device will then continue execution of its code at slow speed, while the crystal oscillator or small-signal input clock is turned off. Switching from the slow clock back to the high-speed crystal oscillator clock is then accomplished in three user steps. First, XTLOFF is cleared. Then, a user-programmed routine sets the internal timer to a delay to wait for the crystal's oscillations to become stable. When the timer counts down to zero, the high-speed clock is selected by clearing the SLOWCKI field, either in the timer's interrupt service routine or following a timer polling loop. If PLL operation is desired, then an additional routine is necessary to enable the PLL and wait for it to lock.

#### **Power Management Examples Without the PLL**

The following examples show the more significant options for reducing the power dissipation. These are valid only if the pllc register is set to disable and deselect the PLL (PLLEN = 0, PLLSEL = 0).

**Standard Sleep Mode.** This is the standard sleep mode. While the processor is clocked with a high-speed clock, CKI, the alf register's AWAIT bit is set. Peripheral units may be turned off to further reduce the sleep power.

```
powerc = 0X00F0 /* Turn off peripherals, core running with CKI */
sleep:a0 = 0x8000 /* Set alf register in cache loop if running from */
     do 1 {
                     /* external memory with >1 wait state */
     alf = a0
                     /* Stop internal processor clock, interrupt circuits */
                     /* active */
     nop
     }
                     /* Needed for bedtime execution. Only sleep power */
     nop
                     /* consumed here until.... interrupt wakes up the device */
     nop
                      /* User code executes here */
cont: . . .
     powerc = 0x0
                      /* Turn peripheral units back on */
```

**Sleep with Slow Internal Clock.** In this case, the ring oscillator is selected to clock the processor before the device is put to sleep. This will reduce the power dissipation while waiting for an interrupt to continue program execution.

```
powerc = 0x40F0 /* Turn off peripherals and select slow clock */
                    /* Wait for it to take effect */
     2*nop
                   /* Set alf register in cache loop if running from */
sleep:a0 = 0x8000
     do 1 {
                     /* external memory with >1 wait state */
                     /* Stop internal processor clock, interrupt circuits */
     alf = a0
     nop
                      /* active */
     }
                     /* Needed for bedtime execution. Reduced sleep power */
     nop
                     /* consumed here.... Interrupt wakes up the device */
     nop
                     /* User code executes here */
cont: . . .
     powerc = 0x00F0  /* Select high-speed clock */
     2*nop
                      /* Wait for it to take effect */
     powerc = 0x0000 /* Turn peripheral units back on */
```

Note that, in this case, the wake-up latency is determined by the period of the ring oscillator clock.

**Sleep with Slow Internal Clock and Crystal Oscillator/Small-Signal Disabled.** If the target device contains the crystal oscillator or the small-signal clock option, the clock input circuitry can be powered down to further reduce power. In this case, the slow clock must be selected first.

```
powerc = 0x40F0     /* Turn off peripherals and select slow clock */
                     /* Wait for it to take effect */
     2*nop
     powerc = 0xC0F0    /* Turn off the crystal oscillator */
sleep:a0 = 0x8000 /* Set alf register in cache loop if running from */
                      /* external memory with >1 wait state */
     do 1 {
                     /* Stop internal processor clock, interrupt circuits */
     alf = a0
                      /* active */
     nop
     }
                      /* Needed for bedtime execution. Reduced sleep power */
     nop
                      /* consumed here.... Interrupt wakes up the device */
     nop
     powerc = 0x40F0     /* Clear XTLOFF, reenable oscillator/small-signal */
     call xtlwait /* Wait until oscillator/small-signal is stable */
cont: powerc = 0x00F0
                     /* Select high-speed clock */
                       /* Wait for it to take effect */
     2*nop
     powerc = 0x0000 /* Turn peripheral units back on */
```

Note that, in this case, the wake-up latency is dominated by the crystal oscillator or small-signal start-up period.

**Software Stop.** In this case, all internal clocking is disabled. INT0, INT1, or RSTB may be used to reenable the clocks. If the device uses the crystal oscillator or small-signal clock option, the power management must be done in correct sequence.

```
powerc = 0x4000  /* SLOWCKI asserted */
                /* Wait for it to take effect */
    2*nop
    sopor:powerc = 0xF000    /* NOCK asserted, all clocks stop */
                 /* Minimum switching power consumed here */
                /* Some nops will be needed */
    3*nop
                /* INTO pin clears the NOCK field, clocking resumes */
cont: powerc = 0x4000    /* INTOEN cleared and XTLOFF cleared, if applicable*/
    /* stabilize, if applicable*/
    powerc = 0x0 /* Clear SLOWCKI field, back to high speed */
                 /* Wait for it to take effect */
    2*nop
    ins = 0x0010
                /* Clear the INTO status bit */
```

In this case also, the wake-up latency is dominated by the crystal oscillator or small-signal start-up period.

The previous examples do not provide an exhaustive list of options available to the user. Many different clocking possibilities exist for which the target device may be programmed, depending on:

- The clock source to the processor.
- Whether the user chooses to power down the peripheral units.
- The operational state of the crystal oscillator/small-signal clock input, powered or unpowered.
- Whether the internal processor clock is disabled through hardware or software.
- The combination of power management modes the user chooses.
- Whether or not the PLL is enabled.

An example subroutine for xtlwait follows:

### **Power Management Examples with the PLL**

The following examples show the more significant options for reducing power dissipation if operation with the PLL clock synthesizer is desired.

**Standard Sleep Mode, PLL Running.** This mode would be entered in the same manner as without the PLL. While the input to the clock synthesizer, CKI, remains running, the alf register's AWAIT bit is set. The PLL will continue to run and dissipate power. Peripheral units may be turned off to further reduce the sleep power.

```
powerc = 0x00F0 /* Turn off peripherals, core running with PLL */
sleep:a0 = 0x8000 /* Set alf register in cache loop if running from */
                   /* external memory with >1 wait state */
    do 1 {
                   /* Stop internal processor clock, interrupt circuits */
     alf = a0
                    /* active */
    nop
     }
                   /* Needed for bedtime execution. Only sleep power plus PLL */
    nop
                   /* power consumed here.... Interrupt wakes up the device */
    nop
cont: . . .
                    /* User code executes here */
```

**Sleep with Slow Internal Clock, PLL Running**. In this case, the ring oscillator is selected to clock the processor before the device is put to sleep. This will reduce power dissipation while waiting for an interrupt to continue program execution.

```
powerc = 0x40F0 /* Turn off peripherals and select slow clock */
                     /* Wait for slow clock to take effect */
     2*nop
sleep:a0 = 0x8000
                     /* Set alf register in cache loop if running from */
                      /* external memory with >1 wait state */
     do 1 {
     alf = a0
                      /* Stop internal processor clock, interrupt circuits */
                       /* active */
     nop
     }
                       /* Needed for bedtime execution. Reduced sleep power, PLL */
     nop
                       /* power, and ring oscillator power consumed here... */
     nop
                       /* Interrupt wakes up the device */
                      /* User code executes here */
cont: . . .
     powerc = 0x00F0    /* Select high-speed PLL based clock */
                      /* Wait for it to take effect */
     2*nop
     powerc = 0x0000  /* Turn peripheral units back on */
```

Sleep with Slow Internal Clock and Crystal Oscillator/Small-Signal Disabled, PLL Disabled. If the target device contains the crystal oscillator or the small-signal clock option, the clock input circuitry can be powered down to further reduce power. In this case, the slow clock must be selected first, and then the PLL must be disabled, since the PLL cannot run without the clock input circuitry being active.

```
powerc = 0x40F0    /* Turn off peripherals and select slow clock */
      2*nop
                       /* Wait for slow clock to take effect */
     pllc = 0x29F2
                      /* Disable PLL (assume N = 1,M = 20, LF = 1001) */
     powerc = 0xC0F0     /* Disable crystal oscillator */
                       /* Set alf register in cache loop if running from */
sleep:a0 = 0x8000
                       /* external memory with >1 wait state */
     do 1 {
     alf = a0
                       /* Stop internal processor clock, interrupt circuits */
     nop
                       /* active */
     }
                       /* Needed for bedtime execution. Reduced sleep power
     nop
                       /* consumed here.... Interrupt wakes up device */
     nop
                       /* Clear XTLOFF, leave PLL disabled */
     powerc = 0x40F0
     call xtlwait
                       /* Wait until crystal oscillator/small-signal is stable */
                      /* Enable PLL, continue to run off slow clock */
     pllc = 0xE9F2
     call pllwait
                       /* Loop to check for LOCK flag assertion */
cont: powerc = 0 \times 0.0 = 0
                       /* Select high-speed PLL based clock */
                       /* Wait for it to take effect */
     2*nop
     powerc = 0x0000
                       /* Turn peripherals back on */
```

**Software Stop, PLL Disabled**. In this case, all internal clocking is disabled. INT0, INT1, or RSTB may be used to reenable the clocks. If the device uses the crystal oscillator or small-signal clock option, the power management must be done in the correct sequence, with the PLL being disabled before shutting down the clock input buffer.

```
powerc = 0x4000
                       /* SLOWCKI asserted */
      2*nop
                       /* Wait for slow clock to take effect */
                       /* Disable PLL (assume N = 1, M = 20, LF = 1001) */
     pllc = 0x29F2
                       /* XTLOFF asserted, if applicable and INTOEN
     powerc = 0xD000
                       /* asserted */
sopor:powerc = 0xF000
                       /* NOCK asserted, all clocks stop */
                       /* Minimum switching power consumed here */
                       /* Some nops will be needed */
      3*nop
                       /* INTO pin clears NOCK field, clocking resumes */
cont: powerc = 0x4000
                       /* INTOEN cleared and XTLOFF cleared, if applicable */
     call xtlwait
                       /* Wait until crystal oscillator/small-signal is stable */
                       /* if applicable */
                       /* Enable PLL, continue to run off slow clock */
     pllc = 0xE9F2
     call pllwait
                       /* Loop to check for LOCK flag assertion */
                      /* Select high-speed PLL based clock */
     2*nop
                       /* Wait for it to take effect */
                       /* Clear the INTO status bit */
     ins = 0x0010
```

### **5 Software Architecture**

#### 5.1 Instruction Set

The DSP1627 processor has seven types of instructions: multiply/ALU, special function, control, F3 ALU, BMU, cache, and data move. The multiply/ALU instructions are the primary instructions used to implement signal processing algorithms. Statements from this group can be combined to generate multiply/accumulate, logical, and other ALU functions and to transfer data between memory and registers in the data arithmetic unit. The special function instructions can be conditionally executed based on flags from the previous ALU or BMU operation, the condition of one of the counters, or the value of a pseudorandom bit in the DSP1627 device. Special function instructions perform shift, round, and complement functions. The F3 ALU instructions enrich the operations available on accumulators. The BMU instructions provide high-performance bit manipulation. The control instructions implement the goto and call commands. Control instructions can also be executed conditionally. Cache instructions are used to implement low-overhead loops, conserve program memory, and decrease the execution time of certain multiply/ALU instructions. Data move instructions are used to transfer data between memory and registers or between accumulators and registers. See the DSP1611/17/18/27 Digital Signal Processor Information Manual for a detailed description of the instruction set.

The following operators are used in describing the instruction set:

- \* 16 x 16-bit -> 32-bit multiplication or register-indirect addressing when used as a prefix to an address register or denotes direct addressing when used as a prefix to an immediate
- + 36-bit addition<sup>†</sup>
- – 36-bit subtraction<sup>†</sup>
- >> Arithmetic right shift
- >>> Logical right shift
- Arithmetic left shift
- <<< Logical left shift</p>
- | 36-bit bitwise OR<sup>†</sup>
- & 36-bit bitwise AND<sup>†</sup>
- ^ 36-bit bitwise EXCLUSIVE OR†
- Compound address swapping, accumulator shuffling
- ~ One's complement

### **Multiply/ALU Instructions**

Note that the function statements and transfer statements in Table 13 are chosen independently. Any function statement (F1) can be combined with any transfer statement to form a valid multiply/ALU instruction. If either statement is not required, a single statement from either column also constitutes a valid instruction. The number of cycles to execute the instruction is a function of the transfer column. (An instruction with no transfer statement executes in one instruction cycle.) Whenever PC, pt, or rM is used in the instruction and points to external memory, the programmed number of wait-states must be added to the instruction cycle count. All multiply/ALU instructions require one word of program memory. The no-operation (nop) instruction is a specialcase encoding of a multiply/ALU instruction and executes in one cycle. The assembly-language representation of a **nop** is either **nop** or a single semicolon.

A single-cycle squaring function is provided in DSP1627. By setting the X = Y = bit in the auc register, any instruction that loads the high half of the y register also loads the x register with the same value. A subsequent instruction to multiply the x register and y register results in the square of the value being placed in the p register. The instruction  $a0 = p p = x^*y y = *r0++ with$ the X = Y = bit set to one will read the value pointed to by r0, load it to both x and y, multiply the previously fetched value of x and y, and transfer the previous product to a0. A table of values pointed to by r0 can thus be squared in a pipeline with one instruction cycle per each value. Multiply/ALU instructions that use x = X transfer statements (such as  $a0 = p p = x^*y y = r0++ x = pt++$ ) are not recommended for squaring because pt will be incremented even though x is not loaded from the value pointed to by pt. Also, the same conflict wait occurrences from reading the same bank of internal memory or reading from external memory apply, since the X space fetch occurs (even though its value is not used).

<sup>†</sup> These are 36-bit operations. One operand is 36-bit data in an accumulator; the other operand may be 16, 32, or 36 bits.

Table 13. Multiply/ALU Instructions

Function Statement		
p = x	* y	
aD = p	p = x * y	
aD = aS + p	p = x * y	
aD = aS - p	p = x * y	
aD =	: р	
aD = aS	S + p	
aD = a	S – p	
aD =	<b>y</b>	
aD = a	S + y	
aD = a	S – y	
aD = aS	S & y	
aD = aS   y		
aD = aS ^ y		
aS – y		
aS & y		

Transfer Statement <sup>†</sup>	Cycles (Out/In Cache) <sup>‡</sup>
y = Y $x = X$	2/1
y = aT	2/1
y[I] = Y	1/1
aT[I] = Y	1/1
x = Y	1/1
Y	1/1
Y = y[I]	2/2
Y = aT[I]	2/2
Z:y $x = X$	2/2
Z:y[I]	2/2
Z:aT[I]	2/2

**Note:** For transfer statements when loading the upper half of an accumulator, the lower half is cleared if the corresponding CLR bit in the auc register is zero. auc is cleared by reset.

Table 14. Replacement Table for Multiply/ALU Instructions

Replace	Value	Meaning
aD, aS, aT	a0, a1	One of two DAU accumulators.
Х	*pt++, *pt++i	X memory space location pointed to by pt. pt is postmodified by +1 and i, respectively.
Y	*rM, *rM++, *rM, rM++j	RAM location pointed to by rM (M = 0, 1, 2, 3). rM is postmodified by $0, +1, -1$ , or j, respectively.
Z	*rMzp, *rMpz, *rMm2, *rMjk	Read/Write compound addressing. rM (M = 0, 1, 2, 3) is used twice. First, postmodified by 0, +1, $-1$ , or j, respectively; and, second, postmodified by +1, 0, +2, or k, respectively.

<sup>†</sup> The I in [] is an optional argument that specifies the low 16 bits of aT or y.

<sup>‡</sup> Add cycles for:

<sup>1.</sup> When an external memory access is made in X or Y space and wait-states are programmed, add the number of wait-states.

<sup>2.</sup> If an X space access and a Y space access are made to the same bank of DPRAM in one instruction, add one cycle.

### **Special Function Instructions**

All forms of the special function require one word of program memory and execute in one instruction cycle. (If PC points to external memory, add programmed wait-states.)

aD = aS >> 1 aD = aS >> 4 aD = aS >> 8 aD = aS >> 16	Arithme	Arithmetic right shift (sign preserved) of 36-bit accumulators	
aD = aS	_	Load destination accumulator from source accumulator	
aD = −aS	_	2's complement	
aD = ~aS <sup>*</sup>	_	1's complement	
aD = rnd(aS)	_	Round upper 20 bits of accumulator	
aDh = aSh +	1 —	Increment upper half of accumulator (lower half cleared)	
aD = aS + 1	_	Increment accumulator	
aD = y	_	Load accumulator with 32-bit y register value with sign extend	
aD = p	_	Load accumulator with 32-bit p register value with sign extend	
aD = aS << 1 aD = aS << 4 aD = aS << 8 aD = aS << 16		etic left shift (sign not preserved) of the lower 32 bits of accumulators 4 bits are sign-bit-extended from bit 31 at the completion of the shift)	

The above special functions can be conditionally executed, as in:

```
if CON instruction
```

and with an event counter

```
ifc CON instruction
```

which means:

```
if CON is true then
    c1 = c1 + 1
    instruction
    c2 = c1
else
    c1 = c1 + 1
```

The above special function statements can be executed unconditionally by writing them directly, e.g., a0 = a1.

**Table 15. Replacement Table for Special Function Instructions** 

Replace	Value	Meaning
aD	a0, a1	One of two DAU accumulators.
aS		
CON	mi, pl, eq, ne, gt, le, lvs, lvc, mvs, mvc, c0ge,	See Table 17 for definitions of mnemonics.
	c0lt, c1ge, c1lt, heads, tails, true, false, allt, allf,	
	somet, somef, oddp, evenp, mns1, nmns1, npint,	
	njint, lock	

<sup>\*</sup> This function is not available for the DSP16A.

#### **Control Instructions**

All control instructions executed unconditionally execute in two cycles, except **icall** which takes three cycles. Control instructions executed conditionally execute in three instruction cycles. (If PC, pt, or pr point to external memory, add programmed wait-states.) Control instructions executed unconditionally require one word of program memory, while control instructions executed conditionally require two words. Control instructions cannot be executed from the cache.

```
goto JA<sup>†</sup>
goto pt
call JA<sup>†</sup>
call pt
icall<sup>‡</sup>
return (goto pr)
ireturn (goto pi)
```

The above control instructions, with the exception of **ireturn** and **icall**, can be conditionally executed. For example:

if le goto 0x0345

**Table 16. Replacement Table for Control Instructions** 

Replace	Value	Meaning
CON	mi, pl, eq, ne, gt, le, nlvs, lvc, mvs, mvc, c0ge, c0lt, c1ge, c1lt, heads, tails, true, false, allt, allf, somet, somef, oddp, evenp, mns1, nmns1, npint, njint, lock	See Table 17 for definitions of mnemonics.
JA	12-bit value	Least significant 12 bits of absolute address within the same 4 Kwords memory section.

<sup>†</sup> The **goto JA** and **call JA** instructions should not be placed in the last or next-to-last instruction before the boundary of a 4 Kwords page. If the **goto** or **call** is placed there, the program counter will have incremented to the next page and the jump will be to the next page, rather than to the desired current page.

<sup>‡</sup> The **icall** instruction is reserved for development system use.

### **Conditional Mnemonics (Flags)**

Table 17 lists mnemonics used in conditional execution of special function and control instructions.

**Table 17. DSP1627 Conditional Mnemonics** 

Test	Meaning	Test	Meaning
pl	Result is nonnegative (sign bit is bit 35). $\geq 0$	mi	Result is negative. < 0
eq	Result is equal to 0. = 0	ne	Result is not equal to 0. ≠ 0
gt	Result is greater than 0. > 0	le	Result is less than or equal to 0. ≤ 0
lvs	Logical overflow set.*	lvc	Logical overflow clear.
mvs	Mathematical overflow set. <sup>†</sup>	mvc	Mathematical overflow clear.
c0ge	Counter 0 greater than or equal to 0.	c0lt	Counter 0 less than 0.
c1ge	Counter 1 greater than or equal to 0.	c1lt	Counter 1 less than 0.
heads	Pseudorandom sequence bit set.	tails	Pseudorandom sequence bit clear.
true	The condition is always satisfied in an if in-	false	The condition is never satisfied in an if instruc-
	struction.		tion.
allt	All True, all BIO input bits tested compared	allf	All False, no BIO input bits tested compared
	successfully.		successfully.
somet	Some True, some BIO input bits tested com-	somef	Some False, some BIO input bits tested did
	pared successfully.		not compare successfully.
oddp	Odd Parity, from BMU operation.	evenp	Even Parity, from BMU operation.
mns1	Minus 1, result of BMU operation.	nmns1	Not Minus 1, result of BMU operation.
npint	Not PINT, used by hardware development	njint	Not JINT, used by hardware development
	system.		system.
lock	The PLL has achieved lock and is stable.		

<sup>\*</sup> Result is not representable in the 36-bit accumulators (36-bit overflow).

#### Notes:

Testing the state of the counters (c0 or c1) automatically increments the counter by one.

The heads or tails condition is determined by a randomly set or cleared bit, respectively. The bit is randomly set with a probability of 0.5. A random rounding function can be implemented with either heads or tails. The random bit is generated by a ten-stage pseudorandom sequence generator (PSG) that is updated after either a heads or tails test. The pseudorandom sequence may be reset by writing any value to the pi register, except during an interrupt service routine (ISR). While in an ISR, writing to the pi register updates the register and does not reset the PSG. If not in an ISR, writing to the pi register resets the PSG. (The pi register is updated, but will be written with the contents of the PC on the next instruction.) Interrupts must be disabled when writing to the pi register. If an interrupt is taken after the pi write, but before pi is updated with the PC value, the ireturn instruction will not return to the correct location. If the RAND bit in the auc register is set, however, writing the pi register never resets the PSG.

<sup>†</sup> Bits 35—31 are not the same (32-bit overflow).

#### **F3 ALU Instructions**

These instructions are implemented in the DSP1600 core. They allow accumulator two-operand operations with either another accumulator, the p register, or a 16-bit immediate operand (IM16). The result is placed in a destination accumulator that can be independently specified. All operations are done with the full 36 bits. For the accumulator with accumulator operations, both inputs are 36 bits. For the accumulator with p register operations, the p register is sign-extended into bits 35—32 before the operation. For the accumulator high with immediate operations, the immediate is sign-extended into bits 35—32 and the lower bits 15—0 are filled with zeros, except for the AND operation, for which they are filled with ones. These conventions allow the user to do operations with 32-bit immediates by programming two consecutive 16-bit immediate operations. The F3 ALU instructions are shown in Table 18.

**Table 18. F3 ALU Instructions** 

F3 ALU Instructions†		
Cachable (One-Cycle)	Not Cachable (Two-Cycle)‡	
aD = aS + aT	aD = aSh + IM16	
aD = aS - aT	aD = aSh - IM16	
aD = aS & aT	aD = aSh & IM16	
aD = aS   aT	aD = aSh   IM16	
aD =aS ^ aT	aD = aSh ^ IM16	
aS – aT	aSh – IM16	
aS & aT	aSh & IM16	
aD = aS + p	aD = aSI + IM16	
aD = aS – p	aD = aSI - IM16	
aD = aS & p	aD = aSI & IM16	
aD = aS   p	aD = aSI   IM16	
aD = aS ^ p	aD = aSI ^ IM16	
aS – p	aSI – IM16	
aS & p	aSI & IM16	

Note: The F3 ALU instructions that do not have a destination accumulator are used to set flags for conditional operations, i.e., bit test operations.

- † If PC points to external memory, add programmed wait-states.
- ‡ The h and I are required notation in these instructions.

#### **F4 BMU Instructions**

The bit manipulation unit in the DSP1627 provides a set of efficient bit manipulation operations on accumulators. It contains four auxiliary registers, ar<0-3> (arM, M = 0, 1, 2, 3), two alternate accumulators (aa0-aa1), which can be shuffled with the working set, and four flags (oddp, evenp, mns1, and nmns1). The flags are testable by conditional instructions and can be read and written via bits 4-7 of the alf register. The BMU also sets the LMI, LEQ, LLV, and LMV flags in the psw register.

- LMI = 1 if negative (i.e., bit 35 = 1)
- LEQ = 1 if zero (i.e., bits 35—0 are 0)
- LLV = 1 if (a) 36-bit overflow, or if (b) illegal shift on field width/offset condition
- LMV = 1 if bits 31—35 are not the same (32-bit overflow)

The BMU instructions and cycle times follow. (If PC points to external memory, add programmed wait-states.) All BMU instructions require 1 word of program memory unless otherwise noted. Please refer to the *DSP1611/17/18/27 Digital Signal Processor Information Manual* for further discussion of the BMU instructions.

#### ■ Barrel Shifter:

aD = aS >> IM16	Arithmetic right shift by immediate (36-bit, sign filled in); 2-cycle, 2-word.
aD = aS >> arM	Arithmetic right shift by arM (36-bit, sign filled in); 1-cycle.
$aD = \overline{aS} >> aS$	Arithmetic right shift by aS (36-bit, sign filled in); 2-cycle.
aD = aS >>> IM16	Logical right shift by immediate (32-bit shift, 0s filled in); 2-cycle, 2-word.
aD = aS >>> arM	Logical right shift by arM (32-bit shift, 0s filled in); 1-cycle.
$aD = \overline{aS} >>> aS$	Logical right shift by aS (32-bit shift, 0s filled in); 2-cycle.
aD = aS << IM16	Arithmetic left shift <sup>†</sup> by immediate (36-bit shift, 0s filled in); 2-cycle, 2-word.
aD = aS << IM16 aD = aS << arM	Arithmetic left shift <sup>†</sup> by immediate (36-bit shift, 0s filled in); 2-cycle, 2-word. Arithmetic left shift <sup>†</sup> by arM (36-bit shift, 0s filled in); 1-cycle.
aD = aS << arM	Arithmetic left shift <sup>†</sup> by arM (36-bit shift, 0s filled in); 1-cycle.
aD = aS << arM aD = aS << aS	Arithmetic left shift <sup>†</sup> by arM (36-bit shift, 0s filled in); 1-cycle. Arithmetic left shift <sup>†</sup> by aS (36-bit shift, 0s filled in); 2-cycle.

<sup>†</sup> Not the same as the special function arithmetic left shift. Here, the guard bits in the destination accumulator are shifted into, not sign-extended.

#### ■ Normalization and Exponent Computation:

aD = exp(aS) Detect the number of redundant sign bits in accumulator; 1-cycle. aD = norm(aS, arM) Normalize aS with respect to bit 31, with exponent in arM; 1-cycle.

#### ■ Bit Field Extraction and Insertion:

aD = extracts(aS, IM16) Extraction with sign extension, field specified as immediate; 2-cycle, 2-word.

aD = extracts(aS, arM) Extraction with sign extension, field specified in arM; 1-cycle.

aD = extractz(aS, IM16) Extraction with zero extension, field specified as immediate; 2-cycle, 2-word.

aD = extractz(aS, arM) Extraction with zero extension, field specified in arM; 1-cycle.

aD = insert(aS, IM16) Bit field insertion, field specified as immediate; 2-cycle, 2-word.

aD = insert(aS, arM) Bit field insertion, field specified in arM; 2-cycle.

**Note:** The bit field to be inserted or extracted is specified as follows. The width (in bits) of the field is the upper byte of the operand (immediate or arM), and the offset from the LSB is in the lower byte.

#### ■ Alternate Accumulator Set:

aD = aS:aa0 Shuffle accumulators with alternate accumulator 0 (aa0); 1-cycle.

aD = aS:aa1 Shuffle accumulators with alternate accumulator 1 (aa1); 1-cycle.

Note: The alternate accumulator gets what was in aS. aD gets what was in the alternate accumulator.

Table 19. Replacement Table for F3 ALU Instructions and F4 BMU Instructions

Replace	Value	Meaning
aD, aT, aS	a0 or a1	One of the two accumulators.
IM16	immediate	16-bit data, sign-, zero-, or one-extended as appropriate.
arM	ar<0—3>	One of the auxiliary BMU registers.

#### **Cache Instructions**

Cache instructions require one word of program memory. The **do** instruction executes in one instruction cycle, and the **redo** instruction executes in two instruction cycles. (If PC points to external memory, add programmed wait-states.) Control instructions and long immediate values cannot be stored inside the cache. The instruction formats are as follows:

- do K {
- instr1
- instr2
- .
- .
- .
- instrN
- **.** }
- redo K

Table 20. Replacement Table for Cache Instructions

Replace	Instruction Encoding	Meaning
K	cloop†	Number of times the instructions are to be executed taken from bits 0—6 of the <b>cloop</b> register.
	1 to 127	Number of times the instructions to be executed is encoded in the instruction.
N	1 to 15	1 to 15 instructions can be included.

<sup>†</sup> The assembly-language statement, do **cloop** (or redo **cloop**), is used to specify that the number of iterations is to be taken from the **cloop** register. K is encoded as 0 in the instruction encoding to select **cloop**.

When the cache is used to execute a block of instructions, the cycle timings of the instructions are as follows:

- 1. In the first pass, the instructions are fetched from program memory and the cycle times are the normal out-of-cache values, except for the last instruction in the block of NI instructions. This instruction executes in two cycles.
- 2. During pass two through pass K 1, each instruction is fetched from cache and the in-cache timings apply.
- 3. During the last (Kth) pass, the block of instructions is fetched from cache and the in-cache timings apply, except that the timing of the last instruction is the same as if it were out-of-cache.
- 4. If any of the instructions access external memory, programmed wait-states must be added to the cycle counts.

The **redo** instruction treats the instructions currently in the cache memory as another loop to be executed K times. Using the **redo** instruction, instructions are reexecuted from the cache without reloading the cache.

The number of iterations, K, for a **do** or **redo** can be set at run time by first moving the number of iterations into the **cloop** register (7 bits unsigned), and then issuing the do **cloop** or redo **cloop**. At the completion of the loop, the value of **cloop** is decremented to 0; hence, **cloop** needs to be written before each **do cloop** or **redo cloop**.

#### **Data Move Instructions**

Data move instructions normally execute in two instruction cycles. (If PC or rM point to external memory, any programmed wait-states must be added. In addition, if PC and rM point to the same bank of DPRAM, then one cycle must be added.) Immediate data move instructions require two words of program memory; all other data move instructions require only one word. The only exception to these statements is a special case immediate load (short immediate) instruction. If a YAAU register is loaded with a 9-bit short immediate value, the instruction requires only one word of memory and executes in one instruction cycle. All data move instructions, except those doing long immediate loads, can be executed from within the cache. The data move instructions are as follows:

- R = IM16
- aT[l] = R
- SR = IM9
- Y = R
- R = Y
- Z:R
- R = aS[I]
- DR = \*(OFFSET)
- \*(OFFSET) = DR

**Table 21. Replacement Table for Data Move Instructions** 

Replace	Value	Meaning
R	Any of the registers in Table 51	_
DR	r<0—3>, a0[i], a1[i], y[i], p, pl, x,	Subset of registers accessible with direct addressing.
	pt, pr, psw	
aS, aT	a0, a1	High half of accumulator.
Υ	*rM, *rM++, *rM, *rM++j	Same as in multiply/ALU instructions.
Z	*rMzp, *rMpz, *rMm2, *rMjk	Same as in multiply/ALU instructions.
IM16	16-bit value	Long immediate data.
IM9	9-bit value	Short immediate data for YAAU registers.
OFFSET	5-bit value from instruction	Value in bits [15:5] of ybase register form the 11 most significant
	11-bit value in base register	bits of the base address. The 5-bit offset is concatenated to this
		to form a 16-bit address.
SR	r<0—3>, rb, re, j, k	Subset of registers for short immediate.

#### Notes:

sioc, sioc2, tdms, tdms2, srta, and srta2 registers are not readable.

When signed registers less than 16 bits wide (c0, c1, c2) are read, their contents are sign-extended to 16 bits. When unsigned registers less than 16 bits wide are read, their contents are zero-extended to 16 bits.

Loading an accumulator with a data move instruction does not affect the flags.

## **5.2 Register Settings**

Tables 22 through 38 describe the programmable registers of the DSP1627 device. Table 40 describes the register settings after reset.

Note that the following abbreviations are used in the tables:

- x = don't care
- R = read only
- W = read/write

The reserved (RSVD) bits in the tables should always be written with zeros to make the program compatible with future chip versions.

### Table 22. Serial I/O Control Registers

#### sioc

Bit	10	9	8	7	6	5	4	3	2	1	0
Field	DODLY	LD	CI	CLK		OLD	ILD	OCK	ICK	OLEN	ILEN

Field	Value	Description
DODLY	0	DO changes on the rising edge of OCK.
	1	DO changes on the falling edge of OCK. This delay in driving DO increases the hold
		time on DO by half a cycle of OCK.
LD	0	In active mode, ILD1 and/or OLD1 = ICK1/16, active SYNC1 = ICK1/[128/256*].
	1	In active mode, ILD1 and/or OLD1 = OCK1/16, active SYNC1 = OCK1/[128/256*].
CLK	00	Active clock = CKI/2 (1X).
	01	Active clock = CKI/6 (1X).
	10	Active clock = CKI/8 (1X).
	11	Active clock = CKI/10 (1X).
MSB	0	LSB first.
	1	MSB first.
OLD	0	OLD1 is an input (passive mode).
	1	OLD1 is an output (active mode).
ILD	0	ILD1 is an input (passive mode).
	1	ILD1 is an output (active mode).
OCK	0	OCK1 is an input (passive mode).
	1	OCK1 is an output (active mode).
ICK	0	ICK1 is an input (passive mode).
	1	ICK1 is an output (active mode).
OLEN	0	16-bit output.
	1	8-bit output.
ILEN	0	16-bit input.
	1	8-bit input.

<sup>\*</sup> See tdms register, SYNC field.

### sioc2<sup>‡</sup>

Bit	10	9	8	7	6	5	4	3	2	1	0
Field	DODLY2	LD2	CL	K2	MSB2	OLD2	ILD2	OCK2	ICK2	OLEN2	ILEN2

<sup>†</sup> See tdms register, SYNC field.

<sup>‡</sup> The bit definitions of the sioc2 register are identical to the sioc register bit definitions.

## **Table 23. Time-Division Multiplex Slot Registers**

#### tdms

Bit	9	8	7	6	5	4	3	2	1	0
Field	SYNCSP	MODE			TRAN	SMIT :	SLOT			SYNC

Field	Value	Description
SYNCSP <sup>†</sup>	0 <sup>‡</sup>	SYNC1 = $ICK1/128$ if $LD = 0^*$ .
		SYNC1 = OCK1/128 if LD = 1*.
	1	SYNC1 = ICK1/256 if LD = 0*.
		SYNC1 = OCK1/256 if LD = 1*.
MODE	0	Multiprocessor mode off; DOEN1 is an input (passive mode).
	1	Multiprocessor mode on; DOEN1 is an output (active mode).
TRANSMIT SLOT	1xxxxxx	Transmit slot 7.
	x1xxxxx	Transmit slot 6.
	xx1xxxx	Transmit slot 5.
	xxx1xxx	Transmit slot 4.
	xxxx1xx	Transmit slot 3.
	xxxxx1x	Transmit slot 2.
	xxxxxx1	Transmit slot 1.
SYNC	1	Transmit slot 0, SYNC1 is an output (active mode).
	0	SYNC1 is an input (passive mode).

<sup>\*</sup> See sioc register, LD field.

#### tdms2§

Bit	9	8	7	6	5	4	3	2	1	0
Field	SYNCSP2 <sup>†</sup>	MODE2			TRAN	ISMIT S	LOT2			SYNC2

<sup>†</sup> See sioc register, LD field.

<sup>‡</sup> Select this mode when in multiprocessor mode.

<sup>‡</sup> Select this mode when in multiprocessor mode.

<sup>§</sup> The tdms2 register bit definitions are identical to the tdms register bit definitions.

## Table 24. Serial Receive/Transmit Address Registers

#### srta

Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Field	RECEIVE ADDRESS										TR	RANSN	1IT AD	DRES	S	

Field	Value	Description
RECEIVE ADDRESS	1xxxxxxx	Receive address 7.
	x1xxxxxx	Receive address 6.
	xx1xxxxx	Receive address 5.
	xxx1xxxx	Receive address 4.
	xxxx1xxx	Receive address 3.
	xxxxx1xx	Receive address 2.
	xxxxxx1x	Receive address 1.
	xxxxxxx1	Receive address 0.
TRANSMIT ADDRESS	1xxxxxxx	Transmit address 7.
	x1xxxxxx	Transmit address 6.
	xx1xxxxx	Transmit address 5.
	xxx1xxxx	Transmit address 4.
	xxxx1xxx	Transmit address 3.
	xxxxx1xx	Transmit address 2.
	xxxxxx1x	Transmit address 1.
	xxxxxxx1	Transmit address 0.

### srta2<sup>†</sup>

Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Field			RECE	EIVE A	ADDR	ESS2	)			-	ΓRAN	SMIT	ADDI	RESS	2	

 $<sup>\</sup>ensuremath{\dagger}$  The srta2 field definitions are identical to the srta register field definitions.

### **Table 25. Multiprocessor Protocol Registers**

### saddx

Bit Field	15—8	7—0
Write	X	Write Protocol Field [7:0]
Read	Read Protocol Field [7:0]	0

# $\mathsf{saddx2}^{\ddagger}$

Bit Field	15—8	7—0
Write	X	Write Protocol2 Field [7:0]
Read	Read Protocol2 Field [7:0]	0

<sup>‡</sup> The saddx2 field definitions are identical to the saddx register field definitions.

### Table 26. Processor Status Word (psw) Register

Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Field		DAU F	LAGS		Χ	Х	a1[V]	6	a1[35	5:32]		a0[V]			a0[3	5:32]

Field	Value	Description
DAU FLAGS*	Wxxx	LMI — logical minus when set (bit 35 = 1).
	xWxx	LEQ — logical equal when set (bit [35:0] = 0).
	xxWx	LLV — logical overflow when set.
	Wxxx	LMV — mathematical overflow when set.
a1[V]	W	Accumulator 1 (a1) overflow when set.
a1[35:32]	Wxxx	Accumulator 1 (a1) bit 35.
	xWxx	Accumulator 1 (a1) bit 34.
	xxWx	Accumulator 1 (a1) bit 33.
	Wxxx	Accumulator 1 (a1) bit 32.
a0[V]	W	Accumulator 0 (a0) overflow when set.
a0[35:32]	Wxxx	Accumulator 0 (a0) bit 35.
	xWxx	Accumulator 0 (a0) bit 34.
	xxWx	Accumulator 0 (a0) bit 33.
	XXXW	Accumulator 0 (a0) bit 32.

<sup>\*</sup> The DAU flags can be set by either BMU or DAU operations.

## Table 27. Arithmetic Unit Control (auc) Register<sup>†</sup>

Bit	8	7	6	5	4	3	2	1	0
Field	RAND	X=Y=		CLR		S	AT		ALIGN

Field	Value	Description
RAND	0	Pseudorandom sequence generator (PSG) reset by writing the pi register
		only outside an interrupt service routine.
	1	PSG never reset by writing the pi register.
X=Y=	0	Normal operation.
	1	All instructions which load the high half of the y register also load the x regis-
		ter, allowing single-cycle squaring with $p = x * y$ .
CLR	1xx	Clearing yl is disabled (enabled when 0).
	x1x	Clearing a1l is disabled (enabled when 0).
	xx1	Clearing a0l is disabled (enabled when 0).
SAT	1x	a1 saturation on overflow is disabled (enabled when 0).
	x1	a0 saturation on overflow is disabled (enabled when 0).
ALIGN	00	a0, a1 ← p.
	01	a0, a1 ← p/4.
	10	a0, a1 ← p x 4 (and zeros written to the two LSBs).
	11	a0, a1 ← p x 2 (and zero written to the LSB).

<sup>†</sup> The auc is 9 bits [8:0]. The upper 7 bits [15:9] are always zero when read and should always be written with zeros to make the program compatible with future chip versions. The auc register is cleared at reset.

### Table 28. Parallel Host Interface Control (phifc) Register

Bit	15—7	6	5	4	3	2	1	0
Field	RSVD	PSOBEF	PFLAGSEL	PFLAG	PBSELF	PSTRB	PSTROBE	PMODE

Field	Value	Description
PMODE	0	8-bit data transfers.
	1	16-bit data transfers.
PSTROBE	0	Intel protocol: PIDS and PODS data strobes.
	1	Motorola protocol: PRWN and PDS data strobes.
PSTRB	0	When PSTROBE = 1, PODS pin (PDS) active-low.
	1	When PSTROBE = 1, PODS pin (PDS) active-high.
PBSELF	0	In either mode, PBSEL pin = $0 \rightarrow pdx0$ low byte. See Table 7.
	1	If PMODE = 0, PBSEL pin = 1 $\rightarrow$ pdx0 low byte.
		If PMODE = 1, PBSEL pin = $0 \rightarrow pdx0$ high byte.
PFLAG	0	PIBF and POBE pins active-high.
	1	PIBF and POBE pins active-low.
PFLAGSEL	0	Normal.
	1	PIBF flag ORed with POBE flag and output on PIBF pin; POBE pin un-
		changed (output buffer empty).
PSOBEF	0	Normal.
	1	POBE flag as read through PSTAT register is active-low.

### Table 29. Interrupt Control (inc) Register

Bit	15	14—11	10	9	8	7—6	5—4	3	2	1	0
Field	I JINT*	RSVD	OBE2	IBF2	TIME	RSVD	INT[1:0]	PIBF	POBE	OBE	IBF

<sup>\*</sup> JINT is a JTAG interrupt and is controlled by the HDS. It may be made unmaskable by the Lucent Technologies development system tools. Encoding: A 0 disables an interrupt; a 1 enables an interrupt.

### Table 30. Interrupt Status (ins) Register

Bit	15	14—11	10	9	8	7—6	5—4	3	2	1	0
Field	JINT	RSVD	OBE2	IBF2	TIME	RSVD	INT[1:0]	PIBF	POBE	OBE	IBF

Encoding: A 0 indicates no interrupt. A 1 indicates an interrupt has been recognized and is pending or being serviced. If a 1 is written to bits 4, 5, or 8 of ins, the corresponding interrupt is cleared.

## Table 31. timerc Register

Bit	15—7	6	5	4	3—0
Field	RSVD	DISABLE	RELOAD	T0EN	PRESCALE

Field	Value	Description
DISABLE	0	Timer enabled.
	1	Timer and prescaler disabled. The period register and timer0 are not reset.
RELOAD	0	Timer stops after counting down to 0.
	1	Timer automatically reloads and repeats indefinitely.
T0EN	0	Timer holds current count.
	1	Timer counts down to 0.
PRESCALE	_	See table below.

## **PRESCALE Field**

PRESCALE	Frequency of Timer Interrupts	PRESCALE	Frequency of Timer Interrupts
0000	CKO/2	1000	CKO/512
0001	CKO/4	1001	CKO/1024
0010	CKO/8	1010	CKO/2048
0011	CKO/16	1011	CKO/4096
0100	CKO/32	1100	CKO/8192
0101	CKO/64	1101	CKO/16384
0110	CKO/128	1110	CKO/32768
0111	CKO/256	1111	CKO/65536

## Table 32. Phase-Locked Loop Control (pllc) Register

Bit	15	14	13	12	11—8	7—5	4—0
Field	PLLEN	PLLSEL	ICP	SEL5V	LF[3:0]	Nbits[2:0]	Mbits[4:0]

Field	Value	Description
PLLEN	0	PLL powered down.
	1	PLL powered up.
PLLSEL	0	DSP internal clock taken directly from CKI.
	1	DSP internal clock taken from PLL.
ICP	_	Charge pump current selection (see Table 64 for proper value).
SEL5V	0	3 V operation (see Table 64 for proper value).
	1	5 V operation (see Table 64 for proper value).
LF[3:0]	_	Loop filter setting (see Table 64 for proper value).
Nbits[2:0]	_	Encodes N, $1 \le N \le 8$ , where N = Nbits[2:0] + 2, unless Nbits[2:0] = 111, then N = 1.
Mbits[4:0]	_	Encodes M, $2 \le M \le 20$ , where M = Mbits[4:0] + 2, finternal clock = fcki x (M/(2N)).

## Table 33. sbit Register

Bit		15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Field	k	DIREC[7:0]											VALUE	[7:0]			

Field	Value	Description
DIREC	1xxxxxxx	IOBIT7 is an output (input when 0).
	x1xxxxxx	IOBIT6 is an output (input when 0).
	xx1xxxxx	IOBIT5 is an output (input when 0).
	xxx1xxxx	IOBIT4 is an output (input when 0).
	xxxx1xxx	IOBIT3 is an output (input when 0).
	xxxxx1xx	IOBIT2 is an output (input when 0).
	xxxxxx1x	IOBIT1 is an output (input when 0).
	xxxxxxx1	IOBIT0 is an output (input when 0).
VALUE	Rxxxxxxx	Reads the current value of IOBIT7.
	xRxxxxxx	Reads the current value of IOBIT6.
	xxRxxxxx	Reads the current value of IOBIT5.
	xxxRxxxx	Reads the current value of IOBIT4.
	xxxxRxxx	Reads the current value of IOBIT3.
	xxxxxRxx	Reads the current value of IOBIT2.
	xxxxxxRx	Reads the current value of IOBIT1.
	xxxxxxxR	Reads the current value of IOBIT0.

## Table 34. cbit Register

Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Field	MODE/MASK[7:4]				MO	DDE/M	IASK[3	:0]		DATA/F	PAT[7:4	]	DATA/PAT[3:0]			

DIREC[n]*	MODE/MASK[n]	DATA/PAT[n]	Action
1 (Output)	0	0	Clear
1 (Output)	0	1	Set
1 (Output)	1	0	No Change
1 (Output)	1	1	Toggle
0 (Input)	0	0	No Test
0 (Input)	0	1	No Test
0 (Input)	1	0	Test for Zero
0 (Input)	1	1	Test for One

<sup>\*</sup>  $0 \le n \le 7$ .

Table 35. alf Register

Bit	15	14	13—0
Field	AWAIT	LOWPR	FLAGS

Field	Value	Action
AWAIT	1	Power-saving standby mode or standard sleep enabled.
	0	Normal operation.
LOWPR	1	The internal DPRAM is addressed beginning at 0x0000 in X space.
	0	The internal DPRAM is addressed beginning at 0xc000 in X space.
FLAGS	_	See table below.

Bit	Flag	Use
13—8	Reserved	_
7	nmns1	NOT-MINUS-ONE from BMU
6	mns1	MINUS-ONE from BMU
5	evenp	EVEN PARITY from BMU
4	oddp	ODD PARITY from BMU
3	somef	SOME FALSE from BIO
2	somet	SOME TRUE from BIO
1	allf	ALL FALSE from BIO
0	allt	ALL TRUE from BIO

### Table 36. mwait Register

Bit	15—12	11—8	7—4	3—0
Field	EROM[3:0]	ERAMHI[3:0]	IO[3:0]	ERAMLO[3:0]

If the EXM pin is high and the INT1 is low upon reset, the mwait register is initialized to all 1s (15 wait-states for all external memory). Otherwise, the mwait register is initialized to all 0s (0 wait-states) upon reset.

Table 37. DSP1627 32-Bit JTAG ID Register

Bit	31	30	29—28	27—19	18—12	11—0
Field	RESERVED	SECURE	CLOCK	ROMCODE	PART ID	0x03B

Field	٧	alue							Ma	sk-P	rogr	amn	able	Fea	ture	s					
RESERVED		0			_																
SECURE		0	١	lonse	ecure	RO	М ор	tion.													
		1	S	Secur	e RC	O MC	ption														
CLOCK		01	S	Small	-sign	al in	out c	ock	optio	n.											
		10	C	Crysta	estal oscillator input clock option.																
		11	C	CMOS	IOS level input clock option.																
ROMCODE		_	J	Jsers	ers ROMCODE ID:																
				he R							-					_	•				
			,	20 x v				,	•					, .		the v	/alue	s of t	he le	tters	are
				n the		_					,	)MC	DDE	GK i	S						
			(	20 x	6) +	(9) =	129	or 0	1000	000	1.										
PART ID	C	x1C		DSP1627x36 with 36K IROM and no EROM in MAP1 or MAP3.																	
	0	x2C		DSP1627x32 with 32K IROM and 16K EROM in MAP1 and MAP3.																	
ROMCODE Let	В	С	D	Е	F	G	Н	J	K	L	М	N	Р	R	S	Т	U	W	Υ		
Value	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19		

## Table 38. ioc Register\*

Bi	t	15	14	13	12	11	10	9	8—7	6—4	3—0
Fie	ld	RSVD	EXTROM	CKO2	EBIOH	WEROM	ESIO2	SIOLBC	CKO[1:0]	RSVD	DENB[3:0]

<sup>\*</sup> The field definitions for the ioc register are different from the DSP1610.

### ioc Fields

ioc Field	Description
EXTROM	If 1, sets AB15 low during external memory accesses when WEROM = 1.
CKO2	CKO configuration (see below).
EBIOH	If 1, enables high half of BIO, IOBIT[4:7], and disables VEC[3:0] from pins.
WEROM	If 1, allows writing into external program (X) memory.
ESIO2	If 1, enables SIO2 and low half of BIO, and disables PHIF from pins.
SIOLBC	If 1, DO1 and DO2 looped back to DI1 and DI2.
CKO[1:0]	CKO configuration (see below).
DENB3	If 1, delay EROM.
DENB2	If 1, delay ERAMHI.
DENB1	If 1, delay IO.
DENB0	If 1, delay ERAMLO.

CKO2	CKO1	CKO0	C	CKO Output	Description
			1X	PLL	_
0	0	0	CKI	CKI x M/(2N)	Free-running clock.
0	0	1	CKI/(1 + W)	CKI x (M/(2N)) / [1 + W]	Wait-stated clock.*, †
0	1	0	1	1	Held high.*, <sup>†</sup> , <sup>‡</sup>
0	1	1	0	0	Held low.
1	0	0	CKI	CKI	Output of CKI buffer.
1	0	1	CKI/(1 + W)	CKI x (M/(2N)) / [1 + W]	Sequenced, wait-stated clock.*, †, ‡, §
1	1	0		Reserved	
1	1	1		Reserved	

<sup>\*</sup> The phase of CKI is synchronized by the rising edge of RSTB.

<sup>†</sup> When SLOWCKI is enabled in the powerc register, these options reflect the low-speed internal ring oscillator.

<sup>‡</sup> The wait-stated clock reflects the internal instruction cycle and may be stretched based on the mwait register setting (see Table 36). During sequenced external memory accesses, it completes one cycle.

<sup>§</sup> The sequenced wait-stated clock completes two cycles during a sequenced external memory access and may be stretched based on the mwait register setting (see Table 36).

### Table 39. powerc Register

The **powerc** register configures various power management modes.

Ī	Bit	15	14	13	12	11	10	9—8	7	6	5	4	3—0
	Field	XTLOFF	SLOWCKI	NOCK	INT0EN	RSVD	INT1EN	RSVD	SIO1DIS	SIO2DIS	PHIFDIS	TIMERDIS	RSVD

Note: The reserved (RSVD) bits should always be written with zeros to make the program compatible with future chip versions.

#### powerc fields

Field	Description
XTLOFF	1 = powerdown crystal oscillator or small-signal clock input.
SLOWCKI	1 = select ring oscillator clock (internal slow clock).
NOCK	1 = disable internal processor clock.
INT0EN	1 = INT0 clears NOCK field.
INT1EN	1 = INT1 clears NOCK field.
SIO1DIS	1 = disable SIO1.
SIO2DIS	1 = disable SIO2.
PHIFDIS	1 = disable PHIF.
TIMERDIS	1 = disable timer.

A • indicates that this bit is unknown on powerup reset and unaffected on subsequent reset. An S indicates that this bit shadows the PC. P indicates the value on an input pin, i.e., the bit in the register reflects the value on the corresponding input pin.

**Table 40. Register Settings After Reset** 

Register	Bits 15—0	Register	Bits 15—0
r0	••••••	inc	000000000000000
r1	••••••	ins	000001000000110
r2	••••••	sdx2	•••••
r3	••••••	saddx	***************************************
j	••••••	cloop	000000000
k	••••••	mwait	000000000000000 <sup>†</sup>
rb	000000000000000	saddx2	•••••
re	000000000000000	sioc2	•••••0000000000
pt	•••••	cbit	••••••
pr	••••••	sbit	00000000PPPPPPP
pi	SSSSSSSSSSSSS	ioc	000000000000000
i	•••••	jtag	••••••
р	••••••		
pl	•••••	a0	••••••
Х	••••••	a0l	***************************************
у	••••••	a1	•••••
yl	••••••	a1l	•••••
auc	000000000000000	timerc	••••••00000000
psw	••••00•••••	timer0	000000000000000
c0	••••••	tdms2	•••••0000000000
c1	•••••	srta2	•••••
c2	••••••	powerc	000000000000000
sioc	•••••0000000000	pllc	000000000000000
srta	••••••	ar0	***************************************
sdx	••••••	ar1	•••••
tdms	•••••0000000000	ar2	••••••
phifc	000000000000000	ar3	•••••
pdx0	000000000000000		
ybase	•••••	alf	00000000

<sup>†</sup> If EXM is high and INT1 is low when RSTB goes high, mwait will contain all ones instead of all zeros.

### **5.3 Instruction Set Formats**

This section defines the hardware-level encoding of the DSP1627 device instructions.

### **Multiply/ALU Instructions**

Format 1: Multiply/ALU Read/Write Group

Field		T 				D	S		F	1		Χ		Υ	′	
Bit	15	14	13		11	10	9	8	7	6	5	4	3	2	1	0

Format 1a: Multiply/ALU Read/Write Group

Field			Т			аТ	S		F	1		Χ		Υ	,	
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 2: Multiply/ALU Read/Write Group

Field			Τ			D	S		F	1		Х		Υ	′	
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 2a: Multiply/ALU Read/Write Group

Field		T				аТ	S		F	1		Х		Υ	′	
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

#### **Special Function Instructions**

Format 3: F2 ALU Special Functions

Field		T				D	S		F	2				CON		
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 3a: F3 ALU Operations

Field			Т			D	S		F	3		SR	C2	аТ	0	1
						lmr	nediate	e Opera	and (IM	116)						
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 3b: BMU Operations

Field			T			D	S	F4	4[3—1]		0	F4[0]		AR	2	
		Immediate Operand (IM16)														
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

### **Control Instructions**

Format 4: Branch Direct Group

Field		i	T							J	A					
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 5: Branch Indirect Group

Field			Т				В				R	eserve	d			0
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 6: Conditional Branch Qualifier/Software Interrupt (icall)

Field			T			SI		Rese	rved				CC	N		
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Note: A branch instruction immediately follows except for a software interrupt (icall).

#### **Data Move Instructions**

Format 7: Data Move Group

Field			Т			аТ				R				Y/	Z	
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 8: Data Move (immediate operand—2 words)

Ī	Field			Τ			D			R					Rese	rved	
Ī								Immed	diate O	peranc	l (IM16	)					
Ī	Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

Format 9: Short Immediate Group

Field		Т								Short		Short Immediate Operand (IM9)						
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0		

Format 9a: Direct Addressing

Field			Т			R/W		DI	R		1		(	)FFSE	1	
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0

#### **Cache Instructions**

Format 10: Do/Redo

Field		Т					NI				К						
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0	

### **Field Descriptions**

Table 41. T Field

Specifies the type of instruction.

Т	Operation		Format
0000x	goto JA		4
00010	Short imm j, k, rb, re		9
00011	Short imm r0, r1, r2, r3		9
00100	Y = a1[I]	F1	1
00101	Z : aT[I]	F1	2a
00110	Y	F1	1
00111	aT[I] = Y	F1	1a
01000	Bit $0 = 0$ , $aT = R$		7
01000	Bit 0 = 1, aTl = R		7
01001	Bit $10 = 0$ , $R = a0$		7
01001	Bit 10 = 1, R = a0l		7
01010	R = IM16		8
01011	Bit $10 = 0$ , $R = a1$		7
01011	Bit 10 = 1, R = a1I		7
01100	Y = R		7
01101	Z : R		7
01110	do, redo		10
01111	R = Y		7
1000x	call JA		4
10010	ifc CON	F2	3
10011	if CON	F2	3
10100	Y = y[I]	F1	1
10101	Z : y[I]	F1	2
10110	x = Y	F1	1
10111	y[I] = Y	F1	1
11000	Bit 0 = 0, branch indirect		5
11000	Bit 0 = 1, F3 ALU		3a
11001	y = a0 x = X	F1	1
11010	Cond. branch qualifier		6
11011	y = a1  x = X	F1	1
11100	Y = a0[I]	F1	1
11101	Z : y x = X	F1	2
11110	Bit 5 = 0, F4 ALU (BMU)		3b
11110	Bit 5 = 1, direct addressing	ng	9a
11111	y = Y x = X	F1	1

Table 42. D Field

Specifies a destination accumulator.

D	Register
0	Accumulator 0
1	Accumulator 1

### Table 43. aT Field

Specifies transfer accumulator.

аТ	Register
0	Accumulator 1
1	Accumulator 0

#### Table 44. S Field

Specifies a source accumulator.

S	Register
0	Accumulator 0
1	Accumulator 1

Table 45. F1 Field

Specifies the multiply/ALU function.

F1	Operation
0000	aD = pp = x * y
0001	aD = aS + pp = x * y
0010	p = x * y
0011	aD = aS - pp = x * y
0100	aD = p
0101	aD = aS + p
0110	nop
0111	aD = aS - p
1000	aD = aS   y
1001	aD = aS ^ y
1010	aS & y
1011	aS – y
1100	aD = y
1101	aD = aS + y
1110	aD = aS & y
1111	aD = aS - y

#### Table 46. X Field

Specifies the addressing of ROM data in two-operand multiply/ALU instructions. Specifies the high or low half of an accumulator or the **y** register in one-operand multiply/ALU instructions.

X	Operation
Two-Ope	rand Multiply/ALU
0	∗pt++
1	∗pt++i
One-Operand Multiply/ALU	
0	aTI, yl
1	aTh, yh

Table 47. Y Field

Specifies the form of register indirect addressing with postmodification.

Y	Operation
0000	*r0
0001	*r0++
0010	*r0
0011	*r0++j
0100	*r1
0101	*r1++
0110	*r1
0111	*r1++j
1000	*r2
1001	*r2++
1010	*r2
1011	*r2++j
1100	*r3
1101	*r3++
1110	*r3
1111	∗r3++j

Table 48. Z Field

Specifies the form of register indirect compound addressing with postmodification.

Z	Operation
0000	*r0zp
0001	*r0pz
0010	∗r0m2
0011	∗r0jk
0100	*r1zp
0101	∗r1pz
0110	*r1m2
0111	∗r1jk
1000	*r2zp
1001	*r2pz
1010	∗r2m2
1011	∗r2jk
1100	*r3zp
1101	*r3pz
1110	∗r3m2
1111	∗r3jk

Table 49. F2 Field

Specifies the special function to be performed.

F2	Operation
0000	aD = aS >> 1
0001	aD = aS << 1
0010	aD = aS >> 4
0011	aD = aS << 4
0100	aD = aS >> 8
0101	aD = aS << 8
0110	aD = aS >> 16
0111	aD = aS << 16
1000	aD = p
1001	aDh = aSh + 1
1010	aD = ~aS
1011	aD = rnd(aS)
1100	aD = y
1101	aD = aS + 1
1110	aD = aS
1111	aD = - aS

#### Table 50. CON Field

Specifies the condition for special functions and conditional control instructions.

CON	Condition	CON	Condition
00000	mi	01110	true
00001	pl	01111	false
00010	eq	10000	gt
00011	ne	10001	le
00100	lvs	10010	allt
00101	lvc	10011	allf
00110	mvs	10100	somet
00111	mvc	10101	somef
01000	heads	10110	oddp
01001	tails	10111	evenp
01010	c0ge	11000	mns1
01011	c0lt	11001	nmns1
01100	c1ge	11010	npint
01101	c1lt	11011	njint
		11100	lock
Other	Reserved	_	_
codes			

Table 51. R Field

Specifies the register for data move instructions.

R	Register	R	Register
000000	r0	100000	inc
000001	r1	100001	ins
000010	r2	100010	sdx2
000011	r3	100011	saddx
000100	j	100100	cloop
000101	k	100101	mwait
000110	rb	100110	saddx2
000111	re	100111	sioc2
001000	pt	101000	cbit
001001	pr	101001	sbit
001010	pi	101010	ioc
001011	i	101011	jtag
001100	р	101100	Reserved
001101	pl	101101	Reserved
001110	pllc	101110	Reserved
001111	Reserved	101111	Reserved
010000	х	110000	a0
010001	У	110001	a0l
010010	yl	110010	a1
010011	auc	110011	a1l
010100	psw	110100	timerc
010101	c0	110101	timer0
010110	c1	110110	tdms2
010111	c2	110111	srta2
011000	sioc	111000	powerc
011001	srta	111001	Reserved
011010	sdx	111010	ar0
011011	tdms	111011	ar1
011100	phifc	111100	ar2
011101	pdx0	111101	ar3
011110	Reserved	111110	Reserved
011111	ybase	111111	alf

#### Table 52. B Field

Specifies the type of branch instruction (except software interrupt).

В	Operation
000	return
001	ireturn
010	goto pt
011	call pt
1xx	Reserved

Table 53. DR Field

DR Value	Register
0000	r0
0001	r1
0010	r2
0011	r3
0100	a0
0101	a0l
0110	a1
0111	a1l
1000	у
1001	yl
1010	р
1011	pl
1100	X
1101	pt
1110	pr
1111	psw

### Table 54. I Field

Specifies a register for short immediate data move instructions.

I	Register
00	rO/j
01	r1/k
10	r2/rb
11	r3/re

### Table 55. SI Field

Specifies when the conditional branch qualifier instruction should be interpreted as a software interrupt instruction.

SI	Operation	
0	Not a software interrupt	
1	Software interrupt	

#### NI Field

Number of instructions to be loaded into the cache. Zero implies redo operation.

#### K Field

Number of times the NI instructions in cache are to be executed. Zero specifies use of value in **cloop** register.

#### JA Field

12-bit jump address.

#### R/W Field

A zero specifies a write, \*(O) = DR.

A one specifies a read, DR = \*(O).

Table 56. F3 Field

Specifies the operation in an F3 ALU instruction.

F3	Operation		
1000	aD = aS[h, l]		{aT, IM16, p}
1001	aD = aS[h, l]	٨	{aT, IM16, p}
1010	aS[h, l]	&	{aT, IM16, p}
1011	aS[h, l]	-	{aT, IM16, p}
1101	aD = aS[h, l]	+	{aT, IM16, p}
1110	aD = aS[h, l]	&	{aT, IM16, p}
1111	aD = aS[h, l]	_	{aT, IM16, p}

Table 57. SRC2 Field

Specifies operands in an F3 ALU instruction.

SRC2	Operands
00	aSI, IM16
10	aSh, IM16
01	aS, aT
11	aS, p

Table 58. BMU Encodings

F4	AR	Operation			
0000	00xx	aD = aS >> arM			
0001	00xx	aD = aS << arM			
0000	10xx	aD = aS >>> arM			
0001	10xx	aD = aS <<< arM			
1000	0000	$aD = \overline{aS} >> aS$			
1001	0000	aD = <del>aS</del> << aS			
1000	1000	aD = <del>aS</del> >>> aS			
1001	1000	aD = aS <<< aS			
1100	0000	aD = aS >> IM16			
1101	0000	aD = aS << IM16			
1100	1000	aD = aS >>> IM16			
1101	1000	aD = aS <<< IM16			
0000	1100	aD = exp(aS)			
0001	11xx	aD = norm(aS, arM)			
1110	0000	aD = extracts(aS, IM16)			
0010	00xx	aD = extracts(aS, arM)			
1110	0100	aD = extractz(aS, IM16)			
0010	01xx	aD = extractz(aS, arM)			
1110	1000	aD = insert(aS, IM16)			
1010	10xx	aD = insert(aS, arM)			
0111	0000	aD = aS:aa0			
0111	0001	aD = aS:aa1			

Note: xx encodes the auxiliary register to be used. 00 (ar0), 01(ar1), 10 (ar2), or 11(ar3).

## 6 Signal Descriptions




Figure 8. DSP1627 Pinout by Interface

Figure 8 shows the pinout for the DSP1627. The signals can be separated into five interfaces as shown. These interfaces and the signals that comprise them are described below.

## 6.1 System Interface

The system interface consists of the clock, interrupt, and reset signals for the processor.

#### **RSTB**

**Reset:** Negative assertion. A high-to-low transition causes the processor to enter the reset state. The auc, powerc, sioc, sioc2, phifc, pdx0, tdms, tdms2, timerc, timer0, sbit (upper byte), inc, ins (except OBE, OBE2,

and PODS status bits set), alf (upper 2 bits, AWAIT and LOWPR), ioc, rb, and re registers are cleared. The mwait register is initialized to all 0s (zero wait-states) unless the EXM pin is high and the INT1 pin is low. In that case, the mwait register is initialized to all 1s (15 wait-states).

Reset clears IACK, VEC[3:0]/IOBIT[4:7], IBF, and IBF2. The DAU condition flags are not affected by reset. IOBIT[7:0] are initialized as inputs. If any of the IOBIT pins are switched to outputs (by writing sbit), their initial value will be logic zero (see Table 40, Register Settings After Reset).

Upon negation of the signal, the processor begins execution at location 0x0000 in the active memory map (see Section 4.4, Memory Maps and Wait-States).

#### CKI

**Input Clock:** A mask-programmable option selects one of three possible input buffers for the CKI pin (see Section 7, Mask-Programmable Options, and Table 1, Pin Descriptions). The internal CKI from the output of the selected input buffer can then drive the internal processor clock directly (1X) or drive the on-chip PLL (see Section 4.13). The PLL allows the CKI input clock to be at a lower frequency than the internal processor clock.

#### CKI2

Input Clock 2: Used with mask-programmable input clock options which require an external crystal or small signal differential across CKI and CKI2 (see Table 1, Pin Descriptions). When the CMOS option is selected, this pin should be tied to VSSA.

#### **STOP**

**Stop Input Clock:** Negative assertion. A high-to-low transition synchronously stops all of the internal processor clocks leaving the processor in a defined state. Returning the pin high will synchronously restart the processor clocks to continue program execution from where it left off without any loss of state. This hardware feature has the same effect as setting the NOCK bit in the powerc register (see Table 39).

#### **CKO**

**Clock Out:** Buffered output clock with options programmable via the ioc register (see Table 38). The selectable CKO options (see Tables 38 and 29) are as follows:

- A free-running output clock at the frequency of the internal processor clock; runs at the internal ring oscillator frequency when SLOWCKI is enabled.
- A wait-stated clock based on the internal instruction cycle; runs at the internal ring oscillator frequency when SLOWCKI is enabled.
- A sequenced, wait-stated clock based on the EMI sequencer cycle; runs at the internal ring oscillator frequency when SLOWCKI is enabled.

- A free-running output clock that runs at the CKI rate, independent of the **powerc** register setting. This option is only available with the crystal and small-signal clock options. When the PLL is selected, the CKO frequency equals the input CKI frequency regardless of how the PLL is programmed.
- A logic 0.
- A logic 1.

#### INT[1:0]

Processor Interrupts 0 and 1: Positive assertion. Hardware interrupt inputs to the DSP1627. Each is enabled via the inc register. When enabled and asserted, each cause the processor to vector to the memory location described in Table 4. INT1 is used in conjunction with EXM to select the desired reset initialization of the mwait register (see Table 36). When both INT0 and RSTB are asserted, all output and bidirectional pins (except TDO, which 3-states by JTAG control) are put in a 3-state condition.

#### **VEC[3:0]**

Interrupt Output Vector: These four pins indicate which interrupt is currently being serviced by the device. Table 4 shows the code associated with each interrupt condition. VEC[3:0] are multiplexed with IOBIT[4:7].

#### **IACK**

**Interrupt Acknowledge:** Positive assertion. IACK signals when an interrupt is being serviced by the DSP1627. IACK remains asserted while in an interrupt service routine, and is cleared when the ireturn instruction is executed.

#### **TRAP**

**Trap Signal:** Positive assertion. When asserted, the processor is put into the trap condition, which normally causes a branch to the location 0x0046. The hardware development system (HDS) can configure the trap pin to cause an HDS trap, which causes a branch to location 0x0003. Although normally an input, the pin can be configured as an output by the HDS. As an output, the pin can be used to signal an HDS breakpoint in a multiple processor environment.

### **6.2 External Memory Interface**

The external memory interface is used to interface the DSP1627 to external memory and I/O devices. It supports read/write operations from/to program and data memory spaces. The interface supports four external memory segments. Each external memory segment can have an independent number of software-programmable wait-states. One hardware address is decoded, and an enable line is provided, to allow glueless I/O interfacing.

### AB[15:0]

#### External Memory Address Bus: Output only.

This 16-bit bus supplies the address for read or write operations to the external memory or I/O. During external memory accesses, AB[15:0] retain the value of the last valid external access.

### DB[15:0]

**External Memory Data Bus:** This 16-bit bidirectional data bus is used for read or write operations to the external memory or I/O.

#### **RWN**

**Read/Write Not:** When a logic 1, the pin indicates that the memory access is a read operation. When a logic 0, the memory access is a write operation.

#### **EXM**

**External Memory Select:** Input only. This signal is latched into the device on the rising edge of RSTB. The value of EXM latched in determines whether the internal ROM is addressable in the instruction/coefficient memory map. If EXM is low, internal ROM is addressable. If EXM is high, only external ROM is addressable in the instruction/coefficient memory map (see Table 5, Instruction/Coefficient Memory Maps). EXM chooses between MAP1 or MAP2 and between MAP3 or MAP4.

#### **EROM**

**External ROM Enable Signal:** Negative assertion. When asserted, the signal indicates an access to external program memory (see Table 5, Instruction/Coefficient Memory Maps). This signal's leading edge can be delayed via the ioc register (see Table 38).

#### **ERAMHI**

External RAM High Enable Signal: Negative assertion. When asserted, the signal indicates an access to external data memory addresses 0x8000 through 0xFFFF (see Table 6, Data Memory Map). This signal's leading edge can be delayed via the ioc register (see Table 38).

#### **ERAMLO**

**External RAM Low Enable Signal:** Negative assertion. When asserted, the signal indicates an access to external data memory addresses 0x4100 through 0x7FFF (see Table 6, Data Memory Map). This signal's leading edge can be delayed via the ioc register (see Table 38).

#### 10

**External I/O Enable Signal:** Negative assertion. When asserted, the signal indicates an access to external data memory addresses 0x4000 through 0x40FF (see Table 6, Data Memory Map). This memory segment is intended for memory-mapped I/O. This signal's leading edge can be delayed via the ioc register (see Table 38).

#### 6.3 Serial Interface #1

The serial interface pins implement a full-featured synchronous/asynchronous serial I/O channel. In addition, several pins offer a glueless TDM interface for multiprocessing communication applications (see Figure 5, Multiprocessor Communications and Connections).

#### DI1

**Data Input:** Serial data is latched on the rising edge of ICK1, either LSB or MSB first, according to the sioc register MSB field (see Table 22).

#### ICK1

**Input Clock:** The clock for serial input data. In active mode, ICK1 is an output; in passive mode, ICK1 is an input, according to the sioc register ICK field (see Table 22). Input has typically 0.7 V hysteresis.

#### ILD1

Input Load: The clock for loading the input buffer, sdx[in], from the input shift register isr. A falling edge of ILD1 indicates the beginning of a serial input word. In active mode, ILD1 is an output; in passive mode, ILD1 is an input, according to the sioc register ILD field (see Table 22). Input has typically 0.7 V hysteresis.

#### IBF1

**Input Buffer Full:** Positive assertion. IBF1 is asserted when the input buffer, sdx[in], is filled. IBF1 is negated by a read of the buffer, as in a0 = sdx. IBF1 is also negated by asserting RSTB.

#### **DO1**

**Data Output:** The serial data output from the output shift register (osr), either LSB or MSB first (according to the sioc register MSB field). DO1 changes on the rising edges of OCK1. DO1 is 3-stated when DOEN1 is high.

#### DOEN1

**Data Output Enable:** Negative assertion. An input when not in the multiprocessor mode. DO1 and SADD1 are enabled only if DOEN1 is low. DOEN1 is bidirectional when in the multiprocessor mode (tdms register MODE field set). In the multiprocessor mode, DOEN1 indicates a valid time slot for a serial output.

#### OCK1

**Output Clock:** The clock for serial output data. In active mode, OCK1 is an output; in passive mode, OCK1 is an input, according to the sioc register OCK field (see Table 22). Input has typically 0.7 V hysteresis.

#### OLD1

**Output Load:** The clock for loading the output shift register, osr, from the output buffer sdx[out]. A falling edge of OLD1 indicates the beginning of a serial output word. In active mode, OLD1 is an output; in passive, OLD1 is an input, according to the sioc register OLD field (see Table 22). Input has typically 0.7 V hysteresis.

#### OBE1

**Output Buffer Empty:** Positive assertion. OBE1 is asserted when the output buffer, sdx[out], is emptied (moved to the output shift register for transmission). It is cleared with a write to the buffer, as in sdx = a0. OBE1 is also set by asserting RSTB.

#### SADD1

**Serial Address:** Negative assertion. A 16-bit serial bit stream typically used for addressing during multiprocessor communication between multiple DSP16xx devices. In multiprocessor mode, SADD1 is an output when the tdms time slot dictates a serial transmission; otherwise, it is an input. Both the source and destination DSP can be identified in the transmission. SADD1 is always an output when not in multiprocessor mode and can be used as a second 16-bit serial output. See the DSP1611/17/18/27 Digital Signal Processor Information Manual for additional information. SADD1 is 3-stated when DOEN1 is high. When used on a bus, SADD1 should be pulled high through a 5 k $\Omega$  resistor.

#### SYNC1

Multiprocessor Synchronization: Typically used in the multiprocessor mode, a falling edge of SYNC1 indicates the first word (time slot 0) of a TDM I/O stream and causes the resynchronization of the active ILD1 and OLD1 generators. SYNC1 is an output when the tdms register SYNC field is set (i.e., selects the master DSP and uses time slot 0 for transmit). As an input, SYNC1 must be tied low unless part of a TDM interface. When used as an output, SYNC1 = [ILD1/OLD1]/8 or 16, depending on the setting of the SYNCSP field of the tdms register. When configured as described above, SYNC1 can be used to generate a slow clock for SIO operations. Input has typically 0.7 V hysteresis.

# 6.4 Parallel Host Interface or Serial Interface #2 and Control I/O Interface

This interface pin multiplexes a parallel host interface with a second serial I/O interface and a 4-bit I/O interface. The interface selection is made by writing the ESIO2 bit in the ioc register (see Table 38 and Section 4.1). The functions and signals for the second SIO correspond exactly with those in SIO#1. Therefore, the pin descriptions below discuss only PHIF and BIO pin functionality.

### PB[7:0]

**Parallel I/O Data Bus:** This 8-bit bidirectional bus is used to input data to, or output data from, the PHIF.

Note that PB[3:0] are pin multiplexed with SIO2 functionality, and PB[7:4] are pin multiplexed with BIO unit pins IOBIT[3:0] (see Section 4.1).

#### **PCSN**

**Peripheral Chip Select Not:** Negative assertion. PCSN is an input. While PCSN is low, the data strobes PIDS and PODS are enabled. While PCSN is high, the DSP1627 ignores any activity on PIDS and PODS.

#### **PBSEL**

**Peripheral Byte Select:** An input pin, configurable in software. Selects the high or low byte of pdx0 available for host accesses.

#### **PSTAT**

**Peripheral Status Select:** PSTAT is an input. When a logic 0, the PHIF will output the pdx0[out] register on the PB bus. When a logic 1, the PHIF will output the contents of the PSTAT register on PB[7:0].

#### **PIDS**

**Parallel Input Data Strobe:** An input pin, software configurable to support both *Intel* and *Motorola* protocols.

In *Intel* mode: Negative assertion. PIDS is pulled low by an external device to indicate that data is available on the PB bus. The DSP latches data on the PB bus on the rising edge (low-to-high transition) of PIDS or PCSN, whichever comes first.

In *Motorola* mode: PIDS(PRWN\*) functions as a read/write strobe. The external device sets PIDS(PRWN\*) to a logic 0 to indicate that data is available on the PB bus (write operation by the external device). A logic 1 on PIDS(PRWN\*) indicates an external read operation by the external device.

#### **PODS**

**Parallel Output Data Strobe:** An input pin, software configurable to support both *Intel* and *Motorola* protocols.

In *Intel* mode: Negative assertion. When PODS is pulled low by an external device, the DSP1627 places the contents of the parallel output register, pdx0, onto the PB bus

In *Motorola* mode: Software-configurable assertion level. The external device uses PODS(PDS\*) as its data strobe for both read and write operations.

#### **PIBF**

**Parallel Input Buffer Full:** An output pin with positive assertion; configurable in software. This flag is cleared after reset, indicating an empty input buffer pdx0[in].

PIBF is set immediately after the rising edge of PIDS or PCSN, indicating that data has been latched into the pdx0[in] register. When the DSP1627 reads the contents of this register, emptying the buffer, the flag is cleared.

Configured in software, PIBF may become the logical OR of the PIBF and POBE flags.

#### **POBE**

**Parallel Output Buffer Empty:** An output pin with positive assertion; configurable in software. This flag is set after reset, indicating an empty output buffer pdx0[out].

POBE is set immediately after the rising edge of PODS or PCSN, indicating that the data in pdx0[out] has been driven onto the PB bus. When the DSP1627 writes to pdx0[out], filling the buffer, this flag is cleared.

### 6.5 Control I/O Interface

This interface is used for status and control operations provided by the bit I/O unit of the DSP1627. It is pin multiplexed with the PHIF and VEC[3:0] pins (see Section 4.1). Setting the ESIO2 and EBIOH bits in the ioc register provides a full 8-bit BIO interface at the associated pins.

#### **IOBIT[7:0]**

**I/O Bits [7:0]:** Each of these bits can be independently configured as either an input or an output. As outputs, they can be independently set, toggled, or cleared. As inputs, they can be tested independently or in combinations for various data patterns.

<sup>\*</sup> Motorola mode signal name.

#### 6.6 JTAG Test Interface

The JTAG test interface has features that allow programs and data to be downloaded into the DSP via four pins. This provides extensive test and diagnostic capability. In addition, internal circuitry allows the device to be controlled through the JTAG port to provide on-chip in-circuit emulation. Lucent Technologies provides hardware and software tools to interface to the on-chip HDS via the JTAG port.

**Note:** The DSP1627 provides all JTAG/*IEEE* 1149.1 standard test capabilities including boundary scan. See the *DSP1611/17/18/27 Digital Signal Processor Information Manual* for additional information on the JTAG test interface.

#### TDI

**Test Data Input:** JTAG serial input signal. All serial-scanned data and instructions are input on this pin. This pin has an internal pull-up resistor.

#### **TDO**

**Test Data Output:** JTAG serial output signal. Serial-scanned data and status bits are output on this pin.

#### **TMS**

**Test Mode Select:** JTAG mode control signal that, when combined with TCK, controls the scan operations. This pin has an internal pull-up resistor.

#### **TCK**

**Test Clock:** JTAG serial shift clock. This signal clocks all data into the port through TDI, and out of the port through TDO, and controls the port by latching the TMS signal inside the state-machine controller.

## 7 Mask-Programmable Options

The DSP1627 contains a ROM that is mask-programmable. The selection of several programmable features is made when a custom ROM is encoded. These features select the input clock options, the instruction/coefficient memory map option, and the hardware emulation or ROM security option, as summarized in Table 59.

Table 59. DSP1627 ROM Options

Features	Options	Comments
Input Clock	CMOS Level	2.7 V, 3.0 V, and 5.0 V.
	Small Signal	2.7 V, 3.0 V, and 5.0 V.
	Crystal	2.7 V, 3.0 V, and 5.0 V.
Memory Map	DSP1627x36	36 Kwords IROM, no EROM in MAP1 or MAP3.
	DSP1627x32	32 Kwords IROM, 16 Kwords EROM in MAP1 and MAP3.
ROM Security	Nonsecure	Specify and link <b>1627hds.v</b> #, allows emulation.
	Secure	Specify and link <b>crc16.v#</b> <sup>†</sup> , no emulation capability.

<sup>\* 1627</sup>hds.v#(# indicates the current version number) is the relocatable HDS object code. It uses approximately 140 words and must reside in the first 4 Kwords of ROM.

## 7.1 Input Clock Options

For all input options, the input clock CKI can run at some fraction of the internal clock frequency by setting the PLL multiplication factors appropriately (see Section 4.12, Clock Synthesis). When the PLL is bypassed, the input clock CKI frequency is the internal clock frequency.

If the mask option for using an external crystal is chosen, the internal oscillator may be used as a noninverting input buffer by supplying a CMOS level to the CKI pin and leaving the CKI2 pin open.

#### 7.2 Memory Map Options

The DSP1627 offers a DSP1627x36 or a DSP1627x32 where the difference is in the instruction/coefficient memory maps. The DSP1627x36 contains 36 Kwords of internal ROM (IROM), but it doesn't support the use of IROM and external ROM (EROM) in the same memory map. The DSP1627x32 supports the use of only 32 Kwords of IROM with 16 Kwords of EROM in the same memory map. See Section 4.4 Memory Maps and Wait-States for further description.

### 7.3 ROM Security Options

The DSP1600 Hardware Development System (HDS) provides on-chip in-circuit emulation and requires that the relocatable HDS code be linked to the application code. This code's object file is called 1627hds.v#, where # is a unique version identifier. Refer to the DSP1627-ST software tools release for more specific information. If on-chip in-circuit emulation is desired, a nonsecure ROM must be chosen. If ROM security is desired with the DSP1627, the HDS cannot be used. To provide testing of the internal ROM contents on a secure ROM device, a cyclic redundancy check (CRC) program is called by and linked with the user's source code. The CRC code resides in the first 4 Kwords of ROM.

See the DSP1600 Support Tools Manual for more detailed information.

<sup>†</sup> crc16.v# is the cyclic redundancy check object code. It uses approximately 75 words and must reside in the first 4 Kwords of ROM. See the *DSP1600 Support Tools Manual* for detailed information.

#### 8 Device Characteristics

## 8.1 Absolute Maximum Ratings

Stresses in excess of the absolute maximum ratings can cause permanent damage to the device. These are absolute stress ratings only. Functional operation of the device is not implied at these or any other conditions in excess of those given in the operational sections of the data sheet. Exposure to absolute maximum ratings for extended periods can adversely affect device reliability.

External leads can be bonded and soldered safely at temperatures of up to 300 °C.

Voltage Range on VDD with Respect to Ground Using Devices D	Designed for 5 V Operation0.5 V to +7 V
Voltage Range on VDD with Respect to Ground Using Devices D	Designed for 3 V Operation–0.5 V to +4.6 V
Voltage Range on Any Pin	
Power Dissipation	1 W
Ambient Temperature Range	
Storage Temperature Range	–65 °C to +150 °C

## 8.2 Handling Precautions

All MOS devices must be handled with certain precautions to avoid damage due to the accumulation of static charge. Although input protection circuitry has been incorporated into the devices to minimize the effect of this static buildup, proper precautions should be taken to avoid exposure to electrostatic discharge during handling and mounting. Lucent Technologies employs a human-body model for ESD susceptibility testing. Since the failure voltage of electronic devices is dependent on the current, voltage, and hence, the resistance and capacitance, it is important that standard values be employed to establish a reference by which to compare test data. Values of 100 pF and  $1500~\Omega$  are the most common and are the values used in the Lucent Technologies human-body model test circuit. The breakdown voltage for the DSP1627 is greater than 2000 V.

## 8.3 Recommended Operating Conditions

**Table 60. Recommended Operating Conditions** 

Maximum Instruction Rate	Device Speed	Input Clock	Package	Supply Voltage VDD (V)		Ambient Temperature TA (°C)	
(MIPS)				Min	Max	Min	Max
50	20 ns	CMOS, small-signal, BQFP crystal rQFP		2.7	3.3	-40	85
80	12.5 ns	CMOS, small-signal, BQFP crystal or TQFP		2.7	3.3	-40	85
100	10 ns	CMOS, small-signal, crystal	BQFP or TQFP	3.0	3.6	-40	85
70	14 ns	CMOS, small-signal, BQFP crystal or TQFP		4.75	5.25	-40	85
90	11 ns	CMOS, small-signal, BQFP crystal or TQFF		4.75	5.25	-40	85

The ratio of the instruction cycle rate to the input clock frequency is 1:1 without the PLL (referred to as 1X operation) and M/(2N) with the PLL selected (see Section 4.12). Device speeds greater than 50 MIPS do not support 1X operation; use the PLL.

## 8 Device Characteristics (continued)

## 8.4 Package Thermal Considerations

The recommended operating temperature specified above is based on the maximum power, package type, and maximum junction temperature. The following equations describe the relationship between these parameters. If the applications' maximum power is less than the worst-case value, this relationship determines a higher maximum ambient temperature or the maximum temperature measured at top dead center of the package.

$$TA = TJ - P \times \Theta JA$$
  
 $TTDC = TJ - P \times \Theta J-TDC$ 

where TA is the still-air ambient temperature and TTDC is the temperature measured by a thermocouple at the top dead center of the package.

Maximum Junction Temperature (TJ) in 100-Pin BQFP	125 °C
100-pin BQFP Maximum Thermal Resistance in Still-Air-Ambient (ΘJA)	55 °C/W
100-pin BQFP Maximum Thermal Resistance, Junction to Top Dead Center (ΘJ-TDC)	12 °C/W
Maximum Junction Temperature (TJ) in 100-Pin TQFP	125 °C
100-pin TQFP Maximum Thermal Resistance in Still-Air-Ambient (ΘJA)	30 °C/W
100-pin TQFP Maximum Thermal Resistance, Junction to Top Dead Center (ΘJ-TDC)	6 °C/W

WARNING: Due to package thermal constraints, proper precautions in the user's application should be taken to avoid exceeding the maximum junction temperature of 125 °C. Otherwise, the device will be affected adversely.

## 9 Electrical Characteristics and Requirements

The following electrical characteristics are preliminary and are subject to change. Electrical characteristics refer to the behavior of the device under specified conditions. Electrical requirements refer to conditions imposed on the user for proper operation of the device. The parameters below are valid for the conditions described in Section 8.3, Recommended Operating Conditions.

**Table 61. Electrical Characteristics and Requirements** 


Parameter	Symbol	Min	Max	Unit
Input Voltage:				
Low	VIL	-0.3	0.3 * VDD	V
High	VIH	0.7 * VDD	VDD + 0.3	V
Input Current (except TMS, TDI):				
Low (VIL = $0 \text{ V}$ , VDD = $5.25 \text{ V}$ )	lıL	<b>–</b> 5	_	μΑ
High (VIH = 5.25 V, VDD = 5.25 V)	lін	_	5	μΑ
Input Current (TMS, TDI):				
Low ( $VIL = 0 V, VDD = 5.25 V$ )	lı∟	-100	_	μΑ
High (VIH = 5.25 V, VDD = 5.25 V)	lін	_	5	μΑ
Output Low Voltage:				
Low (IOL = 2.0 mA)	Vol	_	0.4	V
Low (IOL = $50 \mu A$ )	Vol	_	0.2	V
Output High Voltage:				
High (IOH = $-2.0 \text{ mA}$ )	Voн	VDD - 0.7	_	V
High (IOH = $-50 \mu$ A)	Voн	VDD - 0.2	_	V
Output 3-State Current:				
Low (VDD = 5.25 V, VIL = 0 V)	lozl	-10	_	μΑ
High (VDD = 5.25 V, VIH = 5.25 V)	lozh	_	10	μΑ
Input Capacitance	CI	_	5	pF

Table 62. Electrical Requirements for Mask-Programmable Input Clock Options

Parameter	Symbol	Min	Max	Unit
CKI CMOS Level Input Voltage:				
Low	VIL	-0.3	0.3 * VDD	V
High	VIH	0.7 * VDD	VDD + 0.3	V
Small-signal Peak-to-peak Voltage* (on CKI)	Vpp	0.6	_	V
Small-signal Input Duty Cycle <sup>†</sup>	DCyc	45	55	%
Small-signal Input Voltage Range (pins: CKI, CKI2)	Vin	0.2 * VDD	0.6 * VDD	V
Small-signal Buffer Frequency Range	fss	_	35	MHz
Frequency Range of Fundamental Mode or Overtone Crystal	fX	5	25	MHz
Series Resistance of Fundamental Mode or Overtone Crystal (pins: CKI, CKI2)	RS	_	40	Ω
Mutual Capacitance of Crystal (includes board stray capacitance)	C0	_	7	pF

<sup>\*</sup> The small-signal buffer must be used in single-ended mode where an ac waveform (sine or square) is applied to CKI and a dc voltage approximately equal to the average value of CKI is applied to CKI2, as shown in the figure below. The maximum allowable ripple on CKI2 is 100 mV.

Duty cycle for a sine wave is defined as the percentage of time during each clock cycle that the voltage on CKI exceeds the voltage on CKI2.



## 9 Electrical Characteristics and Requirements (continued)

**Additional Electrical Requirements with Crystal Option:** See Section 13, Crystal Electrical Characteristics and Requirements.

Table 63. PLL Electrical Specifications, VCO Frequency Ranges

Parameter	Symbol	Min	Max	Unit
VCO frequency range $(VDD = 3 V \pm 10\%)^*$	fvco	50	160	MHz
VCO frequency range (VDD = 3.0 V - 3.6 V)*	fvco	50	200	MHz
VCO frequency range (VDD = 5 V ± 5%)*	fvco	70	180	MHz
Input Jitter at CKI	_	_	200	ps-rms

<sup>\*</sup> The M and N counter values in the pllc register must be set so that the VCO will operate in the appropriate range (see Table 63). Choose the lowest value of N and then the appropriate value of M for finternal clock = fcki x (M/(2N)) = fvco/2.

Table 64. PLL Electrical Specifications and pllc Register Settings

М	VDD	plic13 (ICP)	pllc12	pllc[11:8]	Typical Lock-in Time (μs)*
IVI	<b>V</b> DD	plic 13 (ICF)	(SEL5V)	(LF[3:0])	Typical Lock-in Time (μs)
23—24	2.7 V – 3.6 V	1	0	1011	30
21—22	2.7 V – 3.6 V	1	0	1010	30
19—20	2.7 V – 3.6 V	1	0	1001	30
16—18	2.7 V – 3.6 V	1	0	1000	30
12—15	2.7 V – 3.6 V	1	0	0111	30
8—11	2.7 V – 3.6 V	1	0	0110	30
2—7	2.7 V – 3.6 V	1	0	0100	30
19—20	5 V ± 5%	1	1	1110	30
17—18	5 V ± 5%	1	1	1101	30
16	5 V ± 5%	1	1	1100	30
14—15	5 V ± 5%	1	1	1011	30
12—13	5 V ± 5%	1	1	1010	30
10—11	5 V ± 5%	1	1	1001	30
8—9	5 V ± 5%	1	1	1000	30
7	5 V ± 5%	1	1	0111	30
5—6	5 V ± 5%	1	1	0110	30
2—4	5 V ± 5%	1	1	0101	30

Lock-in time represents the time following assertion of the PLLEN bit of the pllc register during which the PLL output clock is unstable. The DSP must operate from the 1X CKI input clock or from the slow ring oscillator while the PLL is locking. Completion of the lock-in interval is indicated by assertion of the LOCK flag.

# 9 Electrical Characteristics and Requirements (continued)




Figure 9. Plot of VoH vs. IoH Under Typical Operating Conditions




Figure 10. Plot of Vol vs. Iol Under Typical Operating Conditions

## 9 Electrical Characteristics and Requirements (continued)

#### 9.1 Power Dissipation

Power dissipation is highly dependent on DSP program activity and the frequency of operation. The typical power dissipation listed is for a selected application. The following electrical characteristics are preliminary and are subject to change.

Table 65. Power Dissipation and Wake-Up Latency

Operating Mode	Typica	al Power D	issipation	(mW)	Wake-Up Latency																			
(Unused Inputs at VDD or VSS)		its ON 7:4] = 0x0		its OFF 7:4] = 0xf	(PLL No During Wa	t Used ke State)	(PLL During W	Used ake State)																
	5 V	3 V	5 V	3 V	5 V 3 V		5 V	3 V																
Normal Operation ioc = 0x0180 PLL Disabled																								
CKI & CKO = 40 MHz																								
CMOS	220	74	214	72	_	-	_	_																
Crystal Oscillator	241	80	235	78	_	-	-	_																
Small Signal	223	76	217	74	_	-	_	_																
CKI & CKO = 0 MHz																								
CMOS	0.19	0.067	0.19	0.067	_	-	-	_																
Small Signal	3.0	1.1	3.0	1.1	_	_	-	_																
Normal Operation ioc = 0x0180  PLL Enabled pllc = 0xFC0E  CKI = 10 MHz CKO = 40 MHz																								
CMOS	228	77	222	75	_		T		_		_		_		-	_								
Crystal Oscillator	249	83	243	81	_	-	-	_																
Small Signal	231	78	225	77	_	-	-	_																
	Power	Managem	ent Mode	s CKO =	40 MHz																			
Standard Sleep, External Interrupt alf[15] = 1, ioc = 0x0180 PLL Disabled During Sleep																								
CMOS	25.2	8.4	17.8	5.6	3T	*	3T*	+ tL <sup>†</sup>																
Crystal Oscillator	46.2	14.0	38.8	12.0	3T	*	3T* + t∟ <sup>†</sup>																	
Small Signal	28.0	9.8	20.8	7.2	3T	*	3T*	+ tL <sup>†</sup>																
Standard Sleep, External Interrupt alf[15] = 1, ioc = 0x0180 PLL Enabled During Sleep																								
CMOS	33.2	10.9	25.8	7.5	_		_		_		_		_				_		_		_			T*
Crystal Oscillator	54.0	17.1	46.0	14.0	_	_		T*																
Small Signal	36.0	12.4	28.8	9.2	_		3	T*																
Sleep with Slow Internal Clock Crystal/Small Signal Enabled powerc[15:14] = 01, alf[15] = 1, ioc = 0x0180 PLL Disabled During Sleep																								
CMOS	1.4	0.4	1.1	0.3	1.5 µs	5.0 μs	1.5 μs + tL	5.0 μs + tL																
Crystal Oscillator	21.9	6.2	21.8	6.1	1.5 µs	5.0 μs	1.5 μs + tL	5.0 μs + tL																
Small Signal	3.9	2.1	3.8	2.0	1.5 µs	5.0 μs	1.5 μs + tL	5.0 μs + tL																

<sup>\*</sup> T = CKI clock cycle for 1X input clock option or T = CKI clock cycle divided by M/(2N) for PLL clock option (see Section 4.12).

<sup>†</sup> tL = PLL lock time (see Table 64).

## 9 Electrical Characteristics and Requirements (continued)

Table 65. Power Dissipation and Wake-Up Latency (continued)

Operating Mode	Typic	al Power D	Dissipation	(mW)	Wake-Up Latency		
(Unused inputs at VDD or VSS)	I/O Un powerc[7	':4] = 0x0	I/O Uni powerc[	ts OFF 7:4] = 0xf	(PLL Not Used During Wake State)	(PLL During W	Used /ake State)
	5 V	3 V	5 V	3 V	5 V 3 V	5 V	3 V
Sleep with Slow Internal Clock							
Crystal/Small Signal Enabled							
powerc[15:14] = 01,							
alf[15] = 1, $ioc = 0x0180$							
PLL Enabled During Sleep							
CMOS	8.3	3.0	7.5	2.7	_	1.5 µs	5.0 μs
Crystal Oscillator	27.5	9.9	24.5	8.8	_	1.5 μs	5.0 μs
Small Signal	10.0	4.5	10.0	4.0	_	1.5 μs	5.0 μs
Sleep with Slow Internal Clock				•	•	•	•
Crystal/Small Signal Disabled							
powerc[15:14] = 11,							
alf[15] = 1, $ioc = 0x0180$							
PLL Disabled During Sleep							
Crystal Oscillator	0.67	0.24	0.56	0.16	20 ms	20 μ	s + tL <sup>†</sup>
Small Signal	0.67	0.24	0.56	0.16	20 μs		s + tL <sup>†</sup>
Software Stop				1	· · · · · · · · · · · · · · · · · · ·	•	
powerc[15:12] = 0011							
PLL Disabled During STOP							
CMOS	0.19	0.067	0.19	0.067	3T*	3T*	+ tL <sup>†</sup>
Software Stop						1	
powerc[15:12] = 1111							
PLL Disabled During STOP							
Crystal Oscillator	0.19	0.067	0.19	0.067	20 ms	20 µ	ıs +t∟ <sup>†</sup>
Small Signal	0.19	0.067	0.19	0.067	20 μs	20 µ	s + tL <sup>†</sup>
Hardware Stop (STOP = Vss)				1		•	
powerc[15:12] = 0000							
PLL Disabled During STOP							
CMOS	0.19	0.067	0.19	0.067	3T*		
Crystal Oscillator	20.0	6.0	20.0	6.0	3T*		_
Small Signal	3.0	1.1	3.0	1.1	3T*		
Hardware Stop (STOP = Vss)				1		· ·	
powerc[15:12] = 0000							
PLL Enabled During STOP							
CMOS	5.6	2.4	5.6	2.4	3T*	3	BT*
Crystal Oscillator	25.6	8.4	25.6	8.4	3T*	3	ST*
Small Signal	8.6	3.5	8.6	3.5	3T*	3	BT*
<u> </u>	1	1		1	1	1	

<sup>\*</sup> T = CKI clock cycle for 1X input clock option or T = CKI clock cycle divided by M/(2N) for PLL clock option (see Section 4.12).

The power dissipation listed is for internal power dissipation only. Total power dissipation can be calculated on the basis of the application by adding  $C \times VDD/2 \times f$  for each output, where C is the additional load capacitance and f is the output frequency.

<sup>†</sup> tL = PLL lock time (see Table 64).

#### 9 Electrical Characteristics and Requirements (continued)

Power dissipation due to the input buffers is highly dependent on the input voltage level. At full CMOS levels, essentially no dc current is drawn. However, for levels between the power supply rails, especially at or near the threshold of VDD/2, high currents can flow. Although input and I/O buffers may be left untied (since the input voltage levels of the input and I/O buffers are designed to remain at full CMOS levels when not driven by the DSP), it is still recommended that unused input and I/O pins be tied to Vss or VDD through a 10 k $\Omega$  resistor to avoid application ambiguities. Further, if I/O pins are tied high or low, they should be pulled fully to Vss or VDD.

WARNING: The device needs to be clocked for at least six CKI cycles during reset after powerup. Otherwise, high currents may flow.

## 10 Timing Characteristics for 5 V Operation

The following timing characteristics and requirements are preliminary information and are subject to change. Timing characteristics refer to the behavior of the device under specified conditions. Timing requirements refer to conditions imposed on the user for proper operation of the device. All timing data is valid for the following conditions:

TA = -40 °C to +85 °C (See Section 8.3.)

VDD = 5 V  $\pm$  5%, Vss = 0 V (See Section 8.3.)

Capacitance load on outputs (CL) = 50 pF, except for CKO, where CL = 20 pF.

Output characteristics can be derated as a function of load capacitance (CL).

All outputs:  $0.03 \text{ ns/pF} \le dt/dCL \le 0.06 \text{ ns/pF}$  for  $10 \le CL \le 100 \text{ pF}$  at VIH for rising edge and at VIL for falling edge.

For example, if the actual load capacitance is 30 pF instead of 50 pF, the derating for a rising edge is (30 - 50) pF x 0.06 ns/pF = 1.2 ns **less** than the specified rise time or delay that includes a rise time.

Test conditions for inputs:

- Rise and fall times of 4 ns or less
- Timing reference levels for delays = VIH, VIL


Test conditions for outputs (unless noted otherwise):

- CLOAD = 50 pF; except for CKO, where CLOAD = 20 pF
- Timing reference levels for delays = VIH, VIL
- 3-state delays measured to the high-impedance state of the output driver

For the timing diagrams, see Table 62 for input clock requirements.

Unless otherwise noted, CKO in the timing diagrams is the free-running CKO.

#### 10.1 DSP Clock Generation



5-4009 (F).a

- \* See Table 62 for input clock electrical requirements.
- † Free-running clock.
- ‡ Wait-stated clock (see Table 38).
- § W = number of wait-states.

Figure 11. I/O Clock Timing Diagram

**Table 66. Timing Requirements for Input Clock** 

Abbreviated Reference	Parameter	14 ns and 11 ns*		ns*
		Min	Max	Unit
t1	Clock In Period (high to high)	20	<u></u> †	ns
t2	Clock In Low Time (low to high)	10	_	ns
t3	Clock In High Time (high to low)	10	_	ns

<sup>\*</sup> Device speeds greater than 50 MIPS do not support 1X operation. Use the PLL.

Table 67. Timing Characteristics for Input Clock and Output Clock

Abbreviated Reference	Parameter	14 ns		11 ns		Unit
		Min	Max	Min	Max	
t4	Clock Out High Delay	_	10	_	8	ns
t5	Clock Out Low Delay (high to low)	_	10	_	8	ns
t6	Clock Out Period (low to low)	T*	_	T*	_	ns
t6a	Clock Out Period with SLOWCKI Bit Set in powerc Register (low to low)	0.74	1.6	0.74	1.6	μs


T = internal clock period, set by CKI or by CKI and the PLL parameters.

<sup>†</sup> Device is fully static, t1 is tested at 100 ns for 1X input clock option, and memory hold time is tested at 0.1 s.

#### 10.2 Reset Circuit

The DSP1627 has a powerup reset circuit that automatically clears the JTAG controller upon powerup. If the supply voltage falls below VDD MIN\* and a reset is required, the JTAG controller must be reset—even if the JTAG port isn't being used—by applying six low-to-high clock edges on TCK with TMS held high, followed by the usual RSTB and CKI reset sequence. Figure 12 shows two separate events: an initial powerup and a powerup following a drop in the power supply voltage.

\* See Table 60, Recommended Operating Condiitons.



5-2253 (F).a

Notes:

See Table 62 for CKI electrical requirements and Table 71 for TCK timing requirements.

When both INT0 and RSTB are asserted, all output and bidirectional pins (except TDO, which 3-states by JTAG control) are put in a 3-state condition. With RSTB asserted and INT0 not asserted, EROM, ERAMHI, ERAMLO, IO, DSEL, and RWN outputs remain high, and CKO remains a free-running clock.

TMS and TDI signals have internal pull-up devices.

Figure 12. Powerup Reset and Chip Reset Timing Diagram

Table 68. Timing Requirements for Powerup Reset and Chip Reset

Abbreviated Reference	Paramete	r	Min	Max	Unit
t8	Reset Pulse (low to high	h)	6T	_	ns
t9	VDD Ramp		_	10	ms
t146	VDD MIN to RSTB Low		2T	_	ns
		Crystal*	20	_	ms
		Small-signal	20	_	μs
t151	TMS High		6 * Ттск <sup>†</sup>	_	ns
t152	JTAG Reset to	CMOS	2T	_	ns
	RSTB Low	Crystal*	20 ms – 6 * Ттск if 6 * Ттск < 20 ms	_	
			0 if 6 * T⊤cк ≥ 20 ms	_	
		Small-Signal	20 μs – 6 * Ττcκ if 6 * Ττcκ < 20 μs	_	
			0 if 6 * Tτcκ ≥ 20 μs	_	
t153	RSTB Rise (low to high	)	_	95	ns

<sup>\*</sup> With external components as specified in Table 62.


<sup>†</sup> TTCK = t12 = TCK period. See Table 71 for TCK timing requirements.

Table 69. Timing Characteristics for Powerup Reset and Chip Reset

Abbreviated Reference	Parameter	Min	Max	Unit
t10	RSTB Disable Time (low to 3-state)	_	100	ns
t11	RSTB Enable Time (high to valid)	_	100	ns

**Note:** The device needs to be clocked for at least six CKI cycles during reset after powerup. Otherwise, high currents may flow.

#### 10.3 Reset Synchronization



<sup>\*</sup> See Table 62 for input clock electrical requirements.


Note: CKO1 and CKO2 are two possible CKO states before reset. CKO is free-running.

Figure 13. Reset Synchronization Timing

Table 70. Timing Requirements for Reset Synchronization Timing

Abbreviated Reference	Parameter	Min	Max	Unit
t126	Reset Setup (high to high)	1.5	T/2 – 5	ns

## 10.4 JTAG I/O Specifications



5-4017 (F)

Figure 14. JTAG Timing Diagram


Table 71. Timing Requirements for JTAG Input/Output

Abbreviated Reference	Parameter	Min	Max	Unit
t12	TCK Period (high to high)	50		ns
t13	TCK High Time (high to low)	22.5	_	ns
t14	TCK Low Time (low to high)	22.5	_	ns
t15	TMS Setup Time (valid to high)	7.5	_	ns
t16	TMS Hold Time (high to invalid)	2	_	ns
t17	TDI Setup Time (valid to high)	7.5	_	ns
t18	TDI Hold Time (high to invalid)	2	_	ns

Table 72. Timing Characteristics for JTAG Input/Output

Abbreviated Reference	Parameter	Min	Max	Unit
t19	TDO Delay (low to valid)	_	19	ns
t20	TDO Hold (low to invalid)	0	_	ns

#### 10.5 Interrupt



<sup>\*</sup> CKO is free-running.

Figure 15. Interrupt Timing Diagram

**Table 73. Timing Requirements for Interrupt** 

Abbreviated Reference	Parameter	Min	Max	Unit
t21	Interrupt Setup (high to low)	15		ns
t22	INT Assertion Time (high to low)	2T	_	ns

Note: Interrupt is asserted during an interruptible instruction and no other pending interrupts.

**Table 74. Timing Characteristics for Interrupt** 

Abbreviated Reference	Parameter	Min	Max	Unit
t23	IACK Assertion Time (low to high)	_	T/2 + 7.5	ns
t24	VEC Assertion Time (low to high)	_	9.5	ns
t25	IACK Invalid Time (low to low)	_	7.5	ns
t26	VEC Invalid Time (low to low)	_	9.5	ns

Note: Interrupt is asserted during an interruptible instruction and no other pending interrupts.

<sup>†</sup> IACK assertion is guaranteed to be enclosed by VEC[3:0] assertion.

#### 10.6 Bit Input/Output (BIO)




Figure 16. Write Outputs Followed by Read Inputs (cbit = Immediate; a1 = sbit)

Table 75. Timing Requirements for BIO Input Read

Abbreviated Reference	Parameter	Min	Max	Unit
t27	IOBIT Input Setup Time (valid to high)	12	_	ns
t28	IOBIT Input Hold Time (high to invalid)	0	_	ns

**Table 76. Timing Characteristics for BIO Output** 

Abbreviated Reference	Parameter	Min	Max	Unit
t29	IOBIT Output Valid Time (low to valid)	_	7.5	ns
t144	IOBIT Output Hold Time (low to invalid)	1	_	ns





Figure 17. Write Outputs and Test Inputs (cbit = Immediate)

**Table 77. Timing Requirements for BIO Input Test** 

Abbreviated Reference	Parameter	Min	Max	Unit
t141	IOBIT Input Setup Time (valid to low)	12	_	ns
t142	IOBIT Input Hold Time (low to invalid)	0	_	ns

#### 10.7 External Memory Interface

The following timing diagrams, characteristics, and requirements do not apply to interactions with delayed external memory enables unless so stated. See the *DSP1611/17/18/27 Digital Signal Processor Information Manual* for a detailed description of the external memory interface including other functional diagrams.



<sup>\*</sup> W = number of wait-states.


Figure 18. Enable Transition Timing

Table 78. Timing Characteristics for External Memory Enables (EROM, ERAMHI, IO, ERAMLO)

Abbreviated Reference	Parameter	Min	Max	Unit
t33	CKO to ENABLE Active (low to low)	0	7	ns
t34	CKO to ENABLE Inactive (low to high)	-1	6	ns

Table 79. Timing Characteristics for Delayed External Memory Enables (ioc = 0x000F)

Abbreviated Reference	Parameter	Min	Max	Unit
t33	CKO to Delayed ENABLE Active (low to low)	T/2 – 2	T/2 + 7	ns



5-4021 (F).a

Figure 19. External Memory Data Read Timing Diagram


**Table 80. Timing Characteristics for External Memory Access** 

Abbreviated Reference	Parameter	Min	Max	Unit
t127	Enable Width (low to high)	T(1 + W) - 4	_	ns
t128	Address Valid (enable low to valid)	_	2	ns

Table 81. Timing Requirements for External Memory Read (EROM, ERAMHI, IO, ERAMLO)

Abbreviated	Parameter	14 ns		14 ns 11 ns		Unit
Reference		Min	Max	Min	Max	
t129	Read Data Setup (valid to enable high)	12	_	11	_	ns
t130	Read Data Hold (enable high to hold)	0	_	0	_	ns
t150	External Memory Access Time (valid to valid)	_	T(1 + W) - 13	_	T(1 + W) – 12	ns

<sup>\*</sup> W = number of wait-states.




\* W = number of wait-states.

Figure 20. External Memory Data Write Timing Diagram

**Table 82. Timing Characteristics for External Memory Data Write (All Enables)** 

Abbreviated	Parameter	14 ns	14 ns			Unit
Reference		Min	Max	Min	Max	
t131	Write Overlap (enable low to 3-state)	_	0	_	0	ns
t132	RWN Advance (RWN high to enable high)	0	_	0		ns
t133	RWN Delay (enable low to RWN low)	0	_	0	_	ns
t134	Write Data Setup (data valid to RWN high)	T(1 + W)/2 - 3	_	T(1 + W)/2 - 2	_	ns
t135	RWN Width (low to high)	T(1 + W) - 5.5	_	T(1 + W) - 5.5		ns
t136	Write Address Setup (address valid to RWN low)	0	_	0	_	ns



5-4023 (F).a

Figure 21. Write Cycle Followed by Read Cycle

Table 83. Timing Characteristics for Write Cycle Followed by Read Cycle

Abbreviated Reference	Parameter	Min	Max	Unit
t131	Write Overlap (enable low to 3-state)		0	ns
t137	Write Data 3-state (RWN high to 3-state)	_	2	ns
t138	Write Data Hold (RWN high to data hold)	0	_	ns
t139	Write Address Hold (RWN high to address hold)	0	1	ns

<sup>\*</sup> W = number of wait-states.

#### 10.8 PHIF Specifications

For the PHIF, "READ" means read by the external user (output by the DSP); "WRITE" is similarly defined. The 8-bit reads/writes are identical to one-half of a 16-bit access.




Figure 22. PHIF Intel Mode Signaling (Read and Write) Timing Diagram

Table 84. Timing Requirements for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t41	PODS to PCSN Setup (low to low)	0	_	ns
t42	PCSN to PODS Hold (high to high)	0	_	ns
t43	PIDS to PCSN Setup (low to low)	0	_	ns
t44	PCSN to PIDS Hold (high to high)	0	_	ns
t45*	PSTAT to PCSN Setup (valid to low)	4.5	_	ns
t46*	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47*	PBSEL to PCSN Setup (valid to low)	4.5	_	ns
t48*	PCSN to PBSEL Hold (high to invalid)	0	_	ns
t51*	PB Write to PCSN Setup (valid to high)	7.5	_	ns
t52*	PCSN to PB Write Hold (high to invalid)	4	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PIDS and PODS signals. An output transaction (read) is initiated by PCSN or PODS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PODS going low, if PODS goes low after PCSN. An output transaction is completed by PCSN or PODS going high, whichever comes first. An input transaction is initiated by PCSN or PIDS going low, whichever comes last. An input transaction is completed by PCSN or PIDS going high, whichever comes first. All requirements referenced to PCSN apply to PIDS or PODS, if PIDS or PODS is the controlling signal.

Table 85. Timing Characteristics for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t49*	PCSN to PB Read (low to valid)	_	13	ns
t50*	PCSN to PB Read Hold (high to invalid)	3	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PIDS and PODS signals. An output transaction (read) is initiated by PCSN or PODS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PODS going low, if PODS goes low after PCSN. An output transaction is completed by PCSN or PODS going high, whichever comes first. An input transaction is initiated by PCSN or PIDS going low, whichever comes last. An input transaction is completed by PCSN or PIDS going high, whichever comes first. All requirements referenced to PCSN apply to PIDS or PODS, if PIDS or PODS is the controlling signal.




Figure 23. PHIF Intel Mode Signaling (Pulse Period and Flags) Timing Diagram

Table 86. Timing Requirements for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t55	PCSN/PODS/PIDS Pulse Width (high to low)	15	_	ns
t56	PCSN/PODS/PIDS Pulse Width (low to high)	15	_	ns

Table 87. Timing Characteristics for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t53*	PCSN/PODS to POBE <sup>†</sup> (high to high)	_	15	ns
t54*	PCSN/PIDS to PIBF <sup>†</sup> (high to high)	_	15	ns

<sup>\*</sup> t53 should be referenced to the rising edge of PCSN or PODS, whichever comes first. t54 should be referenced to the rising edge of PCSN or PIDS, whichever comes first.

<sup>†</sup> POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram (positive assertion levels shown). t53 and t54 apply to the inverted levels as well as those shown.




Figure 24. PHIF Motorola Mode Signaling (Read and Write) Timing Diagram

Table 88. Timing Requirements for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t41	PDS <sup>†</sup> to PCSN Setup (valid to low)	0	_	ns
t42	PCSN to PDS <sup>†</sup> Hold (high to invalid)	0	_	ns
t43	PRWN to PCSN Setup (valid to low)	4.5	_	ns
t44	PCSN to PRWN Hold (high to invalid)	0	_	ns
t45*	PSTAT to PCSN Setup (valid to low)	4.5	_	ns
t46*	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47*	PBSEL to PCSN Setup (valid to low)	4.5	_	ns
t48*	PCSN to PBSEL Hold (high to invalid)	0	_	ns
t51*	PB Write to PCSN Setup (valid to high)	8	_	ns
t52*	PCSN to PB Write Hold (high to invalid)	4	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PDS signal. An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

Table 89. Timing Characteristics for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t49*	PCSN to PB Read (low to valid)	_	13	ns
t50*	PCSN to PB Read (high to invalid)	3	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PDS signal. An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

<sup>†</sup> PDS is programmable to be active-high or active-low. It is shown active-low in Figures 24 and 25. POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram. t53 and t54 apply to the inverted levels as well as those shown.

<sup>†</sup> PDS is programmable to be active-high or active-low. It is shown active-low in Figures 24 and 25. POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram. t53 and t54 apply to the inverted levels as well as those shown.




Figure 25. PHIF Motorola Mode Signaling (Pulse Period and Flags) Timing Diagram

Table 90. Timing Characteristics for PHIF Motorola Mode Signaling


Abbreviated Reference	Parameter	Min	Max	Unit
t53*	PCSN/PDS <sup>†</sup> to POBE <sup>†</sup> (high to high)		15	ns
t54*	PCSN/PDS <sup>†</sup> to PIBF <sup>†</sup> (high to high)		15	ns

<sup>\*</sup> An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, t53 and t54 should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

Table 91. Timing Requirements for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t55	PCSN/PDS/PRWN Pulse Width (high to low)	15	_	ns
t56	PCSN/PDS/PRWN Pulse Width (low to high)	15	_	ns

<sup>†</sup> PDS is programmable to be active-high or active-low. It is shown active-low in Figures 24 and 25. POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram. t53 and t54 apply to the inverted levels as well as those shown.



Motorola mode signal name.

Figure 26. PHIF Intel or Motorola Mode Signaling (Status Register Read) Timing Diagram

Table 92. Timing Requirements for Intel and Motorola Mode Signaling (Status Register Read)

Abbreviated Reference	Parameter	Min	Max	Unit
t45†	PSTAT to PCSN Setup (valid to low)	4.5	_	ns
t46 <sup>‡</sup>	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47†	PBSEL to PCSN Setup (valid to low)	4.5	_	ns
t48‡	PCSN to PBSEL Hold (high to invalid)	0	_	ns

<sup>†</sup> t45, t47, and t49 are referenced to the falling edge of PCSN or PODS(PDS), whichever occurs last.

Table 93. Timing Characteristics for Intel and Motorola Mode Signaling (Status Register Read)

Abbreviated Reference	Parameter	Min	Max	Unit
t49†	PCSN to PB Read (low to valid)	_	13	ns
t50‡	PCSN to PB Read Hold (high to invalid)	3	_	ns

<sup>†</sup> t45, t47, and t49 are referenced to the falling edge of PCSN or PODS(PDS), whichever occurs last.

<sup>‡</sup> t46, t48, and t50 are referenced to the rising edge of PCSN or PODS(PDS), whichever occurs first.

<sup>‡</sup> t46, t48, and t50 are referenced to the rising edge of PCSN or PODS(PDS), whichever occurs first.




Figure 27. PHIF, PIBF, and POBE Reset Timing Diagram

Table 94. PHIF Timing Characteristics for PHIF, PIBF, and POBE Reset

Abbreviated Reference	Parameter	Min	Max	Unit
t57	RSTB Disable to POBE/PIBF* (high to valid)	_	19	ns
t58	RSTB Enable to POBE/PIBF* (low to invalid)	3	19	ns

<sup>\*</sup> After reset, POBE and PIBF always go to the levels shown, indicating output buffer empty and input buffer empty. The DSP program, however, may later invert the definition of the logic levels for POBE and PIBF. t57 and t58 continue to apply.



5-4776 (F)


Figure 28. PHIF, PIBF, and POBE Disable Timing Diagram

Table 95. PHIF Timing Characteristics for POBE and PIBF Disable

Abbreviated Reference	Parameter	Min	Max	Unit
t59	CKO to POBE/PIBF Disable (high/low to disable)		15	ns

<sup>†</sup> POBE and PIBF can be programmed to be active-high or active-low. They are shown active-high. The timing characteristic for active-low is the same as for active-high.

## 10.9 Serial I/O Specifications



<sup>\*</sup> N = 16 or 8 bits.

Figure 29. SIO Passive Mode Input Timing Diagram

**Table 96. Timing Requirements for Serial Inputs** 


Abbreviated Reference	Parameter	Min	Max	Unit
t70 Clock Period (high to high) <sup>‡</sup>		40	†	ns
t71	Clock Low Time (low to high)	18	_	ns
t72	Clock High Time (high to low)	18	_	ns
t73	Load High Setup (high to high)	6	_	ns
t74	Load Low Setup (low to high)	6		ns
t75	Load High Hold (high to invalid)	0	_	ns
t77	Data Setup (valid to high)	5	_	ns
t78	Data Hold (high to invalid)	0	_	ns

<sup>†</sup> Device is fully static; t70 is tested at 200 ns.

**Table 97. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t79	IBF Delay (high to high)	_	22	ns

<sup>‡</sup> For Multiprocessor mode, see note in Section 10.10.



ILD goes high during bit 6 (of 0:15), N = 8 or 16.


Figure 30. SIO Active Mode Input Timing Diagram

**Table 98. Timing Requirements for Serial Inputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t77	Data Setup (valid to high)	5	_	ns
t78	Data Hold (high to invalid)	0	_	ns

**Table 99. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t76a	ILD Delay (high to low)	_	22	ns
t101	ILD Hold (high to invalid)	4	_	ns
t79	IBF Delay (high to high)	_	22	ns



See sioc register, MSB field to determine if B0 is the MSB or LSB. See sioc register, ILEN field to determine if the DO word length is 8 bits or 16 bits.

Figure 31. SIO Passive Mode Output Timing Diagram

**Table 100. Timing Requirements for Serial Inputs** 


Abbreviated Reference	Parameter	Min	Max	Unit
t80	Clock Period (high to high) <sup>‡</sup>	40	†	ns
t81	Clock Low Time (low to high)	18	_	ns
t82	Clock High Time (high to low)	18	_	ns
t83	Load High Setup (high to high)	6	_	ns
t84	Load Low Setup (low to high)	6	_	ns
t85	Load Hold (high to invalid)	0	_	ns

Device is fully static; t80 is tested at 200 ns.

**Table 101. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter M		Max	Unit
t87	Data Delay (high to valid)	_	22	ns
t88	Enable Data Delay (low to active)	_	22	ns
t89	Disable Data Delay (high to 3-state)	_	22	ns
t90	Data Hold (high to invalid)	4	_	ns
t92	Address Delay (high to valid)	_	22	ns
t93	Address Hold (high to invalid)	4	_	ns
t94	Enable Delay (low to active)	_	22	ns
t95	Disable Delay (high to 3-state)	_	22	ns
t96	OBE Delay (high to high)	_	22	ns

<sup>‡</sup> For multiprocessor mode, see note in Section 10.10.




5-4797 (F)

Figure 32. SIO Active Mode Output Timing Diagram

**Table 102. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t86a	OLD Delay (high to low)	_	22	ns
t102	OLD Hold (high to invalid)	4	_	ns
t87	Data Delay (high to valid)	_	22	ns
t88	Enable Data Delay (low to active)	_	22	ns
t89	Disable Data Delay (high to 3-state)	_	22	ns
t90	Data Hold (high to invalid)	4	_	ns
t92	Address Delay (high to valid)	_	22	ns
t93	Address Hold (high to invalid)	4	_	ns
t94	Enable Delay (low to active)	_	22	ns
t95	Disable Delay (high to 3-state)		22	ns
t96	OBE Delay (high to high)	_	22	ns

<sup>\*</sup> OLD goes high at the end of bit 6 of 0:15.




<sup>\*</sup> See sioc register, LD field.

Figure 33. Serial I/O Active Mode Clock Timing

**Table 103. Timing Characteristics for Signal Generation** 

Abbreviated Reference	Parameter	Min	Max	Unit
t97	ICK Delay (high to high)	_	15	ns
t98	ICK Delay (high to low)	_	15	ns
t99	OCK Delay (high to high)	_	15	ns
t100	OCK Delay (high to low)	_	15	ns
t76a	ILD Delay (high to low)	_	22	ns
t76b	ILD Delay (high to high)	_	22	ns
t101	ILD Hold (high to invalid)	4	_	ns
t86a	OLD Delay (high to low)	_	22	ns
t86b	OLD Delay (high to high)	_	22	ns
t102	OLD Hold (high to invalid)	4	_	ns
t103	SYNC Delay (high to low)	_	22	ns
t104	SYNC Delay (high to high)	_	22	ns
t105	SYNC Hold (high to invalid)	4	_	ns

#### 10.10 Multiprocessor Communication



5-4799 (F)

Figure 34. SIO Multiprocessor Timing Diagram

**Note:** All serial I/O timing requirements and characteristics still apply, but the minimum clock period in passive multiprocessor mode, assuming 50% duty cycle, is calculated as (t77 + t116) x 2.

Table 104. Timing Requirements for SIO Multiprocessor Communication

Abbreviated Reference	Parameter	Min	Max	Unit
t112	Sync Setup (high/low to high)	22	_	ns
t113	Sync Hold (high to high/low)	0		ns
t114	Address Setup (valid to high)	9	_	ns
t115	Address Hold (high to invalid)	0	_	ns

**Table 105. Timing Characteristics for SIO Multiprocessor Communication** 

Abbreviated Reference*	Parameter	Min	Max	Unit
t116	Data Delay (bit 0 only) (low to valid)	_	22	ns
t117	Data Disable Delay (high to 3-state)	_	20	ns
t120	DOEN Valid Delay (high to valid)	_	16	ns
t121	Address Delay (bit 0 only) (low to valid)	_	22	ns
t122	Address Disable Delay (high to 3-state)	_	20	ns

 $<sup>^{\</sup>star}$  With capacitance load on ICK, OCK, DO, SYNC, and SADD = 100 pF, add 4 ns to t116—t122.

<sup>\*</sup> Negative edge initiates time slot 0.

#### 11 Timing Characteristics for 3.0 V Operation

The following timing characteristics and requirements are preliminary information and are subject to change. Timing characteristics refer to the behavior of the device under specified conditions. Timing requirements refer to conditions imposed on the user for proper operation of the device. All timing data is valid for the following conditions:

TA = -40 °C to +85 °C (See Section 8.3.)

VDD = 3.0 V to 3.6 V, VSS = 0 V (See Section 8.3.)

Capacitance load on outputs (CL) = 50 pF, except for CKO, where CL = 20 pF.

Output characteristics can be derated as a function of load capacitance (CL).

All outputs: 0.03 ns/pF  $\leq$  dt/dCL  $\leq$  0.07 ns/pF for 10  $\leq$  CL  $\leq$  100 pF at VIH for rising edge and at VIL for falling edge.

For example, if the actual load capacitance is 30 pF instead of 50 pF, the derating for a rising edge is (30 - 50) pF x 0.06 ns/pF = 1.2 ns **less** than the specified rise time or delay that includes a rise time.

Test conditions for inputs:

- Rise and fall times of 4 ns or less
- Timing reference levels for delays = VIH, VIL


Test conditions for outputs (unless noted otherwise):

- CLOAD = 50 pF; except for CKO, where CLOAD = 20 pF
- Timing reference levels for delays = VIH, VIL
- 3-state delays measured to the high-impedance state of the output driver

For the timing diagrams, see Table 62 for input clock requirements.

Unless otherwise noted, CKO in the timing diagrams is the free-running CKO.

#### 11.1 DSP Clock Generation



5-4009 (F).a

Figure 35. I/O Clock Timing Diagram

**Table 106. Timing Requirements for Input Clock** 

Abbreviated Reference	Parameter	10 ns*		
		Min Max		Unit
t1	Clock In Period (high to high)	20	†	ns
t2	Clock In Low Time (low to high)	10	_	ns
t3	Clock In High Time (high to low)	10	_	ns

<sup>\*</sup> Device speeds greater than 50 MIPS do not support 1X operation. Use the PLL.

Table 107. Timing Characteristics for Input Clock and Output Clock

Abbreviated Reference	Parameter	10 ns		Unit
		Min	Max	
t4	Clock Out High Delay		10	ns
t5	Clock Out Low Delay (high to low)	_	10	ns
t6	Clock Out Period (low to low)	T*	_	ns
t6a	Clock Out Period with SLOWCKI Bit Set in powerc Register (low to low)	0.74	3.8	μs

<sup>\*</sup> T = internal clock period, set by CKI or by CKI and the PLL parameters.

<sup>\*</sup> See Table 62 for input clock electrical requirements.

<sup>†</sup> Free-running clock.

<sup>‡</sup> Wait-stated clock (see Table 38).


<sup>§</sup> W = number of wait-states.

<sup>†</sup> Device is fully static, t1 is tested at 100 ns for 1X input clock option, and memory hold time is tested at 0.1 s.

#### 11.2 Reset Circuit

The DSP1627 has a powerup reset circuit that automatically clears the JTAG controller upon powerup. If the supply voltage falls below VDD MIN\* and a reset is required, the JTAG controller must be reset—even if the JTAG port isn't being used—by applying six low-to-high clock edges on TCK with TMS held high, followed by the usual RSTB and CKI reset sequence. Figure 60 shows two separate events: an initial powerup and a powerup following a drop in the power supply voltage.

\* See Table 60, Recommended Operating Condiitons.



5-2253 (F).a

#### Notes:

See Table 62 for CKI electrical requirements and Table 151 for TCK timing requirements.

When both INT0 and RSTB are asserted, all output and bidirectional pins (except TDO, which 3-states by JTAG control) are put in a 3-state condition. With RSTB asserted and INT0 not asserted, EROM, ERAMHI, ERAMLO, IO, DSEL, and RWN outputs remain high, and CKO remains a free-running clock.

TMS and TDI signals have internal pull-up devices.

Figure 36. Powerup Reset and Chip Reset Timing Diagram

Table 108. Timing Requirements for Powerup Reset and Chip Reset

Abbreviated Reference	Paramete	r	Min	Max	Unit
t8	Reset Pulse (low to high	h)	6T		ns
t9	VDD Ramp		_	10	ms
t146	VDD MIN to RSTB Low	CMOS	2T		ns
		Crystal*	20	_	ms
		Small-Signal	20		μs
t151	TMS High		6 * Ττcκ <sup>†</sup>		ns
t152	JTAG Reset to	CMOS	2T	_	ns
	RSTB Low	Crystal*	20 ms – 6 * Ттск if 6 * Ттск < 20 ms	_	
			0 if 6 * Tτcκ ≥ 20 ms	_	
		Small-Signal	20 μs – 6 * Ττcκ if 6 * Ττcκ < 20 μs	_	
			0 if 6 * Tτcκ ≥ 20 μs	1	
t153	RSTB (low to high)		_	54	ns

<sup>\*</sup> With external components as specified in Table 62.


<sup>†</sup> TTCK = t12 = TCK period. See Table 151 for TCK timing requirements.

Table 109. Timing Characteristics for Powerup Reset and Chip Reset

Abbreviated Reference	Parameter	Min	Max	Unit
t10	RSTB Disable Time (low to 3-state)	_	100	ns
t11	RSTB Enable Time (high to valid)	_	100	ns

**Note:** The device needs to be clocked for at least six CKI cycles during reset after powerup. Otherwise, high currents may flow.

## 11.3 Reset Synchronization



<sup>\*</sup> See Table 62 for input clock electrical requirements.


Note: CKO1 and CKO2 are two possible CKO states before reset. CKO is free-running.

Figure 37. Reset Synchronization Timing

Table 110. Timing Requirements for Reset Synchronization Timing

Abbreviated Reference	Parameter	Min	Max	Unit
t126	Reset Setup (high to high)	3	T/2 - 5	ns

## 11.4 JTAG I/O Specifications



5-4017 (F)

Figure 38. JTAG Timing Diagram


Table 111. Timing Requirements for JTAG Input/Output

Abbreviated Reference	Parameter	Min	Max	Unit
t12	TCK Period (high to high)	50	_	ns
t13	TCK High Time (high to low)	22.5	_	ns
t14	TCK Low Time (low to high)	22.5	_	ns
t15	TMS Setup Time (valid to high)	7.5	_	ns
t16	TMS Hold Time (high to invalid)	2	_	ns
t17	TDI Setup Time (valid to high)	7.5	_	ns
t18	TDI Hold Time (high to invalid)	2	_	ns

Table 112. Timing Characteristics for JTAG Input/Output

Abbreviated Reference	Parameter	Min	Max	Unit
t19	TDO Delay (low to valid)	_	19	ns
t20	TDO Hold (low to invalid)	0	_	ns

#### 11.5 Interrupt



<sup>\*</sup> CKO is free-running.

Figure 39. Interrupt Timing Diagram

**Table 113. Timing Requirements for Interrupt** 

Abbreviated Reference	Parameter	Min	Max	Unit
t21	Interrupt Setup (high to low)	19	_	ns
t22	INT Assertion Time (high to low)	2T	_	ns

Note: Interrupt is asserted during an interruptible instruction and no other pending interrupts.

**Table 114. Timing Characteristics for Interrupt** 

Abbreviated Reference	Parameter	Min	Max	Unit
t23	IACK Assertion Time (low to high)	_	T/2 + 10	ns
t24	VEC Assertion Time (low to high)	_	12.5	ns
t25	IACK Invalid Time (low to low)	_	10	ns
t26	VEC Invalid Time (low to low)	_	12.5	ns

Note: Interrupt is asserted during an interruptible instruction and no other pending interrupts.

<sup>†</sup> IACK assertion is guaranteed to be enclosed by VEC[3:0] assertion.

## 11.6 Bit Input/Output (BIO)




Figure 40. Write Outputs Followed by Read Inputs (cbit = Immediate; a1 = sbit)

Table 115. Timing Requirements for BIO Input Read

Abbreviated Reference	Parameter	Min	Max	Unit
t27	IOBIT Input Setup Time (valid to high)	15	_	ns
t28	IOBIT Input Hold Time (high to invalid)	0	_	ns

Table 116. Timing Characteristics for BIO Output

Abbreviated Reference	Parameter	Min	Max	Unit
t29	IOBIT Output Valid Time (low to valid)	_	9	ns
t144	IOBIT Output Hold Time (low to invalid)	1		ns





Figure 41. Write Outputs and Test Inputs (cbit = Immediate)

**Table 117. Timing Requirements for BIO Input Test** 

Abbreviated Reference	Parameter	Min	Max	Unit
t141	IOBIT Input Setup Time (valid to low)	15	_	ns
t142	IOBIT Input Hold Time (low to invalid)	0	1	ns

#### 11.7 External Memory Interface

The following timing diagrams, characteristics, and requirements do not apply to interactions with delayed external memory enables unless so stated. See the *DSP1611/17/18/27 Digital Signal Processor Information Manual* for a detailed description of the external memory interface including other functional diagrams.



<sup>\*</sup> W = number of wait-states.


Figure 42. Enable Transition Timing

Table 118. Timing Characteristics for External Memory Enables (EROM, ERAMHI, IO, ERAMLO)

Abbreviated Reference	Parameter	Min	Max	Unit
t33	CKO to ENABLE Active (low to low)	0	5	ns
t34	CKO to ENABLE Inactive (low to high)	-1	4.5	ns

Table 119. Timing Characteristics for Delayed External Memory Enables (ioc = 0x000F)

Abbreviated Reference	Parameter	Min	Max	Unit
t33	CKO to Delayed ENABLE Active (low to low)	T/2 – 2	T/2 + 7	ns



5-4021 (F).a

Figure 43. External Memory Data Read Timing Diagram

**Table 120. Timing Characteristics for External Memory Access** 

Abbreviated Reference	Parameter	Min	Max	Unit
t127	Enable Width (low to high)	T(1 + W) - 1.5	_	ns
t128	Address Valid (enable low to valid)	_	2	ns

Table 121. Timing Requirements for External Memory Read (EROM, ERAMHI, IO, ERAMLO)

Abbreviated Reference	Parameter		10 ns	Unit
		Min	Max	
t129	Read Data Setup (valid to enable high)	13	_	ns
t130	Read Data Hold (enable high to hold)	0	_	ns
t150	External Memory Access Time (valid to valid)	_	T(1 + W) - 13	ns

<sup>\*</sup> W = number of wait-states.





Figure 44. External Memory Data Write Timing Diagram

Table 122. Timing Characteristics for External Memory Data Write (All Enables)

Abbreviated	Parameter	10	ns	Unit
Reference		Min	Max	
t131	Write Overlap (enable low to 3-state)	_	0	ns
t132	RWN Advance (RWN high to enable high)	0	_	ns
t133	RWN Delay (enable low to RWN low)	0	_	ns
t134	Write Data Setup (data valid to RWN high)	T(1 + W)/2 - 3		ns
t135	RWN Width (low to high)	T(1 + W) – 4	_	ns
t136	Write Address Setup (address valid to RWN low)	0	_	ns

\* W = number of wait-states.



W = number of wait-states.

Figure 45. Write Cycle Followed by Read Cycle

Table 123. Timing Characteristics for Write Cycle Followed by Read Cycle

Abbreviated Reference	Parameter	Min	Max	Unit
t131	Write Overlap (enable low to 3-state)	_	0	ns
t137	Write Data 3-state (RWN high to 3-state)	_	2	ns
t138	Write Data Hold (RWN high to data hold)	0	_	ns
t139	Write Address Hold (RWN high to address hold)	0	1	ns

#### 11.8 PHIF Specifications

For the PHIF, "READ" means read by the external user (output by the DSP); "WRITE" is similarly defined. The 8-bit reads/writes are identical to one-half of a 16-bit access.




Figure 46. PHIF Intel Mode Signaling (Read and Write) Timing Diagram

Table 124. Timing Requirements for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t41	PODS to PCSN Setup (low to low)	0	_	ns
t42	PCSN to PODS Hold (high to high)	0	_	ns
t43	PIDS to PCSN Setup (low to low)	0		ns
t44	PCSN to PIDS Hold (high to high)	0		ns
t45*	PSTAT to PCSN Setup (valid to low)	6	_	ns
t46*	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47*	PBSEL to PCSN Setup (valid to low)	6	_	ns
t48*	PCSN to PBSEL Hold (high to invalid)	0	_	ns
t51*	PB Write to PCSN Setup (valid to high)	10		ns
t52*	PCSN to PB Write Hold (high to invalid)	5	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PIDS and PODS signals. An output transaction (read) is initiated by PCSN or PODS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PODS going low, if PODS goes low after PCSN. An output transaction is completed by PCSN or PODS going high, whichever comes first. An input transaction is initiated by PCSN or PIDS going low, whichever comes last. An input transaction is completed by PCSN or PIDS going high, whichever comes first. All requirements referenced to PCSN apply to PIDS or PODS, if PIDS or PODS is the controlling signal.

Table 125. Timing Characteristics for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t49*	PCSN to PB Read (low to valid)	_	17	ns
t50*	PCSN to PB Read Hold (high to invalid)	3	_	ns

This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PIDS and PODS signals. An output transaction (read) is initiated by PCSN or PODS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PODS going low, if PODS goes low after PCSN. An output transaction is completed by PCSN or PODS going high, whichever comes first. An input transaction is initiated by PCSN or PIDS going low, whichever comes last. An input transaction is completed by PCSN or PIDS going high, whichever comes first. All requirements referenced to PCSN apply to PIDS or PODS, if PIDS or PODS is the controlling signal.




Figure 47. PHIF Intel Mode Signaling (Pulse Period and Flags) Timing Diagram

Table 126. Timing Requirements for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t55	PCSN/PODS/PIDS Pulse Width (high to low)	20.5	_	ns
t56	PCSN/PODS/PIDS Pulse Width (low to high)	20.5	_	ns

Table 127. Timing Characteristics for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t53*	PCSN/PODS to POBE <sup>†</sup> (high to high)	_	20	ns
t54*	PCSN/PIDS to PIBF† (high to high)	1	20	ns

<sup>\*</sup> t53 should be referenced to the rising edge of PCSN or PODS, whichever comes first. t54 should be referenced to the rising edge of PCSN or PIDS, whichever comes first.

<sup>†</sup> POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram (positive assertion levels shown). t53 and t54 apply to the inverted levels as well as those shown.

## 16-bit READ 16-bit WRITE **PCSN PDS** t41 t43 PRWN t43 t44 PBSEL - t47 t48 - t45 t46t49 t50 t154 t51 t52 PB[7:0]

### 11 Timing Characteristics for 3.0 V Operation (continued)

Figure 48. PHIF *Motorola* Mode Signaling (Read and Write) Timing Diagram

Table 128.	. Timina Reauir	ements for PHIF	- <i>Motorola</i> Mod	le Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t41	PDS <sup>†</sup> to PCSN Setup (valid to low)	0	_	ns
t42	PCSN to PDS <sup>†</sup> Hold (high to invalid)	0	_	ns
t43	PRWN to PCSN Setup (valid to low)	6	_	ns
t44	PCSN to PRWN Hold (high to invalid)	0	_	ns
t45*	PSTAT to PCSN Setup (valid to low)	6	_	ns
t46*	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47*	PBSEL to PCSN Setup (valid to low)	6	_	ns
t48*	PCSN to PBSEL Hold (high to invalid)	0	_	ns
t51*	PB Write to PCSN Setup (valid to high)	10	_	ns
t52*	PCSN to PB Write Hold (high to invalid)	5	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PDS signal. An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

Table 129. Timing Characteristics for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t49*	PCSN to PB Read (low to valid)	_	17	ns
t50*	PCSN to PB Read (high to invalid)	3	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PDS signal. An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

5-4038 (F).a

<sup>†</sup> PDS is programmable to be active-high or active-low. It is shown active-low in Figures 72 and 73. POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram. t53 and t54 apply to the inverted levels as well as those shown.




Figure 49. PHIF Motorola Mode Signaling (Pulse Period and Flags) Timing Diagram

Table 130. Timing Characteristics for PHIF Motorola Mode Signaling


Abbreviated Reference	Parameter	Min	Max	Unit
t53*	PCSN/PDS <sup>†</sup> to POBE <sup>†</sup> (high to high)	_	20	ns
t54*	PCSN/PDS <sup>†</sup> to PIBF <sup>†</sup> (high to high)	_	20	ns

<sup>\*</sup> An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, t53 and t54 should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

Table 131. Timing Requirements for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t55	PCSN/PDS/PRWN Pulse Width (high to low)	20	_	ns
t56	PCSN/PDS/PRWN Pulse Width (low to high)	20	_	ns

<sup>†</sup> PDS is programmable to be active-high or active-low. It is shown active-low in Figures 48 and 49. POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram. t53 and t54 apply to the inverted levels as well as those shown.



<sup>\*</sup> Motorola mode signal name.

Figure 50. PHIF Intel or Motorola Mode Signaling (Status Register Read) Timing Diagram

Table 132. Timing Requirements for Intel and Motorola Mode Signaling (Status Register Read)

Abbreviated Reference	Parameter	Min	Max	Unit
t45 <sup>†</sup>	PSTAT to PCSN Setup (valid to low)	6	_	ns
t46 <sup>‡</sup>	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47 <sup>†</sup>	PBSEL to PCSN Setup (valid to low)	6	_	ns
t48 <sup>‡</sup>	PCSN to PBSEL Hold (high to invalid)	0	_	ns

<sup>†</sup> t45, t47, and t49 are referenced to the falling edge of PCSN or PODS(PDS), whichever occurs last.

Table 133. Timing Characteristics for Intel and Motorola Mode Signaling (Status Register Read)

Abbreviated Reference	Parameter	Min	Max	Unit
t49 <sup>†</sup>	PCSN to PB Read (low to valid)		17	ns
t50 <sup>‡</sup>	PCSN to PB Read Hold (high to invalid)	3	_	ns

<sup>†</sup> t45, t47, and t49 are referenced to the falling edge of PCSN or PODS(PDS), whichever occurs last.

<sup>‡</sup> t46, t48, and t50 are referenced to the rising edge of PCSN or PODS(PDS), whichever occurs first.

<sup>‡</sup> t46, t48, and t50 are referenced to the rising edge of PCSN or PODS(PDS), whichever occurs first.





Figure 51. PHIF, PIBF, and POBE Reset Timing Diagram

Table 134. PHIF Timing Characteristics for PHIF, PIBF, and POBE Reset

Abbreviated Reference	Parameter	Min	Max	Unit
t57	RSTB Disable to POBE/PIBF* (high to valid)	_	25	ns
t58	RSTB Enable to POBE/PIBF* (low to invalid)	3	25	ns

After reset, POBE and PIBF always go to the levels shown, indicating output buffer empty and input buffer empty. The DSP program, however, may later invert the definition of the logic levels for POBE and PIBF. t57 and t58 continue to apply.



5-4776 (F)

Figure 52. PHIF, PIBF, and POBE Disable Timing Diagram


Table 135. PHIF Timing Characteristics for POBE and PIBF Disable

Abbreviated Reference	Parameter	Min	Max	Unit
t59	CKO to POBE/PIBF* Disable (high/low to disable)	_	20	ns

<sup>\*</sup> POBE and PIBF can be programmed to be active-high or active-low. They are shown active-high. The timing characteristic for active-low is the same as for active-high.

<sup>†</sup> POBE and PIBF can be programed to be active-high or active-low. They are shown active-high. The timing characteristic for active-low is the same as for active-high.

# 11.9 Serial I/O Specifications



\* N = 16 or 8 bits.

Figure 53. SIO Passive Mode Input Timing Diagram

**Table 136. Timing Requirements for Serial Inputs** 


Abbreviated Reference	Parameter	Min	Max	Unit
t70	Clock Period (high to high) <sup>‡</sup>	40	t	ns
t71	Clock Low Time (low to high)	18	_	ns
t72	Clock High Time (high to low)	18	_	ns
t73	Load High Setup (high to high)	8	_	ns
t74	Load Low Setup (low to high)	8	_	ns
t75	Load High Hold (high to invalid)	0	_	ns
t77	Data Setup (valid to high)	7	_	ns
t78	Data Hold (high to invalid)	0	_	ns

<sup>†</sup> Device is fully static; t70 is tested at 200 ns.

**Table 137. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t79	IBF Delay (high to high)	1	35	ns

<sup>‡</sup> For multiprocessor mode, see note in Section 12.10.



LD goes high during bit 6 (of 0:15), N = 8 or 16.


Figure 54. SIO Active Mode Input Timing Diagram

**Table 138. Timing Requirements for Serial Inputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t77	Data Setup (valid to high)	7		ns
t78	Data Hold (high to invalid)	0	_	ns

**Table 139. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t76a	ILD Delay (high to low)	_	35	ns
t101	ILD Hold (high to invalid)	5	_	ns
t79	IBF Delay (high to high)	_	35	ns



See sioc register, MSB field, to determine if B0 is the MSB or LSB. See sioc register, ILEN field, to determine if the DO word length is 8 bits or 16 bits.

Figure 55. SIO Passive Mode Output Timing Diagram

**Table 140. Timing Requirements for Serial Inputs** 


Abbreviated Reference	Parameter	Min	Max	Unit
t80	Clock Period (high to high) <sup>‡</sup>	40	t	ns
t81	Clock Low Time (low to high)	18	_	ns
t82	Clock High Time (high to low)	18	_	ns
t83	Load High Setup (high to high)	8	_	ns
t84	Load Low Setup (low to high)	8	_	ns
t85	Load Hold (high to invalid)	0	_	ns

<sup>†</sup> Device is fully static; t80 is tested at 200 ns.

**Table 141. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t87	Data Delay (high to valid)	_	35	ns
t88	Enable Data Delay (low to active)	_	35	ns
t89	Disable Data Delay (high to 3-state)	_	35	ns
t90	Data Hold (high to invalid)	5	_	ns
t92	Address Delay (high to valid)	_	35	ns
t93	Address Hold (high to invalid)	5	_	ns
t94	Enable Delay (low to active)	_	35	ns
t95	Disable Delay (high to 3-state)	_	35	ns
t96	OBE Delay (high to high)		35	ns

<sup>‡</sup> For multiprocessor mode, see note in Section 12.10.




OLD goes high at the end of bit 6 of 0:15.

Figure 56. SIO Active Mode Output Timing Diagram

**Table 142. Timing Characteristics for Serial Output** 

Abbreviated Reference	Parameter	Min	Max	Unit
t86a	OLD Delay (high to low)		35	ns
t102	OLD Hold (high to invalid)	5	_	ns
t87	Data Delay (high to valid)		35	ns
t88	Enable Data Delay (low to active)	_	35	ns
t89	Disable Data Delay (high to 3-state)		35	ns
t90	Data Hold (high to invalid)	5	_	ns
t92	Address Delay (high to valid)	_	35	ns
t93	Address Hold (high to invalid)	5	_	ns
t94	Enable Delay (low to active)	_	35	ns
t95	Disable Delay (high to 3-state)		35	ns
t96	OBE Delay (high to high)	_	35	ns




<sup>\*</sup> See sioc register, LD field.

Figure 57. Serial I/O Active Mode Clock Timing

**Table 143. Timing Characteristics for Signal Generation** 

Abbreviated Reference	Parameter	Min	Max	Unit
t97	ICK Delay (high to high)	_	18	ns
t98	ICK Delay (high to low)	_	18	ns
t99	OCK Delay (high to high)	_	18	ns
t100	OCK Delay (high to low)	_	18	ns
t76a	ILD Delay (high to low)	_	35	ns
t76b	ILD Delay (high to high)	_	35	ns
t101	ILD Hold (high to invalid)	5	_	ns
t86a	OLD Delay (high to low)	_	35	ns
t86b	OLD Delay (high to high)	_	35	ns
t102	OLD Hold (high to invalid)	5	_	ns
t103	SYNC Delay (high to low)	_	35	ns
t104	SYNC Delay (high to high)	_	35	ns
t105	SYNC Hold (high to invalid)	5	_	ns

#### 11.10 Multiprocessor Communication



\* Negative edge initiates time slot 0.

Figure 58. SIO Multiprocessor Timing Diagram

**Note:** All serial I/O timing requirements and characteristics still apply, but the minimum clock period in passive multiprocessor mode, assuming 50% duty cycle, is calculated as (t77 + t116) x 2.

Table 144. Timing Requirements for SIO Multiprocessor Communication

Abbreviated Reference	Parameter	Min	Max	Unit
t112	Sync Setup (high/low to high)	35	_	ns
t113	Sync Hold (high to high/low)	0	_	ns
t114	Address Setup (valid to high)	12	_	ns
t115	Address Hold (high to invalid)	0	_	ns

**Table 145. Timing Characteristics for SIO Multiprocessor Communication** 

Abbreviated Reference*	Parameter	Min	Max	Unit
t116	Data Delay (bit 0 only) (low to valid)	_	35	ns
t117	Data Disable Delay (high to 3-state)	_	30	ns
t120	DOEN Valid Delay (high to valid)	_	25	ns
t121	Address Delay (bit 0 only) (low to valid)	_	35	ns
t122	Address Disable Delay (high to 3-state)	_	30	ns

<sup>\*</sup> With capacitance load on ICK, OCK, DO, SYNC, and SADD = 100 pF, add 4 ns to t116—t122.

## 12 Timing Characteristics for 2.7 V Operation

The following timing characteristics and requirements are preliminary information and are subject to change. Timing characteristics refer to the behavior of the device under specified conditions. Timing requirements refer to conditions imposed on the user for proper operation of the device. All timing data is valid for the following conditions:

TA = -40 °C to +85 °C (See Section 8.3.)

 $VDD = 3 V \pm 10\%$ , VSS = 0 V (See Section 8.3.)

Capacitance load on outputs (CL) = 50 pF, except for CKO, where CL = 20 pF.

Output characteristics can be derated as a function of load capacitance (CL).

All outputs:  $0.03 \text{ ns/pF} \le dt/dCL \le 0.07 \text{ ns/pF}$  for  $10 \le CL \le 100 \text{ pF}$  at VIH for rising edge and at VIL for falling edge.

For example, if the actual load capacitance is 30 pF instead of 50 pF, the derating for a rising edge is (30 - 50) pF x 0.06 ns/pF = 1.2 ns **less** than the specified rise time or delay that includes a rise time.

Test conditions for inputs:

- Rise and fall times of 4 ns or less
- Timing reference levels for delays = VIH, VIL


Test conditions for outputs (unless noted otherwise):

- CLOAD = 50 pF; except for CKO, where CLOAD = 20 pF
- Timing reference levels for delays = VIH, VIL
- 3-state delays measured to the high-impedance state of the output driver

For the timing diagrams, see Table 62 for input clock requirements.

Unless otherwise noted, CKO in the timing diagrams is the free-running CKO.

#### 12.1 DSP Clock Generation



5-4009 (F).a

- \* See Table 62 for input clock electrical requirements.
- † Free-running clock.
- ‡ Wait-stated clock (see Table 38).
- § W = number of wait-states.

Figure 59. I/O Clock Timing Diagram

**Table 146. Timing Requirements for Input Clock** 

Abbreviated Reference	Parameter	20 ns	20 ns and 12.5 ns <sup>*</sup>	
		Min	Max	Unit
t1	Clock In Period (high to high)	20	t	ns
t2	Clock In Low Time (low to high)	10	_	ns
t3	Clock In High Time (high to low)	10	_	ns

<sup>\*</sup> Device speeds greater than 50 MIPS do not support 1 X operation. Use the PLL.

Table 147. Timing Characteristics for Input Clock and Output Clock

Abbreviated Reference	Parameter	20 ns		20 ns 12.5 ns		ns	Unit
		Min	Max	Min	Max		
t4	Clock Out High Delay	_	14	_	10	ns	
t5	Clock Out Low Delay (high to low)	_	14	_	10	ns	
t6	Clock Out Period (low to low)	T*	_	T*	_	ns	
t6a	Clock Out Period with SLOWCKI Bit Set in powerc Register (low to low)	0.74	3.8	0.74	3.8	μs	


<sup>\*</sup> T = internal clock period, set by CKI or by CKI and the PLL parameters.

<sup>†</sup> Device is fully static, t1 is tested at 100 ns for 1X input clock option, and memory hold time is tested at 0.1 s.

#### 12.2 Reset Circuit

The DSP1627 has a powerup reset circuit that automatically clears the JTAG controller upon powerup. If the supply voltage falls below VDD MIN\* and a reset is required, the JTAG controller must be reset—even if the JTAG port isn't being used—by applying six low-to-high clock edges on TCK with TMS held high, followed by the usual RSTB and CKI reset sequence. Figure 60 shows two separate events: an initial powerup and a powerup following a drop in the power supply voltage.

\* See Table 60, Recommended Operating Condiitons.



5-2253 (F).a

Notes:

See Table 62 for CKI electrical requirements and Table 151 for TCK timing requirements.

When both INTO and RSTB are asserted, all output and bidirectional pins (except TDO, which 3-states by JTAG control) are put in a 3-state condition. With RSTB asserted and INTO not asserted, EROM, ERAMHI, ERAMLO, IO, DSEL, and RWN outputs remain high, and CKO remains a free-running clock.

TMS and TDI signals have internal pull-up devices.

Figure 60. Powerup Reset and Chip Reset Timing Diagram

Table 148. Timing Requirements for Powerup Reset and Chip Reset

<b>Abbreviated Reference</b>	Paramete	r	Min	Max	Unit
t8	Reset Pulse (low to high	h)	6T		ns
t9	Vdd Ramp		_	10	ms
t146	VDD MIN to RSTB Low	CMOS	2T	_	ns
		Crystal*	20	_	ms
		Small-signal	20	_	μs
t151	TMS High		6 * Ттск <sup>†</sup>	_	ns
t152	JTAG Reset to	CMOS	2T	_	ns
	RSTB Low	Crystal*	20 ms – 6 * Ттск if 6 * Ттск < 20 ms	_	
			0 if 6 * Tτcκ ≥ 20 ms	_	
		Small-Signal	20 μs – 6 * Ττcκ if 6 * Ττcκ < 20 μs	_	
			0 if 6 * Ттск ≥ 20 µs	_	
t153	RSTB (low to high)		_	54	ns

<sup>\*</sup> With external components as specified in Table 62.


<sup>†</sup> TTCK = t12 = TCK period. See Table 151 for TCK timing requirements.

Table 149. Timing Characteristics for Powerup Reset and Chip Reset

Abbreviated Reference	Parameter	Min	Max	Unit
t10	RSTB Disable Time (low to 3-state)	_	100	ns
t11	RSTB Enable Time (high to valid)	_	100	ns

**Note:** The device needs to be clocked for at least six CKI cycles during reset after powerup. Otherwise, high currents may flow.

#### 12.3 Reset Synchronization



<sup>\*</sup> See Table 62 for input clock electrical requirements.

Note: CKO1 and CKO2 are two possible CKO states before reset. CKO is free-running.

Figure 61. Reset Synchronization Timing

Table 150. Timing Requirements for Reset Synchronization Timing

Abbreviated Reference	Parameter	Min	Max	Unit
t126	Reset Setup (high to high)	3	T/2 - 5	ns

# 12.4 JTAG I/O Specifications




Figure 62. JTAG Timing Diagram


Table 151. Timing Requirements for JTAG Input/Output

Abbreviated Reference	Parameter	Min	Max	Unit
t12	TCK Period (high to high)	50	_	ns
t13	TCK High Time (high to low)	22.5	_	ns
t14	TCK Low Time (low to high)	22.5	_	ns
t15	TMS Setup Time (valid to high)	7.5	_	ns
t16	TMS Hold Time (high to invalid)	2	_	ns
t17	TDI Setup Time (valid to high)	7.5	_	ns
t18	TDI Hold Time (high to invalid)	2	_	ns

Table 152. Timing Characteristics for JTAG Input/Output

Abbreviated Reference	Parameter	Min	Max	Unit
t19	TDO Delay (low to valid)	_	19	ns
t20	TDO Hold (low to invalid)	0	_	ns

#### 12.5 Interrupt



CKO is free-running.

Figure 63. Interrupt Timing Diagram

**Table 153. Timing Requirements for Interrupt** 

Abbreviated Reference	Parameter	Min	Max	Unit
t21	Interrupt Setup (high to low)	19		ns
t22	INT Assertion Time (high to low)	2T		ns

Note: Interrupt is asserted during an interruptible instruction and no other pending interrupts.

**Table 154. Timing Characteristics for Interrupt** 

Abbreviated Reference	Parameter	Min	Max	Unit
t23	IACK Assertion Time (low to high)	_	T/2 + 10	ns
t24	VEC Assertion Time (low to high)	_	12.5	ns
t25	IACK Invalid Time (low to low)	_	10	ns
t26	VEC Invalid Time (low to low)	_	12.5	ns

Note: Interrupt is asserted during an interruptible instruction and no other pending interrupts.

<sup>†</sup> IACK assertion is guaranteed to be enclosed by VEC[3:0] assertion.

#### 12.6 Bit Input/Output (BIO)




Figure 64. Write Outputs Followed by Read Inputs (cbit = Immediate; a1 = sbit)

Table 155. Timing Requirements for BIO Input Read

Abbreviated Reference	Parameter	Min	Max	Unit
t27	IOBIT Input Setup Time (valid to high)	15		ns
t28	IOBIT Input Hold Time (high to invalid)	0	_	ns

**Table 156. Timing Characteristics for BIO Output** 

Abbreviated Reference	Parameter	Min	Max	Unit
t29	IOBIT Output Valid Time (low to valid)	_	9	ns
t144	IOBIT Output Hold Time (low to invalid)	1	_	ns




Figure 65. Write Outputs and Test Inputs (cbit = Immediate)


Table 157. Timing Requirements for BIO Input Test

Abbreviated Reference	Parameter	Min	Max	Unit
t141	IOBIT Input Setup Time (valid to low)	15		ns
t142	IOBIT Input Hold Time (low to invalid)	0		ns

5-4019 (F).a

#### 12.7 External Memory Interface

The following timing diagrams, characteristics, and requirements do not apply to interactions with delayed external memory enables unless so stated. See the *DSP1611/17/18/27 Digital Signal Processor Information Manual* for a detailed description of the external memory interface including other functional diagrams.



<sup>\*</sup> W = number of wait-states.


Figure 66. Enable Transition Timing

Table 158. Timing Characteristics for External Memory Enables (EROM, ERAMHI, IO, ERAMLO)

Abbreviated Reference	Parameter	Min	Max	Unit
t33	CKO to ENABLE Active (low to low)	0	5	ns
t34	CKO to ENABLE Inactive (low to high)	-1	4.5	ns

Table 159. Timing Characteristics for Delayed External Memory Enables (ioc = 0x000F)

Abbreviated Reference	Parameter	Min	Max	Unit
t33	CKO to Delayed ENABLE Active (low to low)	T/2 – 2	T/2 + 7	ns



5-4021 (F).a

Figure 67. External Memory Data Read Timing Diagram


**Table 160. Timing Characteristics for External Memory Access** 

Abbreviated Reference	Parameter	Min	Max	Unit
t127	Enable Width (low to high)	T(1 + W) - 1.5	_	ns
t128	Address Valid (enable low to valid)	_	2	ns

Table 161. Timing Requirements for External Memory Read (EROM, ERAMHI, IO, ERAMLO)

Abbreviated	Parameter 20 ns		eter 20 ns 12.5 ns		12.5 ns	Unit
Reference		Min	Max	Min	Max	
t129	Read Data Setup (valid to enable high)	15	_	13	_	ns
t130	Read Data Hold (enable high to hold)	0	_	0	_	ns
t150	External Memory Access Time (valid to valid)	_	T(1 + W) - 15	_	T(1 + W) – 14	ns

<sup>\*</sup> W = number of wait-states.




\* W = number of wait-states.

Figure 68. External Memory Data Write Timing Diagram

**Table 162. Timing Characteristics for External Memory Data Write (All Enables)** 

Abbreviated	Parameter	20 ns		12.5 ns		Unit
Reference		Min	Max	Min	Max	
t131	Write Overlap (enable low to 3-state)	_	0	_	0	ns
t132	RWN Advance (RWN high to enable high)	0	_	0	_	ns
t133	RWN Delay (enable low to RWN low)	0	_	0	_	ns
t134	Write Data Setup (data valid to RWN high)	T(1 + W)/2 - 4	_	T(1 + W)/2 - 3	_	ns
t135	RWN Width (low to high)	T(1 + W) – 5	_	T(1 + W) - 4	_	ns
t136	Write Address Setup (address valid to RWN low)	0	_	0	_	ns



<sup>\*</sup> W = number of wait-states.

Figure 69. Write Cycle Followed by Read Cycle

Table 163. Timing Characteristics for Write Cycle Followed by Read Cycle

Abbreviated Reference	Parameter	Min	Max	Unit
t131	Write Overlap (enable low to 3-state)	_	0	ns
t137	Write Data 3-state (RWN high to 3-state)	_	2	ns
t138	Write Data Hold (RWN high to data hold)	0	_	ns
t139	Write Address Hold (RWN high to address hold)	0	_	ns

#### 12.8 PHIF Specifications

For the PHIF, "READ" means read by the external user (output by the DSP); "WRITE" is similarly defined. The 8-bit reads/writes are identical to one-half of a 16-bit access.




Figure 70. PHIF Intel Mode Signaling (Read and Write) Timing Diagram

Table 164. Timing Requirements for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t41	PODS to PCSN Setup (low to low)	0	_	ns
t42	PCSN to PODS Hold (high to high)	0	_	ns
t43	PIDS to PCSN Setup (low to low)	0	_	ns
t44	PCSN to PIDS Hold (high to high)	0	_	ns
t45*	PSTAT to PCSN Setup (valid to low)	6	_	ns
t46*	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47*	PBSEL to PCSN Setup (valid to low)	6	_	ns
t48*	PCSN to PBSEL Hold (high to invalid)	0	_	ns
t51*	PB Write to PCSN Setup (valid to high)	10	_	ns
t52*	PCSN to PB Write Hold (high to invalid)	5	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PIDS and PODS signals. An output transaction (read) is initiated by PCSN or PODS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PODS going low, if PODS goes low after PCSN. An output transaction is completed by PCSN or PODS going high, whichever comes first. An input transaction is initiated by PCSN or PIDS going low, whichever comes last. An input transaction is completed by PCSN or PIDS going high, whichever comes first. All requirements referenced to PCSN apply to PIDS or PODS, if PIDS or PODS is the controlling signal.

Table 165. Timing Characteristics for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t49*	PCSN to PB Read (low to valid)	_	17	ns
t50*	PCSN to PB Read Hold (high to invalid)	3	_	ns

This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PIDS and PODS signals. An output transaction (read) is initiated by PCSN or PODS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PODS going low, if PODS goes low after PCSN. An output transaction is completed by PCSN or PODS going high, whichever comes first. An input transaction is initiated by PCSN or PIDS going low, whichever comes last. An input transaction is completed by PCSN or PIDS going high, whichever comes first. All requirements referenced to PCSN apply to PIDS or PODS, if PIDS or PODS is the controlling signal.




Figure 71. PHIF Intel Mode Signaling (Pulse Period and Flags) Timing Diagram

Table 166. Timing Requirements for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t55	PCSN/PODS/PIDS Pulse Width (high to low)	20.5	_	ns
t56	PCSN/PODS/PIDS Pulse Width (low to high)	20.5	_	ns

Table 167. Timing Characteristics for PHIF Intel Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t53*	PCSN/PODS to POBE† (high to high)	_	20	ns
t54*	PCSN/PIDS to PIBF <sup>†</sup> (high to high)	_	20	ns

<sup>\*</sup> t53 should be referenced to the rising edge of PCSN or PODS, whichever comes first. t54 should be referenced to the rising edge of PCSN or PIDS, whichever comes first.

<sup>†</sup> POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram (positive assertion levels shown). t53 and t54 apply to the inverted levels as well as those shown.

5-4038 (F).a

#### 16-bit READ 16-bit WRITE **PCSN** t42 PDS t41 t43 t44 PRWN t43 t44 **PBSEL** - t47 t48 t45 t46 t49 t50 t51 t52 t154 PB[7:0]

Figure 72. PHIF Motorola Mode Signaling (Read and Write) Timing Diagram

Table 168. Timing Requirements for	PHIF <i>Motorola</i> Mode Signaling
------------------------------------	-------------------------------------

Abbreviated Reference	Parameter	Min	Max	Unit
t41	PDS <sup>†</sup> to PCSN Setup (valid to low)	0	_	ns
t42	PCSN to PDS <sup>†</sup> Hold (high to invalid)	0	_	ns
t43	PRWN to PCSN Setup (valid to low)	6	_	ns
t44	PCSN to PRWN Hold (high to invalid)	0	_	ns
t45*	PSTAT to PCSN Setup (valid to low)	6	_	ns
t46*	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t47*	PBSEL to PCSN Setup (valid to low)	6	_	ns
t48*	PCSN to PBSEL Hold (high to invalid)	0	_	ns
t51*	PB Write to PCSN Setup (valid to high)	10	_	ns
t52*	PCSN to PB Write Hold (high to invalid)	5	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PDS signal. An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

Table 169. Timing Characteristics for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t49*	PCSN to PB Read (low to valid)	_	17	ns
t50*	PCSN to PB Read (high to invalid)	3	_	ns

<sup>\*</sup> This timing diagram for the PHIF port shows accesses using the PCSN signal to initiate and complete a transaction. The transactions can also be initiated and completed with the PDS signal. An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, the timing requirements referenced to PCSN going low, t45 and t49, should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

<sup>†</sup> PDS is programmable to be active-high or active-low. It is shown active-low in Figures 72 and 73. POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram. t53 and t54 apply to the inverted levels as well as those shown.

# 16-bit READ 16-bit WRITE 8-bit READ 8-bit WRITE PCSN VIHVILPDS VIHVILPRWN VIHVILPBSEL VOHVOLPOBE VOHVOLPIBF VOHVOLPIBF VOHVOLPIBF VOHVOLPIBF VOHVOLPIBF VOHPOBE VOHVOLPIBF VOHPIBF VOHPIBF

# 12 Timing Characteristics for 2.7 V Operation (continued)

Figure 73. PHIF Motorola Mode Signaling (Pulse Period and Flags) Timing Diagram

Table 170. Timing Characteristics for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t53*	PCSN/PDS <sup>†</sup> to POBE <sup>†</sup> (high to high)	_	20	ns
t54*	PCSN/PDS <sup>†</sup> to PIBF <sup>†</sup> (high to high)	_	20	ns


<sup>\*</sup> An input/output transaction is initiated by PCSN or PDS going low, whichever comes last. For example, t53 and t54 should be referenced to PDS going low, if PDS goes low after PCSN. An input/output transaction is completed by PCSN or PDS going high, whichever comes first. All requirements referenced to PCSN should be referenced to PDS, if PDS is the controlling signal. PRWN should never be used to initiate or complete a transaction.

Table 171. Timing Requirements for PHIF Motorola Mode Signaling

Abbreviated Reference	Parameter	Min	Max	Unit
t55	PCSN/PDS/PRWN Pulse Width (high to low)	20	_	ns
t56	PCSN/PDS/PRWN Pulse Width (low to high)	20	1	ns

5-4039 (F).a

<sup>†</sup> PDS is programmable to be active-high or active-low. It is shown active-low in Figures 72 and 73. POBE and PIBF may be programmed to be the opposite logic levels shown in the diagram. t53 and t54 apply to the inverted levels as well as those shown.



<sup>\*</sup> Motorola mode signal name.

Figure 74. PHIF Intel or Motorola Mode Signaling (Status Register Read) Timing Diagram

Table 172. Timing Requirements for Intel and Motorola Mode Signaling (Status Register Read)

Abbreviated Reference	Parameter	Min	Max	Unit
t45 <sup>†</sup>	PSTAT to PCSN Setup (valid to low)	6	_	ns
t46 <sup>‡</sup>	PCSN to PSTAT Hold (high to invalid)	0	_	ns
t475 <sup>†</sup>	PBSEL to PCSN Setup (valid to low)	6	_	ns
t48 <sup>‡</sup>	PCSN to PBSEL Hold (high to invalid)	0		ns

<sup>†</sup> t45, t47, and t49 are referenced to the falling edge of PCSN or PODS(PDS), whichever occurs last.

Table 173. Timing Characteristics for Intel and Motorola Mode Signaling (Status Register Read)

Abbreviated Reference	Parameter	Min	Max	Unit
t49 <sup>†</sup>	PCSN to PB Read (low to valid)	_	17	ns
t50 <sup>‡</sup>	PCSN to PB Read Hold (high to invalid)	3	_	ns

<sup>†</sup> t45, t47, and t49 are referenced to the falling edge of PCSN or PODS(PDS), whichever occurs last.

<sup>‡</sup> t46, t48, and t50 are referenced to the rising edge of PCSN or PODS(PDS), whichever occurs first.

<sup>‡</sup> t46, t48, and t50 are referenced to the rising edge of PCSN or PODS(PDS), whichever occurs first.





Figure 75. PHIF, PIBF, and POBE Reset Timing Diagram

Table 174. PHIF Timing Characteristics for PHIF, PIBF, and POBE Reset

Abbreviated Reference	Parameter	Min	Max	Unit
t57	RSTB Disable to POBE/PIBF* (high to valid)	_	25	ns
t58	RSTB Enable to POBE/PIBF* (low to invalid)	3	25	ns

\* After reset, POBE and PIBF always go to the levels shown, indicating output buffer empty and input buffer empty. The DSP program, however, may later invert the definition of the logic levels for POBE and PIBF. t57 and t58 continue to apply.



5-4776 (F)

† POBE and PIBF can be programmed to be active-high or active-low. They are shown active-high. The timing characteristic for active-low is the same as for active-high.


Figure 76. PHIF, PIBF, and POBE Disable Timing Diagram

Table 175. PHIF Timing Characteristics for POBE and PIBF Disable

Abbreviated Reference	Parameter	Min	Max	Unit
t59	CKO to POBE/PIBF Disable (high/low to disable)		20	ns

<sup>\*</sup> POBE and PIBF can be programmed to be active-high or active-low. They are shown active-high. The timing characteristic for active-low is the same as for active-high.

# 12.9 Serial I/O Specifications



<sup>\*</sup> N = 16 or 8 bits.

Figure 77. SIO Passive Mode Input Timing Diagram

**Table 176. Timing Requirements for Serial Inputs** 


Abbreviated Reference	Parameter	Min	Max	Unit
t70	Clock Period (high to high) <sup>‡</sup>	40	t	ns
t71	Clock Low Time (low to high)	18	_	ns
t72	Clock High Time (high to low)	18	_	ns
t73	Load High Setup (high to high)	8	_	ns
t74	Load Low Setup (low to high)	8	_	ns
t75	Load High Hold (high to invalid)	0	_	ns
t77	Data Setup (valid to high)	7	_	ns
t78	Data Hold (high to invalid)	0	_	ns

<sup>†</sup> Device is fully static; t70 is tested at 200 ns.

**Table 177. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t79	IBF Delay (high to high)	_	35	ns

<sup>‡</sup> For multiprocessor mode, see note in Section 12.10.



5-4778 (F)

Figure 78. SIO Active Mode Input Timing Diagram


**Table 178. Timing Requirements for Serial Inputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t77	Data Setup (valid to high)	7	_	ns
t78	Data Hold (high to invalid)	0	_	ns

**Table 179. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t76a	ILD Delay (high to low)	_	35	ns
t101	ILD Hold (high to invalid)	5	_	ns
t79	IBF Delay (high to high)	_	35	ns

<sup>\*</sup> ILD goes high during bit 6 (of 0:15), N = 8 or 16.



See sioc register, MSB field, to determine if B0 is the MSB or LSB. See sioc register, ILEN field, to determine if the DO word length is 8 bits or 16 bits.

Figure 79. SIO Passive Mode Output Timing Diagram

**Table 180. Timing Requirements for Serial Inputs** 


Abbreviated Reference	Parameter	Min	Max	Unit
t80	Clock Period (high to high) <sup>‡</sup>	40	t	ns
t81	Clock Low Time (low to high)	18	_	ns
t82	Clock High Time (high to low)	18	_	ns
t83	Load High Setup (high to high)	8	_	ns
t84	Load Low Setup (low to high)	8		ns
t85	Load Hold (high to invalid)	0	_	ns

<sup>†</sup> Device is fully static; t80 is tested at 200 ns.

**Table 181. Timing Characteristics for Serial Outputs** 

Abbreviated Reference	Parameter	Min	Max	Unit
t87	Data Delay (high to valid)	_	35	ns
t88	Enable Data Delay (low to active)		35	ns
t89	Disable Data Delay (high to 3-state)	_	35	ns
t90	Data Hold (high to invalid)	5	_	ns
t92	Address Delay (high to valid)	_	35	ns
t93	Address Hold (high to invalid)	5	_	ns
t94	Enable Delay (low to active)		35	ns
t95	Disable Delay (high to 3-state)		35	ns
t96	OBE Delay (high to high)		35	ns

<sup>‡</sup> For multiprocessor mode, see note in Section 12.10.




<sup>\*</sup> OLD goes high at the end of bit 6 of 0:15.

Figure 80. SIO Active Mode Output Timing Diagram

**Table 182. Timing Characteristics for Serial Output** 

Abbreviated Reference	Parameter	Min	Max	Unit
t86a	OLD Delay (high to low)	_	35	ns
t102	OLD Hold (high to invalid)	5	_	ns
t87	Data Delay (high to valid)	_	35	ns
t88	Enable Data Delay (low to active)	_	35	ns
t89	Disable Data Delay (high to 3-state)	_	35	ns
t90	Data Hold (high to invalid)	5	_	ns
t92	Address Delay (high to valid)	_	35	ns
t93	Address Hold (high to invalid)	5	_	ns
t94	Enable Delay (low to active)	_	35	ns
t95	Disable Delay (high to 3-state)	_	35	ns
t96	OBE Delay (high to high)	_	35	ns




<sup>\*</sup> See sioc register, LD field.

Figure 81. Serial I/O Active Mode Clock Timing

**Table 183. Timing Characteristics for Signal Generation** 

Abbreviated Reference	Parameter	Min	Max	Unit
t97	ICK Delay (high to high)	_	18	ns
t98	ICK Delay (high to low)	_	18	ns
t99	OCK Delay (high to high)	_	18	ns
t100	OCK Delay (high to low)	_	18	ns
t76a	ILD Delay (high to low)	_	35	ns
t76b	ILD Delay (high to high)	_	35	ns
t101	ILD Hold (high to invalid)	5		ns
t86a	OLD Delay (high to low)	_	35	ns
t86b	OLD Delay (high to high)	_	35	ns
t102	OLD Hold (high to invalid)	5		ns
t103	SYNC Delay (high to low)	_	35	ns
t104	SYNC Delay (high to high)	_	35	ns
t105	SYNC Hold (high to invalid)	5		ns

#### 12.10 Multiprocessor Communication



<sup>\*</sup> Negative edge initiates time slot 0.

Figure 82. SIO Multiprocessor Timing Diagram

**Note:** All serial I/O timing requirements and characteristics still apply, but the minimum clock period in passive multiprocessor mode, assuming 50% duty cycle, is calculated as (t77 + t116) x 2.

Table 184. Timing Requirements for SIO Multiprocessor Communication

Abbreviated Reference	Parameter	Min	Max	Unit
t112	Sync Setup (high/low to high)	35	_	ns
t113	Sync Hold (high to high/low)	0	_	ns
t114	Address Setup (valid to high)	12	_	ns
t115	Address Hold (high to invalid)	0	1	ns

**Table 185. Timing Characteristics for SIO Multiprocessor Communication** 

Abbreviated Reference*	Parameter	Min	Max	Unit
t116	Data Delay (bit 0 only) (low to valid)	_	35	ns
t117	Data Disable Delay (high to 3-state)	_	30	ns
t120	DOEN Valid Delay (high to valid)	_	25	ns
t121	Address Delay (bit 0 only) (low to valid)	_	35	ns
t122	Address Disable Delay (high to 3-state)	_	30	ns


<sup>\*</sup> With capacitance load on ICK, OCK, DO, SYNC, and SADD = 100 pF, add 4 ns to t116—t122.

### 13 Crystal Electrical Characteristics and Requirements

If the option for using the external crystal is chosen, the following electrical characteristics and requirements apply.

#### 13.1 External Components for the Crystal Oscillator

The crystal oscillator is enabled by connecting a crystal across CKI and CKI2, along with one external capacitor from each of these pins to ground (see Figure 83). For most applications, 10 pF external capacitors are recommended; however, larger values allow for better frequency precision (see Section 13.4, Frequency Accuracy Considerations). The crystal should be either fundamental or overtone mode, parallel resonant, with a rated power (drive level) of at least 1 mW, and specified at a load capacitance equal to the total capacitance seen by the crystal (including external capacitors and strays). The series resistance of the crystal should be specified to be less than **half** the absolute value of the negative resistance shown in Figure 84 or Figure 85 for the crystal frequency. The frequency of the signal at the CKI input pin is equal to the crystal frequency.



5-4041 (F).a

Figure 83. Fundamental Crystal Configuration

The following guidelines should be followed when designing the printed-circuit board layout for a crystal-based application:

- Keep crystal and external capacitors as close to CKI and CKI2 pins as possible to minimize board stray capacitance.
- 2. Keep high-frequency digital signals such as CKO away from CKI and CKI2 traces to avoid coupling.

#### 13.2 Power Dissipation

Figures 86 and 87 indicate the typical power dissipation of the on-chip crystal oscillator circuit versus frequency. Note that these curves are intended to show the relative effects of load capacitance on supply current and that the actual supply current measured depends on crystal resistance. For typical crystals, measured supply current at the VDDA pin should be less than that shown in the figures.






Figure 84. Negative Resistance of Crystal Oscillator Circuit,  $V_{DD} = 4.75 \text{ V}$ 

Figure 85. Negative Resistance of Crystal Oscillator Circuit, VDD = 2.7 V



5-5188 (F)

Figure 86. Typical Supply Current of Crystal Oscillator Circuit, VDD = 5.0 V,  $25 \,^{\circ}\text{C}$ 




5-5189 (F)

Figure 87. Typical Supply Current of Crystal Oscillator Circuit,  $VDD = 2.7 \text{ V}, 25 ^{\circ}\text{C}$ 

#### 13.3 LC Network Design for Third Overtone Crystal Circuits

For certain crystal applications, it is cheaper to use a third overtone crystal instead of a fundamental mode crystal. When using third overtone crystals, it is necessary, however, to filter out the fundamental frequency so that the circuit will oscillate only at the third overtone. There are several techniques that will accomplish this; one of these is described below. Figure 88 shows the basic setup for third overtone operation.



5-4043 (F).a

Figure 88. Third Overtone Crystal Configuration

The parallel combination of L1 and C1 forms a resonant circuit with a resonant frequency between the first and third harmonic of the crystal such that the LC network appears inductive at the fundamental frequency and capacitive at the third harmonic. This ensures that a 360° phase shift around the oscillator loop will occur at the third overtone frequency but not at the fundamental. The blocking capacitor, C3, provides dc isolation for the trap circuit and should be chosen to be large compared to C1.

For example, suppose it is desired to operate with a 40 MHz, third overtone, crystal:

Let: f3 = operating frequency of third overtone crystal (40 MHz in this example)

f1 = fundamental frequency of third overtone crystal, or f3/3 (13.3 MHz in this example)

fT = resonant frequency of trap =  $\frac{1}{2\pi\sqrt{L1C1}}$ 

C2 = external load capacitor (10 pF in this example)

C3 = dc blocking capacitor (0.1  $\mu$ F in this example)

Arbitrarily, set trap resonance to geometric mean of f1 and f3. Since f1 = f3/3, the geometric mean would be:

$$fT = \frac{f3}{\sqrt{3}} = \frac{40 \text{ MHz}}{\sqrt{3}} = 23 \text{ MHz}$$

At the third overtone frequency,  $f_3$ , it is desirable to have the net impedance of the trap circuit (X $\tau$ ) equal to the impedance of C2 (XC2), i.e.,

$$XT = XC2 = XC1 \parallel (XC3 + XL1)$$

Selecting C3 so that XC3 << XL1 yields,

$$XT = XC2 = XC1 \parallel XL1$$

For a capacitor,

$$XC = \frac{-j}{\omega C}$$
 where  $\omega = 2\pi f$ 

For an inductor,

$$XL = j\omega L$$

Solving for C<sub>1</sub>, and realizing that L<sub>1</sub>C<sub>1</sub> =  $3/\omega 3^2$  yields,

$$C1 = \frac{3}{2}C2$$

Hence, for  $C_2 = 10$  pF,  $C_1 = 15$  pF. Since the impedance of the trap circuit in this example would be equal to the impedance of a 10 pF capacitor, the negative resistance and supply current curves for  $C_1 = C_2 = 10$  pF at 40 MHz would apply to this example.

Finally, solving for the inductor value,

$$L1 = \frac{1}{4\pi^2 f \Gamma^2 C 1}$$


For the above example,  $L_1$  is 3.2  $\mu$ H.

#### 13.4 Frequency Accuracy Considerations

For frequency accuracy implications of using the PLL, see Section 4.12, Clock Synthesis.

For most applications, clock frequency errors in the hundreds of parts per million can be tolerated with no adverse effects. However, for applications where precise average frequency tolerance on the order of 100 ppm is required, care must be taken in the choice of external components (crystal and capacitors) as well as in the layout of the printed-circuit board. Several factors determine the frequency accuracy of a crystal-based oscillator circuit. Some of these factors are determined by the properties of the crystal itself. Generally, a low-cost, standard crystal will not be sufficient for a high-accuracy application, and a custom crystal must be specified. Most crystal manufacturers provide extensive information concerning the accuracy of their crystals, and an applications engineer from the crystal vendor should be consulted prior to specifying a crystal for a given application.

In addition to absolute, temperature, and aging tolerances of a crystal, the operating frequency of a crystal is also determined by the total load capacitance seen by the crystal. When ordering a crystal from a vendor, it is necessary to specify a load capacitance at which the operating frequency of the crystal will be measured. Variations in this load capacitance due to temperature and manufacturing variations will cause variations in the operating frequency of the oscillator. Figure 89 illustrates some of the sources of this variation.



5-4045 (F).a

Notes:

Cext = External load capacitor (one each required for CKI and CKI2).

CD = Parasitic capacitance of the DSP1627 itself.

 $C_B$  = Parasitic capacitance of the printed-wiring board.

Co = Parasitic capacitance of crystal (not part of CL but still a source of frequency variation).

Figure 89. Components of Load Capacitance for Crystal Oscillator

The load capacitance, CL, must be specified to the crystal vendor. The crystal manufacturer will cut the crystal so that the frequency of oscillation will be correct when the crystal sees this load capacitance. Note that CL refers to a capacitance seen across the crystal leads, meaning that for the circuit shown in Figure 89, CL is the series combination of the two external capacitors (Cext/2) plus the equivalent board and device strays (CB/2 + CD/2). For example, if 10 pF external capacitors were used and parasitic capacitance is neglected, then the crystal should be specified for a load capacitance of 5 pF. If the load capacitance deviates from this value due to the tolerance on the external capacitors or the presence of strays, then the frequency will also deviate. This change in frequency as function of load capacitance is known as pullability and is expressed in units of ppm/pF. For small deviations of a few pF, pullability can be determined by the equation below:

pullability (ppm/pF) = 
$$\frac{(C1)(10^6)}{2(C0 + CL)^2}$$

where  $C_0$  = parasitic capacitance of crystal in pF.

C1 = motional capacitance of crystal in pF (usually between 1 fF to 25 fF, value available from crystal vendor).

CL = total load capacitance in pF seen by crystal.

Note that for a given crystal, the pullability can be reduced, and, hence, the frequency stability improved, by making CL as large as possible while still maintaining sufficient negative resistance to ensure start-up per the curves shown in Figures 86 and 87.

Since it is not possible to know the exact values of the parasitic capacitance in a crystal-based oscillator system, the external capacitors are usually selected empirically to null out the frequency offset on a typical prototype board. Thus, if a crystal is specified to operate with a load capacitance of 10 pF, the external capacitors would have to be made slightly less than 20 pF each in order to account for strays. Suppose, for instance, that a crystal for which CL = 10 pF is specified is plugged into the system and it is determined empirical that the best frequency accuracy occurs with Cext = 18 pF. This would mean that the equivalent board and device strays from each leac to ground would be 2 pF.

As an example, suppose it is desired to design a 23 MHz, 3.3 V system with ±100 ppm frequency accuracy. The parameters for a typical high-accuracy, custom, 23 MHz fundamental mode crystal are as follows:

In order to ensure oscillator start-up, the negative resistance of the oscillator with load and parasitic capacitance must be at least twice the series resistance of the crystal, or 40  $\Omega$ . Interpolating from Figure 89, external capacitors plus strays can be made as large as 30 pF while still achieving 40  $\Omega$  of negative resistance. Assume for this example that external capacitors are chosen so that the total load capacitance including strays is 30 pF per lead, or 15 pF total. Thus, a load capacitance, CL = 15 pF would be specified to the crystal manufacturer.

From the above equation, the pullability would be calculated as follows:

pullability = 
$$\frac{(C1)(10^6)}{2(C0 + CL)^2} = \frac{(0.015)(10^6)}{2(7 + 15)^2} = 15.5 \text{ ppm/pF}$$

If 2% external capacitors are used, the frequency deviation due to capacitor tolerance is equal to:

$$(0.02)(15 pF)(15.5 ppm/pF) = 4.7 ppm$$

**Note:** To simplify analysis, Cext is considered to be 30 pF. In practice, it would be slightly less than this value to account for strays. Also, temperature and aging tolerances on the capacitors have been neglected.

Typical capacitance variation of the oscillator circuit in the DSP1627 itself across process, temperature, and supply voltage is  $\pm 1$  pF. Thus, the expected frequency variation due to the DSP1627 is:

$$(1 pF)(15.5 ppm/pF) = 15.5 ppm$$

Approximate variation in parasitic capacitance of crystal =  $\pm 0.5$  pF.

Frequency shift due to variation in C0 = (0.5 pF)(15.5 ppm/pF) = 7.75 ppm

Approximate variation in parasitic capacitance of printed-circuit board =  $\pm 1.5$  pF.

Frequency shift due to variation in board capacitance = (1.5 pF)(15.5 ppm/pF) = 23.25 ppm

Thus, the contributions to frequency variation add up as follows:


Initial Tolerance of Crystal 10.0 ppm 25.0 Temperature Tolerance of Crystal Aging Tolerance of Crystal 6.0 4.7 **Load Capacitor Variation** DSP1627 Circuit Variation1 5.5 C<sub>0</sub> Variation 7.8 **Board Variation** 23.3 Total 92.3 ppm

This type of detailed analysis should be performed for any crystal-based application where frequency accuracy is critical.

# **14 Outline Diagrams**

## 14.1 100-Pin BQFP (Bumpered Quad Flat Pack)

All dimensions are in millimeters.





5-1970 (F)r.10

# 14 Outline Diagrams (continued)

# 14.2 100-Pin TQFP (Thin Quad Flat Pack)

All dimensions are in millimeters.





For additional information, contact your Microelectronics Group Account Manager or the following:

INTERNET: http://www.lucent.com/micro E-MAIL: docmaster@micro.lucent.com

N. AMERICA: Microelectronics Group, Lucent Technologies Inc., 555 Union Boulevard, Room 30L-15P-BA, Allentown, PA 18103

1-800-372-2447, FAX 610-712-4106 (In CANADA: 1-800-553-2448, FAX 610-712-4106)

ASIA PACIFIC: Microelectronics Group, Lucent Technologies Singapore Pte. Ltd., 77 Science Park Drive, #03-18 Cintech III, Singapore 118256

Tel. (65) 778 8833, FAX (65) 777 7495

Microeléctronics Group, Lucent Technologies (China) Co., Ltd., A-F2, 23/F, Zao Fong Universe Building, 1800 Zhong Shan Xi Road, Shanghai CHINA:

200233 P. R. China Tel. (86) 21 6440 0468, ext. 316, FAX (86) 21 6440 0652

JAPAN: Microelectronics Group, Lucent Technologies Japan Ltd., 7-18, Higashi-Gotanda 2-chome, Shinagawa-ku, Tokyo 141, Japan

Tel. (81) 3 5421 1600, FAX (81) 3 5421 1700

EUROPE: Data Requests: MICROELECTRONICS GROUP DATALINE: Tel. (44) 7000 582 368, FAX (44) 1189 328 148

Technical Inquiries:GERMANY: (49) 89 95086 0 (Munich), UNITED KINGDOM: (44) 1344 865 900 (Ascot), FRANCE: (33) 1 40 83 68 00 (Paris), SWEDEN: (46) 8 594 607 00 (Stockholm), FINLAND: (358) 9 4354 2800 (Helsinki),

ITALY: (39) 02 6608131 (Milan), SPAIN: (34) 1 807 1441 (Madrid)

Lucent Technologies Inc. reserves the right to make changes to the product(s) or information contained herein without notice. No liability is assumed as a result of their use or application. No rights under any patent accompany the sale of any such product(s) or information.

Copyright © 2000 Lucent Technologies Inc. All Rights Reserved

**Lucent Technologies**